

The New Normal – Planning for Sediment Project Water Management Considering Climate Change



Cannon Silver, PE

**CDM
Smith**


SAME

 **DCHWS**
Design and Construction Issues at Hazardous Waste Sites

OCTOBER 26-28, 2020

Remedial Action Objectives

- Tidally influenced creek and estuary contaminated with PCBs, PAHs, metals
 - Situated between residential and industrial areas
- Reduce risks from stream sediment



Remedy Action



- Remedy selected with community input
- Remove 14,000 cubic yards of contaminated sediment via “excavation in the dry”
 - Bypass pump-around system and series of cofferdams to create dry working conditions
 - Water treatment system required to treat contact water
- Followed by 1.2-acre floodplain reconstruction and 2.5-acre wetland restoration

Design Analysis

- Design based on state regulatory requirements
 - Required sufficient capacity to convey 2-year flows (24-hour precipitation event)
- CDM Smith served role of owner's representative during design and construction
 - Coordinated "Failure Modes and Effects Analysis" during 60% design
 - Among 96 potential risks, two identified related to:
 - **uncommon weather conditions or large storm event**
 - **failure of cofferdam, or bypass pump-around system**
 - Potential effects identified:
 - Flooding, inundation of work area; more contact water to collect, store and treat; possible recontamination
 - Recommended actions:
 - Develop a contingency plan for handling storm bigger than design
 - Incorporate safety factor into the design



Bypass Pump Around System



- State regulations required sufficient capacity to convey 2-year (24-hour precipitation event) flows
 - Equates to 3.3 inches precipitation, or 20 cubic feet per second [cfs]
- Pumping equipment **over-designed** to handle 10-year storm
 - Added redundant pumping system to accommodate total of 5.1 inches precipitation, or 30 cfs

Dam System

- Dams used in conjunction with bypass pump-around system to create dry working conditions
- Dam heights designed for **2-year flow event**
 - Included 1-foot freeboard



Dam System



Water Treatment System



- Frac tank, sand filter unit, bag filters and 5000-lbs of activated carbon filters
- Design capacity 300 gallons per minute
 - <1 cfs

Project Challenges – Storm Events; Dam Overtopping and Failure

Storm Events Encountered

- July 28 and 29, 2017
 - 5.7 inches of rain overnight
 - Storm approached and possibly exceeded 24-hour, 25-year flow event
 - Dam at station 10+00 overtopped and dam at station 19+00 breached
- August 18, 2017
 - 1.5 inches of rain in 1-hour
 - Storm exceeded 60-minute, 2-year flow event
 - Dam at station 10+00 overtopped
- August 21, 2017
 - 1.75 inches of rain in 2-hours
 - Storm exceeded 2-hour, 2-year flow event
 - Dam at station 10+00 overtopped
- Design (with safety factor)
 - 10-year flow event (24-hours)
 - equivalent to 5.1 inches of precipitation in 24-hours
 - ~0.2 inches/hr

Dam Overtopping and Breaches



Consequences

- Released untreated contact water downstream of the work area
- Schedule delayed due to inundation of the work areas
- Overwhelmed the water treatment system due to the need to treat significantly more contact water than planned




Dewatered creek early July 2017



Dewatered creek inundated with water on 7/29/2017

Corrective Action

- Constructed additional dams and impoundments
- Reinforced by installing sheet piles
- Optimized the water treatment system



Project Challenges – Bladder Dam Failure



OCTOBER 26-28, 2020

Bladder Dam Failure

- Bladder dam installed August 25, 2017
- Bladder dam breached on November 10, 2017 by creek water channeling under the dam from the downstream side, flooding the upstream segment




Consequences/ Corrective Action

Consequences

- Schedule delays due to inundation of the work areas
- Operation of the water treatment system problematic due to need to treat significantly more contact water than planned
- Release of untreated contact water downstream of the work area

Corrective Action

- Multiple repair attempts
- Repair completed by placing an impermeable liner and 800 tons of sand upstream and downstream of the dam
- Large volume of contact water in excavation area treated prior to completing excavation activities



Project Completion

- Corrective actions sufficient for completion of excavation and restoration efforts
- Following excavation, creek reconstructed and restored
- Restoration included:
 - Floodplain reconstruction
 - Wetland restoration
 - Slope stabilization
 - Restoration of submerged vegetation



Lessons Learned

- Failure modes should be considered during design process and during construction preparation
- Design based on regulatory requirements, even with 50% safety factor, proved insufficient for storm events that occurred during construction
 - As part of the design process, future projects should consider increased frequency and increased intensity of storms that may be a result of climate change
- Contingency plans for failure modes should be developed **prior** to construction
- Unintended consequences of design changes **must** be fully considered