

Long-Term Groundwater  
Monitoring Optimization  
Clare Water Supply Superfund Site  
Permeable Reactive Barrier and  
Soil Remedy Areas  
Clare, Michigan



Solid Waste and  
Emergency Response  
(5203P)

EPA 542-R-07-010  
August 2007  
[www.epa.gov](http://www.epa.gov)

Long-Term Groundwater  
Monitoring Optimization  
Clare Water Supply Superfund Site  
Permeable Reactive Barrier and  
Soil Remedy Areas  
Clare, Michigan

### Notice and Disclaimer

Work described herein was performed by GSI Environmental, Inc., Houston, TX, for the U.S. Environmental Protection Agency (U.S. EPA) and Parsons, Inc., Denver CO, for the U.S. Army Corps of Engineers (USACE). It has undergone technical review by EPA and USACE. Work conducted by GSI Environmental, Inc., including preparation of this report, was performed under EPA contract 68-W-03-038 to Environmental Management Support, Inc., Silver Spring, Maryland. Work conducted by Parsons, Inc., was performed under USACE Purchase Order W9128F-05-P-0041. Reference to any trade names, commercial products, process, or service does not constitute or imply endorsement, recommendation for use, or favoring by the U. S. EPA, USACE, or any other agency of the United States Government. The views and opinions of the authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof. For further information, contact

Kathy Yager  
U.S. EPA/OSRTI  
617-918-8362  
yager.kathleen@epa.gov

Kirby Biggs  
EPA/OSRTI  
703-299-3438  
biggs.kirby@epa.gov.

A PDF version of this report is available for viewing or downloading from EPA's Hazardous Waste Cleanup Information (Clu-In) website at <http://clu-in.org/optimization> by clicking on "Application" and then "Long-Term Monitoring." PDF copies also are available on the Federal Remediation Technologies Roundtable website at <http://www.frtr.gov/optimization/monitoring.htm>.

## Table of Contents

1.0	Project Objectives .....	1
2.0	Site Background Information .....	2
2.1	PRB Area.....	2
2.2	Soil Remedy Area.....	3
3.0	Methods.....	4
3.1	Qualitative Evaluation.....	4
3.2	MAROS Statistical Methods .....	5
3.3	Data Input, Consolidation, and Site Assumptions .....	5
4.0	PRB Area Results .....	6
4.1	Qualitative Review for the PRB Area.....	6
4.2	MAROS Statistical Review for the PRB Area .....	10
4.3	Recommendations for the PRB Area .....	11
5.0	Soil Remedy Area Results .....	12
5.1	Qualitative Review for the Soil Remedy Area.....	12
5.2	MAROS Statistical Review for the Soil Remedy Area .....	14
5.3	Recommendations for the Soil Remedy Area .....	15
6.0	Long-Term Monitoring Program Flexibility .....	16
7.0	References Cited.....	16

### Tables

Table 1	Summary of Site-Wide Long-Term Groundwater Monitoring Plan
Table 2	Aquifer Input Parameters
Table 3	Qualitative Evaluation of PRB Area Groundwater Monitoring Network
Table 4	Well Trend Summary Results For PRB Area: 1999-2006
Table 5	Well Redundancy Analysis Summary Results For PRB Area
Table 6	Final Recommended Groundwater Monitoring Network For PRB Area
Table 7	Qualitative Evaluation of Soil Remedy Area Groundwater Monitoring Network
Table 8	Well Trend Summary Results For Soil Remedy Area: 1999-2006
Table 9	Final Recommended Groundwater Monitoring Network For Soil Remedy Area

### Figures

Figure 1	Groundwater Monitoring Locations: PRB and Soil Remedy Areas
Figure 2a	Approximate Well Screen Intervals for PRB Area
Figure 2b	Approximate Well Screen Intervals for Soil Remedy Area
Figure 3	Qualitative Evaluation Results for PRB Area
Figure 4	Temporal Trend Results: Vinyl Chloride PRB Area
Figure 5	Well Sufficiency Vinyl Chloride PRB Area
Figure 6	Final Recommended Monitoring Network PRB Area
Figure 7	Qualitative Evaluation Results for Soil Remedy Area
Figure 8	Temporal Trend Results: TCE Soil Remedy Area
Figure 9	Final Recommended Monitoring Network Soil Remedy Area

### Attachments

A:	Geologic Cross-Sections
B:	MAROS 2.2 Methodology
C:	MAROS Reports
D:	Electronic Database (on CD)
E:	Selected November 2006 Data
F:	Review Comments and Responses

## LIST OF ACRONYMS AND ABBREVIATIONS

µg/L	microgram(s) per liter
bgs	below ground surface
<i>cis</i> -1,2-DCE	<i>cis</i> -1,2-dichloroethene
cm/sec	centimeters per second
COCs	constituents of concern
CUO	cleanup objective
DCE	dichloroethene
DO	dissolved oxygen
DPE	dual-phase extraction
FS	Feasibility Study
ft amsl	feet above mean sea level
ft/day	feet per day
GSI	Groundwater Services, Inc.
LTM	long-term monitoring
MAROS	Monitoring and Remediation Optimization System software
MCES	Modified Cost Effective Sampling
MCL	Maximum Contaminant Level
mg/L	milligram(s) per liter
MNA	monitored natural attenuation
MNO	monitoring network optimization
ORP	oxidation-reduction potential
Parsons	Parsons Infrastructure and Technology Group, Inc.
PCE	tetrachloroethene
PRB	Permeable Reactive Barrier
Progressive	Progressive Engineering & Construction, Inc.
RI	Remedial Investigation
ROD	Record of Decision
TAL	target analyte list
TCE	trichloroethene
USEPA	United States Environmental Protection Agency
VC	vinyl chloride
VOCs	volatile organic compounds

## **GROUNDWATER MONITORING NETWORK OPTIMIZATION PRB AND SOIL REMEDY AREAS**

### **CLARE WATER SUPPLY SUPERFUND SITE**

The following memorandum contains a review of the long-term groundwater monitoring network for the Permeable Reactive Barrier (PRB) and Soil Remedy Areas at the Clare Water Supply Superfund Site in Clare, Michigan. The review was a joint effort performed by Groundwater Services, Inc. (GSI) of Houston, Texas and Parsons Infrastructure and Technology Group, Inc. (Parsons) of Denver, Colorado. The current monitoring network in each area was evaluated using a formal qualitative approach (performed by Parsons) and statistical tools found in the Monitoring and Remediation Optimization System software (MAROS) (performed by GSI). Following performance of the qualitative and quantitative evaluations, Parsons and GSI collaborated to derive final recommendations for the groundwater monitoring networks using the results of the qualitative and quantitative evaluations.

Recommendations are made for groundwater sampling frequency and location based on available data pertaining to current hydrogeologic and contaminant conditions. The report evaluates the PRB Area and Soil Remedy Area monitoring networks using analytical data obtained from Progressive Engineering & Construction, Inc. (Progressive). PRB Area data extended from March 1994 to May 2006, although most wells only had data extending from May 2005 to May 2006. Soil Remedy Area data extended from June 1988 to May 2006, although most wells only had data for the period from March 1999 to May 2006. Additional data for the PRB and Soil Remedy Areas collected in November 2006 were received after the monitoring network optimization (MNO) evaluation had been completed. These data were qualitatively reviewed to assess any impacts on MNO recommendations, but were not formally incorporated into the complete evaluation described in this report. The November 2006 sampling results are provided in Attachment E.

#### **1.0 Project Objectives**

The goal of the monitoring network optimization (MNO) evaluation for the PRB and Soil Remedy Areas is to design monitoring programs that are cost and time efficient as well as protective of potential receptors. The monitoring program should provide sufficient data to support site management decisions. The evaluation focuses on the following objectives:

- Evaluate well locations and screened intervals within the context of the hydrogeologic regime to determine if they meet site characterization and decision support objectives. Identify possible data gaps.
- Evaluate overall plume stability qualitatively and through trend and moment analysis.
- Evaluate individual well concentration trends over time for target constituents of concern (COCs) both qualitatively and statistically.
- Develop sampling location and frequency recommendations based on both qualitative and quantitative statistical analysis results.

## 2.0 Site Background Information

Site background information was primarily obtained from 1) the *2005 Annual Monitoring Report* for the Clare Water Supply Superfund Site (Progressive, 2006), 2) personal communications with Progressive personnel, and 3) the draft five-year review report prepared in 2006 (USEPA, 2006). The five-year review report states that the site soils create two different hydrologic regimes within the investigation area. The first hydraulic regime consists of a perched water zone created by the low-permeability clay/till unit(s) in the western half of the site (where the PRB and Soil Remedy Areas are located). The second is created by aquifer sand underlying till. The aquifer is 20 to 40 feet thick in a sand unit beginning at 30 to 40 feet below the ground surface. In the western, industrialized portion of the site, 30 to 40 feet of clay and glacial till overlie the aquifer. The inferred goals of the groundwater monitoring program at these two areas are to:

- Determine the combined impact of engineered remedial measures and natural attenuation on concentrations of priority chlorinated constituents dissolved in groundwater; and
- Ensure that groundwater contamination is not posing unacceptable risks to potential receptors.

### 2.1 PRB Area

The PRB groundwater remedy consists of two PRBs in sequence that were installed to a depth of 17 feet below ground surface (bgs) along the property boundary of the former Mitchell source area in December 2004 (see Figure 1). The PRBs are designed to treat shallow groundwater contaminated with chlorinated volatile organic compounds (VOCs) as it migrates through the treatment walls. They are reportedly filled with iron-encrusted foundry sand.

The uppermost 8 to 23 feet of the soil column in the vicinity of the PRBs consists of sand backfill material (filling a former contaminated soil excavation) having a hydraulic conductivity of approximately  $1 \times 10^{-4}$  centimeters per second (cm/sec). The water table is present within 5 feet of the ground surface. The sand is underlain and encased laterally by low-permeability native material having a hydraulic conductivity of approximately  $1 \times 10^{-7}$  to  $5 \times 10^{-7}$  cm/sec (see cross sections from Progressive in Attachment A). The shallow groundwater flow direction is inferred to be south to southeast, across the PRBs, based on hydraulic potential data. The groundwater flow direction in the deep zone appears to range from north to east in the vicinity of the PRB Area, based on potentiometric surface maps contained in the *2005 Annual Monitoring Report* (Progressive, 2006). A representative groundwater seepage velocity for the site provided by Progressive is 0.27 foot per day (ft/day) based on data contained in a Secor (November 2004) design report. According to Progressive, this seepage velocity is more representative of the sand backfill than of the surrounding native materials, which have a relatively low permeability.

According to Progressive, the recent and historical hydraulic data suggest a perched water table in the vicinity of the PRB and Soil Remedy Areas. The remedial investigation (RI) and feasibility study (FS) concluded that lateral flow in the perched water-bearing zone is possible in some areas, but is likely limited due to seasonal water table changes, and vertical flow is possible through assumed (but not verified) desiccation cracks in the glacial till.

March 22, 2007

A drainage channel (the U.S. 10 Drainage Ditch) is located immediately south (downgradient) of the PRB Area. The drainage ditch empties into a small wetlands area which directly recharges the aquifer in the vicinity of water supply wells MW2 and MW5 (USEPA, 2006). According to Lithologic Cross Section A-A', transmitted by Progressive and contained in Attachment A, this ditch is approximately 7 to 8 feet deep with a bottom elevation of approximately 835 to 836 feet above mean sea level (ft amsl). However, a review comment for the draft report submitted by Progressive indicates that the ditch is only 2 to 3 feet deep with a bottom elevation of approximately 840 ft amsl. Assuming that Progressive is referring to the same ditch, this discrepancy should be reviewed and the actual depth of the ditch should be confirmed. Given the shallow depth to groundwater in the perched zone, it is possible that some groundwater discharge to this ditch occurs if it is indeed 7 to 8 feet deep. Progressive reports that the channel is only seasonally wetted, with minimal flow, and even if PRB Area groundwater discharges to the swale, sampling data indicate that it poses no unacceptable risk to the downstream wetland area or to the water supply wells themselves. Therefore, Progressive reports that there are no significant receptor impacts related to PRB Area groundwater. The clean-up objective (CUO) for this area is the Michigan ground to surface water criterion for VC (15 micrograms per liter [ $\mu\text{g/L}$ ]), as opposed to the US Environmental Protection Agency (USEPA) maximum contaminant level (MCL) of 2  $\mu\text{g/L}$ . However, if groundwater in the vicinity of the PRB is found to be in communication with the deeper aquifer used for municipal water supplies, the MCL would apply.

## 2.2 Soil Remedy Area

Soil from the former Mitchell and ExCello properties was placed on the existing land surface beneath an engineered cap within the former ExCello property. A slurry wall was installed around the cap, and a dual-phase extraction (DPE) system was installed to treat vapor and groundwater removed from the contained area. The soil remedy was constructed in 1999, and the DPE system began operating in April 1999. The DPE system continues to operate on a cyclic basis, with treated water discharged to the local wastewater treatment plant.

The area on which the excavated soils were stockpiled was not excavated, but did contain soils with high concentrations of contaminants to depths up to about 15 to 28 feet bgs. No liner exists beneath the emplaced soils. The cap overlying the emplaced soils (from surface downward) consists of 1) vegetative cover, 2) a geonet underlain by a minimum 2-foot-thick soil cover, and 3) a low-density polyethylene 40-mil membrane liner. The native soils at the original land surface consist of silty sand underlain by low permeability clay and then low permeability till at varying depths. Geologic cross-sections created by Secor in 2005 and transmitted by Progressive are contained in Attachment A. The DPE wells are 30 feet deep and extend to beneath the silty sand/clay interface. The water table in the shallow wells installed north of the soil remedy cell (DMW-1S, -2S, and -3S) in May and November 2005 ranged from approximately 8 to 13 feet bgs, a few feet below the bottom of the emplaced soils and near the top of the native clay and glacial till.

The slurry wall surrounds the entire cap and reportedly varies in depth from about 14 to 22 feet bgs (deeper to the north); it extends a minimum of two feet beneath the clay/till interface. The permeability of the slurry wall (per the design) was to be less than  $1 \times 10^{-7}$  cm/sec. Per the RI report the average hydraulic conductivities are as follows: till  $10^{-7}$  cm/sec, clay  $10^{-7}$  cm/sec, silty sand  $10^{-3}$  cm/sec, and clayey sand  $10^{-5}$  cm/sec. The cap/slurry wall does not contain all of the area of soil impacts originally defined at Ex-



Cello; the area north of the cap close to US10 could not be excavated due to utilities/sewers and right of way issues – some impacts remained in place near DMW-1S, 2S, and 3S. Also, one of the DPE wells (EW-13) is located outside the slurry wall to the south, potentially due to the presence of impacted soils that were left in place, although the reason is not known with certainty. According to Progressive, there are no potential receptors for the Soil Remedy Area groundwater.

The groundwater seepage velocity outside of the soil treatment cell, obtained from Progressive, is  $2.9 \times 10^{-5}$  foot per day (0.01 foot per year). This velocity is based on the calculated seepage velocity for the vicinity of groundwater extraction well PRP-1 using a hydraulic conductivity of  $2.67 \times 10^{-7}$  cm/sec reported in the RI report (Dames & Moore, 1990). Based on the author's professional judgment and experience, this velocity is likely biased low, and the actual average seepage velocity at the site is likely substantially higher.

### 3.0 Methods

Evaluation of the groundwater monitoring networks in the vicinity of the PRB and Soil Remedy Areas consisted of both qualitative evaluation of site analytical data and hydrogeologic conditions and a quantitative, statistical evaluation of site analytical data. These two methods were combined to recommend a final groundwater monitoring strategy to support site monitoring objectives.

#### 3.1 Qualitative Evaluation

Multiple factors were considered in developing recommendations for continuation or cessation of groundwater monitoring at each well. In some cases, a recommendation was made to continue monitoring a particular well, but at a reduced frequency. A recommendation to discontinue groundwater quality monitoring at a particular well based on the information reviewed does not necessarily constitute a recommendation to physically abandon the well. A change in site conditions might warrant resumption of monitoring at some time in the future at wells that are not currently recommended for continued sampling. In general, continuation of water level measurements in all site wells to facilitate groundwater flow direction and hydraulic gradient evaluation is recommended. Typical factors considered in developing recommendations to retain a well in, or remove a well from, a long-term monitoring (LTM) program are summarized in the table below.

REASONS FOR RETAINING A WELL IN MONITORING NETWORK	REASONS FOR REMOVING A WELL FROM MONITORING NETWORK
Well is needed to further characterize the site or monitor changes in contaminant concentrations through time	Well provides spatially redundant information with a neighboring well (e.g., same constituents, and/or short distance between wells)
Well is important for defining the lateral or vertical extent of contaminants	Well has been dry for more than two years <sup>a/</sup>
Well is needed to monitor water quality at a compliance or receptor exposure point (e.g., water supply well)	Contaminant concentrations are consistently below laboratory detection limits or cleanup goals
Well is important for defining background water quality	Well is completed in same water-bearing zone as nearby well(s)

a/ Periodic water-level monitoring should be performed in dry wells to confirm that the upper boundary of the saturated zone remains below the well screen. If the well becomes re-wetted, then its inclusion in the monitoring program should be evaluated.

Once the decision has been made to retain a well in the network, data are reviewed to determine a sampling frequency supportive of site monitoring objectives. Typical factors considered in developing recommendations for monitoring frequency are summarized below.

<b>REASONS FOR INCREASING SAMPLING FREQUENCY</b>	<b>REASONS FOR DECREASING SAMPLING FREQUENCY</b>
Groundwater velocity is high	Groundwater velocity is low
Change in contaminant concentration would significantly alter a decision or course of action	Change in contaminant concentration would not significantly alter a decision or course of action
Well is necessary to monitor source area or operating remedial system	Well is distal from source area and remedial system
Cannot predict if concentrations will change significantly over time, or recent significant increasing trend in contaminant concentrations at a monitoring location resulting in concentrations approaching or exceeding a cleanup goal, possibly indicating plume expansion	Concentrations are not expected to change significantly over time, or contaminant levels have been below groundwater cleanup objectives for some prescribed period of time

### 3.2 *MAROS Statistical Methods*

Statistical methods in the MAROS 2.2 software were used along with the qualitative evaluation of the network to evaluate concentration trends, concentration stability, and spatial uncertainty in the PRB and Soil Remedy Areas. MAROS is a collection of tools in one software package that is used in an explanatory, non-linear but linked fashion to statistically evaluate groundwater monitoring programs. The software includes individual well trend and plume stability analysis tools, spatial statistics, and empirical relationships to assist the user in improving a groundwater monitoring network system. Results generated from the software tool were used to develop lines of evidence, which, in combination with results of the qualitative analysis, were used to recommend an optimized monitoring network for the PRB and Soil Remedy Areas. A description of each tool used in the MAROS software is provided as Attachment B. For a detailed description of the structure of the software and further utilities, refer to the MAROS 2.2 Manual (AFCEE, 2003; <http://www.gsi-net.com/software/maros/Maros.htm>) and Aziz et al., 2003.

### 3.3 *Data Input, Consolidation, and Site Assumptions*

Data for the PRB and Soil Remedy Areas were supplied by Progressive, supplemented with information from historic site reports. Chemical analytical data were organized by Progressive in a database, from which summary statistics were calculated. It should be noted that the dataset transmitted by Progressive was not complete in that not all historical analytical data collected for site wells were included. A complete set of historical analytical results was not available to Progressive when they assumed responsibility for site monitoring. Specifically, data for VC and tetrachloroethene (PCE)

collected prior to May 2005 were not included for most wells. This evaluation assumed that the missing data were generally non-detect; however, this should be confirmed to the extent practical and feasible before final changes to the LTM program are made. Wells and sampling frequencies in the current groundwater monitoring program are shown in Table 1. Each of the wells listed in Table 1 was considered in the qualitative evaluation. Data for 18 wells at the PRB Area (all wells listed in Table 1 except SW-11) and 9 wells at the Soil Remedy Area (all wells listed in Table 1 except EW-series wells) were used in the quantitative (MAROS) analysis.

The monitoring wells in each area are grouped into shallow, intermediate, and deep categories based on their screen intervals in the underlying aquifer. Screened intervals for wells at the PRB and Soil Remedy Areas are illustrated on Figures 2 and 3, respectively. All but four of the wells at the PRB area are screened in the shallow zone near the water table, with the remaining wells assigned to the intermediate (1 well) and deep (3 wells) zones. In the Soil Remedy Area, the monitoring wells are primarily shallow (4 wells) or deep (4 wells), while the dual-phase extraction wells are classified as intermediate-depth. For both the PRB and Soil Remedy Areas shallow and intermediate groundwater zones were considered together as one two-dimensional slice for the quantitative evaluation (MAROS). The deep zone was considered separate from the shallow/intermediate zone. For the qualitative evaluation, the zones were viewed as largely independent.

A list of aquifer physical parameters assumed for the analysis is shown in Table 2. Two screening levels were identified for concentrations of VC in groundwater at the PRB Area. The draft 5-year review report for the Clare Superfund Site prepared by the USEPA (2006) states that The goal of the PRB installation *“was to degrade Vinyl Chloride within the groundwater to levels below the Michigan Part 201 Ground Water/Surface Water Interface (GSI) standards or below 15 µg/l before it discharged into the drainage ditch or otherwise migrates off the former Mitchell facility property and enters the water supply aquifer.”* Therefore, a CUO for VC of 0.015 milligrams per liter (mg/L) was assumed, while the USEPA MCL for VC of 0.002 mg/L was used as a general screening level for water quality in the aquifer. The USEPA MCL for trichloroethene (TCE) of 0.005 mg/L was used as a general screening level for water quality in the Soil Remedy Area, where TCE is the primary COC. Groundwater seepage velocities obtained from Progressive and discussed in Section 2.0 were used. Groundwater flow directions were inferred from potentiometric surface elevation data contained in the 2005 annual monitoring report (Progressive, 2006).

#### **4.0 PRB Area Results**

The qualitative and quantitative evaluation results are discussed in the following subsections.

##### **4.1 Qualitative Review for the PRB Area**

- Details of the qualitative evaluation are shown on Figure 4 and Table 3. Wells recommended to be retained in the monitoring program were those that best defined the magnitude and extent of the plume and indicated the VOC removal effectiveness of the PRBs.
- Most of the monitoring wells present at the PRB Area were sampled quarterly from May 2005 to May 2006 (total of five events). After May 2006, the sampling frequency for these wells was reduced to semiannual, with the next event

occurring in November 2006. These wells include 300A and MW-301 through MW-313. Wells 220, 300B, and 300C have been sampled semiannually and were not sampled quarterly from May 2006 to May 2006.

- A total of five wells were recommended for exclusion from the monitoring program because the qualitative evaluation determined that additional sampling would not provide useful information. A reduction in the sampling frequency was recommended for an additional two wells (MW-312 and MW-313). The rationale for the sampling frequency reductions is provided on a well-specific basis in Table 3.
- In general, a semiannual sampling frequency for most wells is recommended because 1) at least six monitoring events have been performed at each well as of November 2006, including five quarterly sampling events for the most recently installed wells (MW-301 through MW-313), providing a baseline to assess temporal trends and observe any seasonal variations in concentrations; 2) increasing concentration trends were not observed for most wells; 3) reducing sampling frequency would not endanger potential receptors based on available information; and 4) semiannual monitoring will still provide sufficient data to assess the effectiveness of the PRBs and determine temporal trends qualitatively and/or statistically.
- The available data indicate a high degree of vertical variation in contaminant concentrations over short distances at some locations, even within what is identified as sand backfill material on Cross-Sections A-A' and B-B' provided by Progressive (see Attachment A). For example, total combined concentrations of TCE+*cis*-1,2-dichloroethene (DCE)+VC at vertical profiling borehole VAS-301 (Figure 3) varied from 2 µg/L at 8 to 10.5 feet bgs to 2,040 µg/L at 10.5 to 13 feet bgs, a total vertical distance of only five feet. Similarly, VC concentrations at VAS-302 decreased by an order of magnitude from 870 µg/L from 7.5 to 10 feet bgs to 90 µg/L from 10 to 12.5 feet bgs. It appears that the vertical profiling data were used to select well screen intervals. However, the groundwater quality data obtained from the subsequently-installed wells at the same location sometimes vary significantly in magnitude from the vertical profiling data. For example, the VC concentration in MW-302 in May 2005 was 99 µg/L, compared to vertical profiling concentrations in the same depth interval of 1,010 to 1,700 µg/L in VAS-301 (January 2005). Therefore, the wells may not always be accurate indicators of maximum VOC concentrations present in the shallow aquifer. The only way to achieve better resolution would be to have multiple short, discrete screens at various depths at a given location.
- The target analyte list (TAL) for the PRB area includes VOCs (SW8260B) and selected field parameters (pH, conductivity, temperature, turbidity, dissolved oxygen [DO], oxidation-reduction potential [ORP], and ferrous iron). In addition, samples from six wells are analyzed for Michigan 10 metals. With the exception of Michigan 10 metals and ferrous iron, this TAL is reasonably optimized. However, the following recommendations are offered:
  - Discuss optimizing the target VOC list to a short-list of key contaminants of concern (e.g., chlorinated ethenes) with the analytical laboratory. Potential advantages include lower laboratory analytical costs and lower data management/validation/reporting costs. However, all constituents targeted for

analysis should be entered into the site database for each sampling event. Data gaps in the current database create uncertainty in the evaluation of lower priority constituents.

- Continued analysis for ferrous iron during every sampling event is not necessary. Groundwater from wells MW-301 through MW-313 was analyzed for ferrous iron three times in 2005. Ferrous iron concentrations provide an indication of whether iron-reducing conditions are present, which facilitates an evaluation of whether certain chlorinated VOCs can be readily degraded. However, once ferrous iron conditions are established, the sampling frequency can be reduced substantially to at least biennial (every other year) to allow periodic remedy evaluations.
- Delete Michigan 10 metals analysis based on the August 2005 metals data. There was only one very slight exceedance of an MCL (arsenic of 0.011 mg/L at MW-311 compared to MCL of 0.01 mg/L).
- In general, hydraulic monitoring for all wells located within the area of interest and screened within the depth zones of interest is recommended to maximize the accuracy of potentiometric surface maps. This recommendation is based on the observation that measurement of water levels in monitoring wells is generally relatively fast and inexpensive relative to water quality monitoring, and provides very important site characterization information. However, if multiple wells screened at similar depths are clustered in a small area and have similar groundwater elevations, one or more could be considered for removal from the hydraulic monitoring program unless more detailed delineation of local groundwater flow patterns is desired. At least two years of quarterly hydraulic monitoring is recommended to determine seasonal impacts on the potentiometric surface in the vicinity of the PRB Area. After that, semiannual hydraulic monitoring during relatively wet and dry times (e.g., spring and fall, concurrent with the groundwater sampling events) should be sufficient unless the quarterly monitoring results indicate significant seasonal variability that needs to be monitored more frequently. Hydraulic monitoring of all wells at the PRB area is recommended.
- The following potential data gaps were noted during performance of the qualitative evaluation for the PRB Area. They should be reviewed with the objective of verifying whether or not the current level of plume definition is acceptable in terms of 1) risks posed to potential receptors and 2) estimating the time and cost to achieve CUOs in groundwater.
  - The downgradient extent of the VOC plume is not well defined. VC concentrations in the most downgradient wells in May 2006 ranged up to 58 µg/L (well MW-308); in November 2006 the VC concentration in this well had decreased to 20 µg/L. VC concentrations that exceed the cleanup goal appear to be bypassing the PRBs in the shallow zone, as indicated by VC concentrations detected at MW-310 (21 to 27 µg/L in May and November 2006). There are no wells installed that could be used to define the downgradient extent of the contamination detected at MW-310 based on inferred groundwater flow directions for the shallow zone. A surface water drainage channel borders the site on the south side. Given the shallow depth to the water table at the site (within approximately 2 feet of the ground surface

at MW-308) and the assumed depth of the adjacent drainage channel (approximately 7-8 feet based on Lithologic Cross Section A-A' in Attachment A), it appears likely that some discharge of contaminated groundwater to the surface water drainage occurs. However, information obtained from Progressive indicates that surface water and other sampling has indicated that this potential exposure pathway is not of concern (Personal communication from Bridget Morello, 23 October 2006).

- Appropriate sampling should continue to be performed to confirm that surface water is not an exposure/migration pathway of concern that will result in unacceptable levels of risk to human or ecological receptors. An aerial photograph of the site obtained from the USEPA indicates that an areally extensive, undeveloped, partially forested area is located on the downgradient (south) side of the drainage channel. Any contaminants that underflow the drainage channel would migrate beneath this area. The boundary of the Clare Water Supply Superfund Site is located approximately 400 feet south of the PRBs. The stakeholders should verify that the current level of plume definition is acceptable in terms of risks posed to potential receptors.
- Intermediate-depth well 300B contained 200 µg/L of VC in May 2006 and 140 µg/L in November 2006. This is the only intermediate-depth well at the site and is screened from approximately 3 to 13 feet below the bottom of the PRBs. Therefore, the detected contamination is likely not treated by the PRBs. The areal extent and magnitude of contamination in the intermediate depth zone is not defined. Similarly, groundwater quality in the deep zone is not well defined, given that there are only three wells screened in this zone at the site, one of which is cross-gradient of the plume (well 220) and one which is south of the drainage channel (MW-312). Therefore, the vertical extent of groundwater contamination is not well delineated. There are no deep wells installed at the PRB Area downgradient of 300C, which has had recent exceedances of the CUO for VC. In addition, well 300C may be screened in a more permeable sand aquifer underlying the till based on geologic information presented in Section 2.0. As stated above, the stakeholders should verify that the current level of plume definition is acceptable in terms of risks posed to potential receptors and that sufficient data are available to properly estimate the time and cost required to achieve CUOs and site closure.
- Although monitored natural attenuation (MNA) is not part of the remedy specified in the Record of Decision (ROD; USEPA, 1992), the degree to which natural attenuation processes are reducing dissolved contaminant concentrations at the PRB Area is of interest because VC concentrations exceeding CUOs are migrating downgradient from the PRBs, and the PRBs are not deep enough to treat all of the CUO exceedances (i.e., at well 300B). Therefore, it is desirable to determine the effectiveness of MNA at treating the residual contamination in order to assess the time and cost required to achieve CUOs and whether they can be achieved within a reasonable timeframe. Some important natural attenuation indicator parameters that can provide insight into the ability of the groundwater system to degrade the COCs are already measured (i.e., DO and ORP). It should be noted however, that the biogeochemical nature of the shallow groundwater environment

immediately downgradient of the PRBs is impacted by the PRBs, and may not be representative of the groundwater environment farther downgradient. The *Technical Protocol for Evaluating Natural Attenuation of Chlorinated Solvents in Ground Water* (EPA/600/R-98/128, 1998) provides guidance on evaluating the site-specific effectiveness of MNA for chlorinated VOCs.

#### 4.2 MAROS Statistical Review for the PRB Area

- The MAROS COC Assessment ranked VC as the priority constituent for the PRB area. VC was, therefore, chosen as the target monitoring constituent for the MAROS evaluation. Qualitative consideration was given to cis-1,2-DCE and the less frequent detections of TCE and PCE.
- Individual well trend analyses for VC were determined in MAROS using analytical data collected between 1999 and 2006. Results are illustrated in Table 4 and Figure 5. The majority of wells have a relatively short monitoring record of quarterly samples between May 2005 and May 2006. Among the 12 wells recently installed in the shallow zone, roughly half show a stable concentration trend. One well, MW-306, shows a decreasing trend, while the others show variation in VC concentrations over the recent time frame. Older wells 300-A, 300-B and 300-C show increasing concentration trends.
- The total dissolved mass estimate (zerth moment) for VC showed a “Decreasing” trend between 1999 and 2006 for the shallow groundwater zone. Recent estimates of total dissolved mass in the shallow zone range between 0.3 kilograms (Kg) in 2005 dropping to 0.2 Kg in 2006. First moments (center of mass) in the PRB area are very stable over the 2005 to 2006 time-frame, as mass stays centered on higher concentration wells near 300A. However, this time-frame is very short. Moments should be reevaluated after a longer data set has been collected (4 years of data). Moments for the deep zone could not be evaluated due to the small number of monitoring locations.
- Spatial analysis of the VC plume using Delaunay triangulation and slope factor calculations indicate that the interior of the plume is well characterized by the existing well network and no new wells are recommended inside the network. However, a qualitative evaluation of the plume shows that the downgradient area to the south is not delineated to the CUO. Redundancy analysis indicates that locations MW-301, MW-304 and MW-305 may be removed from the network without loss of information. The results of the spatial analysis were considered in a final qualitative review, and wells MW-304 and MW-305 were retained in the program at a reduced sample frequency.
- Results of the MAROS well sampling frequency tool (the Modified Cost Effective Sampling [MCES] method) indicate that sampling frequency for the majority of wells in the PRB area can maintained at semiannual. Results of the MCES are shown in Table 5. Most of the monitoring well network was sampled quarterly from May 2005 to May 2006; since then, the sampling frequency has been decreased to semiannual.

Based on current trends, the MCES results for the majority of wells indicate that Annual sampling would be adequate to monitor changes in the plume. Wells 300A and 300B were recommended for Quarterly sampling based on a recent increasing concentration trend; however, due to the length of the monitoring

record and the location of these wells, a semiannual monitoring frequency is recommended after the qualitative evaluation. A Quarterly result was also returned for well MW-305, based on an order of magnitude concentration increase between November 2005 and March 2006. The increase may be a transient phenomenon, but after the qualitative evaluation, the well is recommended for retention in the monitoring program at a semiannual frequency.

Final recommendations for sampling frequency were determined after a review of both qualitative and quantitative information.

#### 4.3 *Recommendations for the PRB Area*

Recommendations for the PRB Area are summarized in Table 6 and described below.

- Continued sampling of 15 monitoring wells at the PRB Area is recommended. Continuation of a semiannual monitoring frequency for most wells is deemed appropriate assuming that future monitoring results do not indicate increasing trends that should be monitored more closely. Continued sampling of two lower-priority wells (MW-313 and MW-312) at an annual frequency is recommended. MW-313 is located cross-gradient of the VOC plume and MW-312 is screened in a relatively deep interval.
- Exclusion of four wells from the monitoring program at the PRB Area is recommended for the reasons identified in Tables 3 and 6. In general, these wells are not providing data of sufficient usefulness to justify continued sampling.
- The potential data gaps identified in Section 4.1 should be carefully considered, and additional sampling/characterization should be performed if appropriate to ensure that 1) the plume is adequately characterized to determine risks to potential receptors, 2) potential receptors are not being impacted by site-related contamination to an unacceptable degree, and 3) the appropriate data are collected to evaluate the effectiveness of MNA and properly estimate the time and cost required to achieve CUOs. Detailed site characterization information for the PRB area is not currently available in site documents provided to the authors. The lack of clarity in determining the depth of the drainage ditch near the PRB is indicative of challenges in information management associated with this area of concern. The majority of wells in the PRB area were drilled after the RODs were issued (1990, 1992, and 1997) and current information on the specific source of contamination and area hydrogeology are not included in these documents. The recommendation for the PRB area includes development of a Site Conceptual Model document to guide management decisions for this area of concern.
- Development of a comprehensive site-wide database should continue. Current and future analytical results should be available from laboratories in electronic data deliverable (EDD) format, which should simplify the validation and importation process. Results of historical analyses should be added to the database where possible, particularly when these data are used to support management decisions. The site-wide database should be made available to all stakeholders.



## 5.0 Soil Remedy Area Results

### 5.1 Qualitative Review for the Soil Remedy Area

- Details of the qualitative evaluation for the Soil Remedy Area are summarized in Table 7 and depicted on Figure 7. All wells that are part of the current monitoring program for this site are recommended for retention. However, a reduction in the sampling frequency is recommended for at least seven of the nine monitoring wells listed in Table 7. In general, the frequency reductions were recommended because 1) existing monitoring wells have been sampled at least 16 times over a period of at least 7 years, and, with few exceptions, increasing trends are not evident (based on statistical trend analysis results through May 2006); 2) the reported low groundwater flow velocity and presence of a slurry wall surrounding the soil remedy cell should prevent rapid changes in dissolved contaminant concentrations and preclude the need for more frequent monitoring; 3) operation of the DPE system within/beneath the soil remedy cell is apparently removing VOC mass and reducing VOC concentrations in the vadose and saturated zones over time; and 4) available information indicates that there are no nearby receptors. Continued semi-annual monitoring of two wells DMW-3S and DMW-3D is recommended due the magnitude of recent COC detections. Continuation of this frequency is contingent on future analytical results.
- The TAL for the Soil Remedy Area includes VOCs (SW8260B) and selected field parameters (pH, conductivity, temperature, turbidity, DO, and ORP). This TAL is reasonably optimized. However, discussion with the analytical laboratory regarding optimization of the target VOC list to a short-list of key COCs (e.g., chlorinated ethenes) is recommended. Potential advantages include lower laboratory analytical costs and lower data management/validation/reporting costs.
- The hydraulic monitoring recommendations made for the PRB Area (Section 4.1) are also applicable to the Soil Remedy Area.
- The following potential data gaps were noted during performance of the MNO evaluation for the Soil Remedy Area. They should be reviewed with the objective of verifying whether or not the current level of plume definition is acceptable in terms of 1) risks posed to potential receptors and 2) estimating the time and cost to achieve CUOs in groundwater.
  - The downgradient extent of the VOC plume in the shallow zone is not well defined. The TCE concentration measured in well DMW-3S in May 2006 was 23 µg/L compared to a CUO of 5 µg/L, and there are no shallow wells installed farther downgradient. The DO and ORP values measured at this well in November 2005 (8.8 mg/L and 94 millivolts, respectively) indicate that the shallow saturated zone is aerobic and oxidizing in this area, and the TCE will not readily degrade. This observation is supported by the relative lack of reductive dechlorination daughter products at DMW-3S (i.e., DCE and VC). However, information obtained from Progressive indicates that there are no receptors in the vicinity of the Soil Remedy Area (Personal communication from Bridget Morello, 26 October 2006). The northern boundary of the Clare Water Supply Superfund Site appears to be located approximately 200 feet north of the Soil Remedy Area, and institutional controls that preclude exposure to groundwater may not be in place north of this boundary. The

stakeholders should verify that the current level of plume definition is acceptable in terms of characterizing risks posed to potential receptors.

- The intermediate zone is the first water-bearing zone below the bottom of the slurry wall. There is only one well screened in this zone (215), and it is located approximately 165 feet north of the soil remedy cell. Therefore, the existing monitoring network would likely not detect contaminant migration from beneath the soil cell in the intermediate zone. Installation of three intermediate-zone wells along the northern (presumed downgradient) edge of the soil cell (at or near shallow wells DMW-1S, -2S, and -3S, Figure 7) should be considered. The intermediate-zone well control in this area appears to be sparse, and inferred groundwater flow directions in the intermediate zone are therefore somewhat speculative. Installation of new wells in this zone would help establish the groundwater flow direction in the intermediate zone (i.e., via triangulation between well 215 and the new wells). If the groundwater flow direction in the intermediate zone is actually more directly eastward as suggested by a more recent potentiometric surface map transmitted by Progressive (that was contoured without using anomalous data from well 300B), then consideration should be given to focusing installation of new intermediate wells on the east side of the soil remedy cell as indicated in the response to Progressive comment #16 (Attachment F). Two intermediate wells could be installed along the east side and a third on the north side to determine the vertical extent of identified contamination given the presence of a continuing source in that area.
- Groundwater elevation data collected in 2005 indicate a northerly to northwesterly groundwater flow direction in the shallow zone at the Soil Remedy Area. Well DMW-1S is located approximately 70 feet east of the northwestern corner of the soil cell. Therefore, dissolved contaminants migrating from beneath the western portion of the soil cell may not be detected by the existing shallow well network. Installation of an additional shallow well along the southern edge of US Highway 10 approximately 70 feet west of DMW-1S should be considered (Figure 7). It appears that the contouring of shallow groundwater elevation data for the Soil Remedy Area on Figures 7 and 10 of the *2005 Annual Monitoring Report* may not be completely correct. For example, the elevation for DMW-2S measured in May 2005 (838.23) is incorrectly located between the 836 and 838 elevation contours.
- Groundwater elevation data collected in 2005 indicate groundwater flow in the deep zone toward the east to east-northeast. However, it appears that the well control in this area is sparse, and inferred flow directions in the deep zone are somewhat speculative. Given the potential for migration toward the east-northeast, installation of one additional deep zone well northwest of DMW-3S (Figure 7) should be considered to detect any contaminant migration in the deep zone from beneath the northern portion of the soil cell. Installing a deep zone well near DMW-3S would have the added benefit of allowing assessment of vertical hydraulic gradients between the shallow, intermediate, and deep zones (assuming an intermediate well is also installed as discussed above), and also would help determine the groundwater flow direction with a higher degree of certainty (via triangulation with existing deep wells). Installation of one additional deep zone well could be made conditional on

sampling results for new intermediate zone wells. If the intermediate zone wells do not contain COCs at concentrations of concern, indicating a lack of significant vertical migration of COCs, then installation of a new deep well would not be necessary or recommended.

- As described in Section 2.2, it appears that the estimated groundwater velocity for the native materials at the Soil Remedy Area may be based on a single hydraulic conductivity measurement made elsewhere on the Clare Superfund Site. Therefore, there appears to be a fairly high degree of uncertainty regarding the groundwater seepage velocity at the Soil Remedy Area. Refinement/confirmation of the magnitude of this variable via performance of slug and/or pumping tests in selected site wells should be considered given that it is an important variable in assessing contaminant fate and transport and determining optimal monitoring locations and frequencies.
- The contaminant conditions required to trigger a reexamination of the monitoring program (i.e. monitoring objectives) do not appear to be well defined. Currently there is a CUO exceedance at well DMW-3S. However, this TCE detection does not appear to be of concern given the reported lack of nearby receptors. Is there a threshold value above which additional plume characterization would be determined to be advisable? Some thought should be given to articulating what contaminant concentrations are considered to be significant.
- There are 13 DPE wells at the Soil Remedy Area, all of which are assumed to be operating on at least an intermittent basis. However, these wells are not sampled (or at least sample results are not reported in the database) so it is not possible to determine if one or more of the wells can be shut down because it is no longer removing significant VOC mass. This situation is economical from a monitoring perspective, but may not be economical from the standpoint of energy usage, costs for treatment of extracted water, and system operation and maintenance. Consideration should be given to whether the economic benefits of occasional sampling of the DPE wells would outweigh the added cost.

## 5.2 *MAROS Statistical Review for the Soil Remedy Area*

The Soil Remedy Area has a limited number of wells screened in both the shallow and deep intervals. Because fewer than six locations are monitored in each zone, the spatial statistical evaluation of the Soil Remedy area was limited in scope.

- The COC Assessment module in MAROS identified VC as the only priority constituent in the Soil Remedy area, based on its low MCL and historic concentrations at some locations; however the data set did not have a complete record for VC. TCE was chosen as the guiding constituent for the network evaluation based on its more extensive record.
- The majority of wells in the Soil Remedy Area have limited detections of TCE. Mann-Kendall concentration trend results are illustrated on Figure 9. Locations UMW-1S, DMW-2D, and UMW-1D had non-detect results for all sample events, while locations DMW-1D, and DMW-3D had single detections that were not confirmed in later sampling. The deep zone of the aquifer to the east of the Soil Remedy area is largely unaffected by COCs.

Concentrations for shallow zone wells DMW 1 through 3 all showed strongly decreasing trends for TCE, while location 215 showed sporadic detections resulting in No Trend (NT), or high variability for TCE. Strongly decreasing trends at downgradient shallow zone locations indicate that the combined slurry wall and DPE remediation systems are functioning to reduce concentrations in this area.

- Preliminary sample frequency results from the MCES tool indicate that the frequency of well sampling could be reduced from semiannual to largely annual without loss of significant information. For the deep zone wells, preliminary results indicate that a biennial (every two year) sampling frequency would be adequate to characterize the change in concentration at these locations. In order to determine the final sampling frequency, the results of both the qualitative and statistical analyses were combined. Final recommendations are presented in Table 9 and are illustrated on Figure 10.
- The number of wells in the Soil Remedy Area in each groundwater zone (<6) were insufficient to perform moment analysis and formal spatial analysis for well redundancy and sufficiency. Well redundancy and sufficiency recommendations are based on the qualitative evaluation detailed above.

### 5.3 *Recommendations for the Soil Remedy Area*

Recommendations for the Soil Remedy Area are summarized in Table 9 and described below.

- Nine monitoring wells currently included in the monitoring program should be retained for continued sampling as described in Tables 7 and 9; however, sampling frequencies for at least seven of the wells could be reduced to annual (five wells) or biennial (every other year) (two wells). The current semiannual frequency for the remaining two wells (DMW-3S and DMW-3D) should be retained due to potentially increasing concentrations. Concentration trends can be evaluated at these locations after another one to two additional semi-annual monitoring events are performed, and the sample frequency adjusted to annual if concentrations are stable to decreasing.
- Shallow well SW-5 can be excluded from the Soil Remedy Area monitoring program as described in Tables 7 and 9. However, if this well is considered useful for site-wide monitoring or for monitoring another nearby site, then it should be retained for those purposes.
- The potential data gaps identified in Section 5.1 should be carefully considered, and additional sampling/characterization should be performed as appropriate to ensure that 1) the plume is adequately characterized to determine risks to potential receptors, 2) potential receptors are not being impacted by site-related contamination to an unacceptable degree, and 2) the appropriate data are collected to properly estimate the time and cost required to achieve CUOs for groundwater. As with the PRB area, a Site Conceptual Model document including detailed descriptions of area hydrogeology may be valuable in organizing site information and providing management decision support.
- At a minimum, installation of one shallow well and three intermediate-depth wells is recommended to more fully characterize the quality of groundwater migrating

downgradient from beneath the soil remedy cell and to better define groundwater flow directions in the intermediate zones. In addition, installation of one deep well should be considered if sampling results for new intermediate-depth wells indicate the presence of COCs at concentrations of concern in intermediate groundwater as described in Section 5.1.

- Development of a comprehensive site-wide database should continue. Current and future analytical results should be available from laboratories in electronic data deliverable (EDD) format, which should simplify the validation and importation process. Results of historical analyses should be added to the database where possible, particularly when these data are used to support management decisions. The site-wide database should be made available to all stakeholders.

## **6.0 Long-Term Monitoring Program Flexibility**

The long-term monitoring (LTM) program recommendations described above are based on available data regarding current (and expected future) site conditions. Changing site conditions, such as changes in hydraulic (pumping-related) stresses or remedial system operation, could affect contaminant fate and transport. Therefore, the LTM program should be reviewed if site conditions change significantly, and revised as necessary to adequately track changes in the magnitude and extent of COCs in groundwater over time.

## **7.0 References Cited**

- AFCEE. (1997). Air Force Center for Environmental Excellence, AFCEE Long-Term Monitoring Optimization Guide, <http://www.afcee.brooks.af.mil>.
- AFCEE. (2003). Monitoring and Remediation Optimization System (MAROS) 2.1 Software Users Guide. Air Force Center for Environmental Excellence. [http://www.gsi-net.com/software/MAROS\\_V2\\_1Manual.pdf](http://www.gsi-net.com/software/MAROS_V2_1Manual.pdf)
- Aziz, J. A., C. J. Newell, M. Ling, H. S. Rifai and J. R. Gonzales (2003). "MAROS: A Decision Support System for Optimizing Monitoring Plans." Ground Water **41**(3): 355-367.
- Progressive Environmental and Construction, Inc. (2006). 2005 Annual Monitoring Report, Clare Water Supply Superfund Site, Clare Michigan. Prepared for Clare PRP Group. February 21. Tampa, Florida.
- USEPA (1992). EPA Superfund Record of Decision: Clare Water Supply, EPA ID MID980002273, OU 02, Clare, MI. EPA/ROD/R05-92/209. September 16.
- USEPA (1998). Technical Protocol for Evaluating Natural Attenuation of Chlorinated Solvents in Ground Water. EPA/600/R-98/128. Office of Research and Development. September.
- USEPA (2006). Draft Second Five-Year Review Report for Clare Water Supply, City of Clare, Clare County, Michigan. Prepared by USEPA Region 5, Chicago, Illinois. September.

## Tables

**TABLE 1**  
**Summary of Site-Wide Long**  
**Term Groundwater Monitoring Plan**  
Clare Water Supply Superfund Site, Michigan

Well	General Well Depth	Well Depth (BGS)	Top of Screen (BGS)	Screen Length	Hydraulic Monitoring	Water Quality Monitoring	
					Current Frequency	Current Frequency	Method
<b>PRB Monitoring</b>							
220	Deep	60.5	55.5	5	Monthly	Semi Annual	VOCs - 8260B
300A	Shallow	17	12	5	Monthly	Semi Annual	VOCs - 8260B
300B	Intermediate	30	20	10	Monthly	Semi Annual	VOCs - 8260B
300C	Deep	80	60	20	Monthly	Semi Annual	VOCs - 8260B
MW-301	Shallow	17	12	5	Monthly	Semi Annual	VOCs - 8260B
MW-302	Shallow	15	10	5	Monthly	Semi Annual	VOCs - 8260B
MW-303	Shallow	15	10	5	Monthly	Semi Annual	VOCs - 8260B
MW-304	Shallow	15	10	5	Monthly	Semi Annual	VOCs - 8260B, MI 10 Metals
MW-305	Shallow	12	7	5	Monthly	Semi Annual	VOCs - 8260B, MI 10 Metals
MW-306	Shallow	17	12	5	Monthly	Semi Annual	VOCs - 8260B, MI 10 Metals
MW-307	Shallow	17	12	5	Monthly	Semi Annual	VOCs - 8260B, MI 10 Metals
MW-308	Shallow	12	7	5	Monthly	Semi Annual	VOCs - 8260B, MI 10 Metals
MW-309	Shallow	17	12	5	Monthly	Semi Annual	VOCs - 8260B
MW-310	Shallow	17	12	5	Monthly	Semi Annual	VOCs - 8260B
MW-311	Shallow	10	5	5	Monthly	Semi Annual	VOCs - 8260B, MI 10 Metals
MW-312	Deep	70	65	5	Monthly	Semi Annual	VOCs - 8260B
MW-313	Shallow	17	12	5	Monthly	Semi Annual	VOCs - 8260B
SW-11	Shallow	5.5	2	3	Monthly	Not Sampled	--
SW-12	Shallow	11.5	8	3	Monthly	Semi Annual	VOCs - 8260B
<b>Soil Remedy Monitoring</b>							
DMW-1D	Deep	75	70	5	Semi Annual	Semi Annual	VOCs - 8260B
DMW-1S	Shallow	17	12	5	Semi Annual	Semi Annual	VOCs - 8260B
DMW-2D	Deep	75	70	5	Semi Annual	Semi Annual	VOCs - 8260B
DMW-2S	Shallow	11	6	5	Semi Annual	Semi Annual	VOCs - 8260B
DMW-3D	Deep	75	70	5	Semi Annual	Semi Annual	VOCs - 8260B
DMW-3S	Shallow	10	5	5	Semi Annual	Semi Annual	VOCs - 8260B
EW-1	Intermediate	30	25	5	Semi Annual	Not Sampled	
EW-2	Intermediate	30	25	5	Semi Annual	Not Sampled	
EW-3	Intermediate	30	25	5	Semi Annual	Not Sampled	
EW-4	Intermediate	30	25	5	Semi Annual	Not Sampled	
EW-5	Intermediate	30	25	5	Semi Annual	Not Sampled	
EW-6	Intermediate	30	25	5	Semi Annual	Not Sampled	
EW-7	Intermediate	30	25	5	Semi Annual	Not Sampled	
EW-8	Intermediate	30	25	5	Semi Annual	Not Sampled	
EW-9	Intermediate	30	25	5	Semi Annual	Not Sampled	
EW-10	Intermediate	30	25	5	Semi Annual	Not Sampled	
EW-11	Intermediate	30	25	5	Semi Annual	Not Sampled	
EW-12	Intermediate	30	25	5	Semi Annual	Not Sampled	
EW-13	Intermediate	30	25	5	Semi Annual	Not Sampled	
SW-5	Shallow	6	3	3	Semi Annual	Semi Annual	VOCs - 8260B
UMW-1D	Deep	55	50	5	Semi Annual	Semi Annual	VOCs - 8260B
UMW-1S	Shallow	9	4	5	Semi Annual	Semi Annual	VOCs - 8260B

Notes:

Monthly hydraulic monitoring ended in May 2006; next hydraulic monitoring event was November 2006.

BGS = feet below ground surface.



**TABLE 2**  
**AQUIFER INPUT PARAMETERS FOR MAROS**  
**LONG-TERM MONITORING OPTIMIZATION**  
**CLARE WATER SUPPLY SUPERFUND SITE, MICHIGAN**

Parameter	PRB	Soil Remedy	
	Value	Value	Units
Current Plume Length	380	350	ft
Maximum Plume Length	380	350	ft
PlumeWidth	380	350	ft
SeepageVelocity Intermediate (ft/yr)*	98	0.005	ft/yr
Distance to Receptors (Source to MW-5)	1200	2000	ft
GWFluctuations	No	No	--
SourceTreatment	Permeable Reactive Barrier	Cap, slurry wall and DPE	--
PlumeType	Chlorinated Solvent	Chlorinated Solvent	--
NAPL Present	No	No	--
Vinyl Chloride	Screening Levels	Trichloroethene	
Cleanup Objective	0.015	--	mg/L
MCL	0.002	0.005	mg/L
Parameter	Value	Value	
Groundwater flow direction	South	North	
Porosity	0.38	0.39	--
Source Location near Well	300A*	Soil Remedy Cell	--
Source X-Coordinate	13014379.33	13014044.21	ft
Source Y-Coordinate	845654.49	846239.92	ft
Saturated Thickness	30	15 (Shallow)	ft

**Notes:**

1. Aquifer data from Progressive database (2006).
2. Priority COCs defined by prevalence, toxicity and mobility.
3. Saturated thickness represents the span of the shallow to intermediate aquifer.
5. ft = Coordinates in NAD 1983 State Plane Michigan Central feet.
6. Cleanup Objective from Michigan Part 201 Ground Water /Surface Water Interface standard for PRB area.  
MCL = USEPA Maximum Contaminant Level for drinking water.
7. \* = For the purpose of the spatial analysis, a point north of the barrier wall was chosen as the 'source' area.



**TABLE 3**  
**QUALITATIVE EVALUATION OF PRB AREA GROUNDWATER MONITORING NETWORK**  
**LONG-TERM MONITORING OPTIMIZATION**  
**CLARE WATER SUPPLY SUPERFUND SITE, MICHIGAN**

Well Name	Hydrologic Unit	Current Sampling Frequency	Qualitative Analysis			
			Exclude	Retain	Monitoring Frequency Recommendation	Rationale
220	Deep	Semi-Annual	X		NA	VOCs trace-level to non-detect during 43 sampling events over 12 years (1994-2006) with no cleanup objective (CUO) exceedances. No reason to believe that this will change in the future. Continued monitoring of this deep zone well that is screened below the primary contaminated interval would not provide useful information.
300A	Shallow	Semi-Annual		X	Semi-Annual	Provides upgradient data to evaluate VOC removal effectiveness of southern PRB. 17 sampling events from Dec '99 to Nov '06 provide sufficient baseline data to evaluate seasonal removal effectiveness; semiannual monitoring frequency should allow sufficient data to be collected to permit evaluation of PRB performance over time.
300B	Intermediate	Semi-Annual		X	Semi-Annual	Screened in Gray Till below bottom of PRBs that is not well-monitored; contains elevated VC levels that appear to be increasing with time; results indicative of underflow of VOCs beneath PRB; retain to continue monitoring groundwater quality in deeper zone.
300C	Deep	Semi-Annual		X	Semi-Annual*	Screened approx 44 to 64 ft below bottom of PRBs; only 3 deep wells present at site. Increasing VC trend between April '03 and Nov '05. Retain at moderate frequency to monitor trend. Consider reducing frequency to annual if increasing trend ceases.
MW-301	Shallow	Semi-Annual	X		NA	Results of 5 sampling events in 2005-2006 indicate occasional presence of very low VOC levels < CUO; no apparent increasing or decreasing trends. However, this well does not serve to bound plume on west side or accurately indicate VOC mass migrating around PRBs given higher COC detections in MW310, which is screened in same interval and located further west. Therefore, MW301 not providing useful data.
MW-302	Shallow	Semi-Annual		X	Semi-Annual	Measures water quality upgradient of PRBs in MW302-303-304/311 transect. COC concentrations over 5 quarterly events ending in May 06 consistently increased from MW302 to MW303; therefore, contrast between MW302 and MW303 did not appear to be a good indicator of PRB removal efficiency. Potential explanations include: 1) PRB is not effective at this location, 2) MW302 is not screened in primary contaminant flowpath, 3) groundwater does not migrate from MW302 to MW303, or 4) there is a source of VOCs between MW302 and MW303. However, trend reversed in Nov 06 (VC higher at MW302 than at MW303), potentially indicating PRB effects. Maintain semiannual monitoring frequency to assess future trends and PRB impacts. Note that COC concentrations in MW302 are much lower than detected in adjacent vertical profiling samples from VAS-301, indicating that data for MW302 are not representative of maximum COC concentrations in groundwater at this location.
MW-303	Shallow	Semi-Annual		X	Semi-Annual	Measures elevated COC levels in this area, and provides useful upgradient data to evaluate VOC removal efficiency of southern PRB. Concentration decrease from Aug to Nov 05 appears to indicate effect of northern PRB installation. Semi-annual monitoring frequency should yield sufficient data over time regarding PRB effectiveness.
MW-304	Shallow	Semi-Annual		X	Semi-Annual	Provides useful data regarding VOC removal efficiency of southern PRB near base of shallow zone. Semiannual monitoring frequency should yield sufficient data over time regarding PRB effectiveness. Note that vertical profiling data for adjacent VAS-304 indicate that MW-304 may be screened beneath highest VOC concentrations present in aquifer at this location.
MW-305	Shallow	Semi-Annual	X		NA	Measures water quality upgradient of PRBs in MW305-300A-307/308 transect. COC concentrations over 5 quarterly events consistently increased from MW305 to MW300A; therefore, contrast between these two wells does not appear to be a good indicator of northern PRB removal efficiency. Same trend observed in Nov 06. Potential explanations include: 1) PRB is not effective at this location, 2) MW305 is not screened in primary contaminant flowpath, 3) groundwater does not migrate from MW305 to MW300A, or 4) there is a source of VOCs between MW305 and MW300A. Note that COC concentrations in MW305 are much lower than detected in adjacent vertical profiling samples from VAS-302, indicating that data for MW305 are not representative of maximum COC concentrations in groundwater at this location. Continued monitoring of MW305 does not provide useful information regarding COC concentrations entering northern PRB and PRB effectiveness.
MW-306	Shallow	Semi-Annual		X	Semi-Annual	Provides useful data regarding combined VOC removal efficiency of northern and southern PRBs and concentrations exiting PRB area. Semi-annual monitoring frequency should yield sufficient data over time regarding PRB effectiveness.
MW-307	Shallow	Semi-Annual		X	Semi-Annual	Provides useful data regarding VOC removal efficiency of southern PRB and concentrations exiting PRB area near base of shallow zone. Semi-annual monitoring frequency should yield sufficient data over time regarding PRB effectiveness.
MW-308	Shallow	Semi-Annual		X	Semi-Annual	Provides useful data regarding VOC removal efficiency of southern PRB and concentrations exiting PRB area in middle portion of shallow zone. Semi-annual monitoring frequency should yield sufficient data over time regarding PRB effectiveness.
MW-309	Shallow	Semi-Annual		X	Semi-Annual	Monitors untreated VOC concentrations migrating past east end of PRBs. Data suggest possible increasing trend from Aug '05 to May '06, with lower VC concentration in Nov 06. Semi-annual monitoring frequency should yield sufficient data over time regarding PRB effectiveness unless increasing trend continues in the future.

**TABLE 3**  
**QUALITATIVE EVALUATION OF PRB AREA GROUNDWATER MONITORING NETWORK**  
**LONG-TERM MONITORING OPTIMIZATION**  
**CLARE WATER SUPPLY SUPERFUND SITE, MICHIGAN**

Well Name	Hydrologic Unit	Current Sampling Frequency	Qualitative Analysis			
			Exclude	Retain	Monitoring Frequency Recommendation	Rationale
MW-310	Shallow	Semi-Annual		X	Semi-Annual	Monitors untreated VOC concentrations migrating past west end of PRBs. Stable VC trend indicated as of Nov 06; semi-annual monitoring frequency should yield sufficient data over time regarding COC concentrations in this area.
MW-311	Shallow	Semi-Annual		X	Semi-Annual	Provides useful data regarding VOC removal efficiency of southern PRB and concentrations exiting PRB area in middle to upper portion of shallow zone. COC concentrations generally similar to slightly higher than in paired well MW304, consistent with vertical profiling results from VAS-305 (maximum concentrations at 8.5' bls). Semi-annual monitoring frequency should yield sufficient data over time regarding PRB effectiveness.
MW-312	Deep	Semi-Annual		X	Annual	Retain as deep zone sentry well in downgradient direction due to increasing trends in well 300C, which is screened at similar depth interval. Relatively low frequency justified by lack of COC detections through Nov 06 and reported lack of receptors. If rapid plume expansion at this depth was going to occur it would likely have already impacted this well.
MW-313	Shallow	Semi-Annual		X	Every other year	Well appears to be cross-gradient of VOC plume; only 2 trace-level chlorinated ethene detections in 6 monitoring events (up to Nov 06). Retain at low frequency to monitor eastern extent of plume over time.
SW-11	Shallow	Not Sampled	X		NA	Nov 06 sampling event first since 1999. No COC detections over 11 events from 1994 to 1999, and only 1 trace-level toluene detection in Nov 06 (possible lab contaminant). Distant and upgradient from PRBs. Other wells installed closer to PRBs provide better site-specific upgradient data.
SW-12	Shallow	Semi-Annual	X		NA	Well is cross-gradient of VOC plume; only 1 trace-level chlorinated ethene detection in 14 monitoring events. Continued low-frequency monitoring of MW313 would facilitate assessment of eastern plume extent over time.

NA = not applicable.

\* = conditional recommendation; see comments.



**TABLE 4**  
**WELL TREND SUMMARY RESULTS FOR PRB AREA: 1999-2006**

**LONG-TERM MONITORING OPTIMIZATION**  
**CLARE WATER SUPPLY SUPERFUND SITE, MICHIGAN**

WellName	Number of Samples	Number of Detects	Maximum Result [mg/L]	Max Result Above CUO?	Average Result [mg/L]	Average Result Above MCL?	Mann Kendall Trend	Linear Regression Trend	Overall Trend Result
<b><i>Vinyl Chloride Shallow and Intermediate Zone</i></b>									
300A	15	15	5.2	Yes	0.925	Yes	I	I	I
300B	13	13	0.2	Yes	0.0546	Yes	I	I	I
MW-301	5	4	0.0015	No	0.0013	No	S	S	S
MW-302	5	5	0.099	Yes	0.059	Yes	S	D	PD
MW-303	5	5	1.6	Yes	0.604	Yes	NT	D	S
MW-304	5	5	0.041	Yes	0.0231	Yes	S	S	S
MW-305	5	5	0.24	Yes	0.152	Yes	S	NT	S
MW-306	5	5	0.015	No	0.00518	Yes	D	D	D
MW-307	5	4	0.033	Yes	0.012	Yes	NT	NT	NT
MW-308	5	5	0.058	Yes	0.0414	Yes	NT	NT	NT
MW-309	5	5	0.048	Yes	0.0242	Yes	NT	S	S
MW-310	5	5	0.027	Yes	0.0167	Yes	NT	NT	NT
MW-311	5	5	0.069	Yes	0.0312	Yes	S	S	S
MW-313	5	1	0.00073	No	0.000946	No	ND*	ND*	ND*
SW-12	12	1	0.0016	No	0.00105	No	ND*	ND*	ND*
<b><i>Vinyl Chloride Deep Zone</i></b>									
220	15	1	0.00031	No	0.000954	No	S	S	S
300C	13	8	0.027	Yes	0.0076	Yes	I	I	I
MW-312	5	0	0.001	No	0.001	No	--	--	ND

**Notes**

- Trends were evaluated for data collected between 1/1/1999 and 5/30/2006. Trends including new data from 11/2006 are shown in Attachment C.
- Shallow and Intermediate zone is approximately between 7 and 40 ft bgs (847 and 817 ft AMSL). Deep zone is below 40 ft bgs (below 817 ft AMSL).
- Number of Samples is the number of samples for the compound at this location.  
Number of Detects is the number of times the compound has been detected at this location.
- Maximum Result is the maximum concentration for the COC indicated between 1999 and 2006.
- CUO = Clean-up Objective, 0.015 mg/L. MCL = 0.002 mg/L for vinyl chloride. 'Above MCL' indicates that the result value is above the screening level'.
- D = Decreasing; PD = Probably Decreasing; S = Stable; PI = Probably Increasing; I = Increasing; N/A = Insufficient Data to determine trend;  
NT = No Trend; ND = well has all non-detect results for COC; ND\* = Non-detect except for one trace value.
- Mann-Kendall trend results are illustrated on Figure 4.



**TABLE 5  
 WELL REDUNDANCY ANALYSIS SUMMARY RESULTS FOR PRB AREA  
 LONG-TERM MONITORING OPTIMIZATION  
 CLARE WATER SUPPLY SUPERFUND SITE, MICHIGAN**

WellName	Vinyl Chloride Average Slope Factor	Vinyl Chloride Minimum Slope Factor	Vinyl Chloride Maximum Slope Factor	Preliminary Statistical Result	Preliminary Sample Frequency
<b>Shallow and Intermediate Zone Wells</b>					
300A	0.47	0.28	0.72	Retain	Quarterly
300B	0.39	0.15	0.54	Retain	Quarterly
MW-301	0.87	0.59	1.00	Retain	Biennial
MW-302	0.11	0.02	0.28	<b>Exclude</b>	Annual
MW-303	0.35	0.30	0.50	Retain	Annual
MW-304	0.13	0.00	0.27	<b>Exclude</b>	Annual
MW-305	0.19	0.00	0.49	<b>Exclude</b>	Quarterly
MW-306	0.60	0.20	0.80	Retain	Annual
Mw-307	0.54	0.16	1.00	Retain	Annual
MW-308	0.24	0.00	0.53	Retain	Annual
MW-309	0.20	0.13	0.31	Retain	Annual
MW-310	0.32	0.03	0.70	Retain	SemiAnnual
MW-311	0.13	0.01	0.25	Retain	Annual
MW-313	0.90	0.55	1.00	Retain	Biennial
SW-12	0.88	0.65	1.00	Retain	Annual
<b>Deep Zone Wells</b>					
220	<b>Insufficient well locations in deep zone for spatial analysis</b>				Biennial
300C					Biennial
MW-312					Biennial

**Notes:**

- Slope Factor is the difference between the actual concentration and the concentration estimated from nearest neighbors normalized by the actual concentration. Slope factors close to 1 show the concentrations cannot be estimated from the nearest neighbors, and the well is important in the network.
- Slope factors were calculated using data between January 2002 and May 2006.
- Locations with slope factors below 0.3 were considered for elimination.
- Preliminary Sample Frequency is the result from the MCES analysis, 1999-2006.

**TABLE 6  
FINAL RECOMMENDED GROUNDWATER MONITORING NETWORK FOR PRB AREA**

**LONG-TERM MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE, MICHIGAN**

WellName	Number of Samples	Number of Detects	Average Result [mg/L]	Average Result Above CUO?	VC Mann Kendall Trend	VC Linear Regression Trend	VC Overall Trend Result	Recommendation After Qualitative and Quantitative Review		Rationale
								Sample Locations	Sample Frequency	
<b>Shallow and Intermediate Zone</b>										
300A	15	15	0.925	Yes	I	I	I	Retain	Semiannual	Monitors high concentrations between PRB, efficacy of southern PRB.
300B	13	13	0.055	Yes	I	I	I	Retain	Semiannual	Monitors Intermediate groundwater zone, not treated by PRB
MW-301	5	4	0.001	No	S	S	S	Exclude	--	Low concentration to non-detect, redundant with MW-310.
MW-302	5	5	0.059	Yes	S	D	PD	Retain	Semiannual	Upgradient, low concentrations, outside of main plume
MW-303	5	5	0.604	Yes	NT	D	S	Retain	Semiannual	Monitors efficacy of PRB
MW-304	5	5	0.023	Yes	S	S	S	Retain*	Semiannual	Monitors efficacy of PRB in lower Shallow Zone, companion well to MW311
MW-305	5	5	0.152	Yes	S	NT	S	Retain*	Semiannual	Monitors upgradient of PRB in Shallow Zone
MW-306	5	5	0.005	No	D	D	D	Retain	Semiannual	Monitors immediately downgradient of eastern PRB in Shallow Zone
MW-307	5	4	0.012	No	NT	NT	NT	Retain	Semiannual	Monitors efficacy of PRB in lower Shallow Zone, companion well to MW-308
MW-308	5	5	0.041	Yes	NT	NT	NT	Retain	Semiannual	Monitors efficacy of PRB in mid-upper Shallow Zone
MW-309	5	5	0.024	Yes	NT	S	S	Retain	Semiannual	Monitors eastern edge of PRB for possible routing of plume around PRB
MW-310	5	5	0.017	Yes	NT	NT	NT	Retain	Semiannual	Monitors western Shallow Zone, outside of PRB remedy.
MW-311	5	5	0.031	Yes	S	S	S	Retain	Semiannual	Monitors efficacy of PRB in mid-upper Shallow Zone
MW-313	5	1	0.001	No	ND*	ND*	ND*	Retain	Annual	Sentry well cross-gradient shallow eastern edge of plume
SW-12	12	1	0.001	No	ND*	ND*	ND*	Exclude	--	Cross-gradient, not in main plume.
SW-11	2	0	0.001	No	ND	ND	ND	Exclude	--	Upgradient, not in plume
<b>Deep Zone</b>										
220	15	1	0.000954	No	S	S	S	Exclude	--	Largely non-detect, not representative of plume or source.
300C	13	8	0.0076	No	I	I	I	Retain	Semiannual	Monitors upgradient Deep Zone
MW-312	5	0	0.001	No	--	--	ND	Retain	Annual	Deep Zone sentry well

**Notes**

- Shallow and Intermediate zone is approximately between 7 to 37 ft bgs (847 and 817 ft AMSL). Deep zone is below 40 ft bgs (below 817 ft AMSL).
- Number of Samples is the number of samples during the recent time-frame for the compound at this location.  
Number of Detects is the number of times the compound has been detected for data consolidated by quarter at this location.
- Average Result is the average concentration for TCE between 1999 and 2006.
- CUO = Clean-up Objective, 0.005 mg/L. 'Above CUO' indicates that the result value is above the objective standard.
- D = Decreasing; PD = Probably Decreasing; S = Stable; PI = Probably Increasing; I = Increasing; N/A = Insufficient Data to determine trend;  
NT = No Trend; ND = well has all non-detect results for COC; ND\* = Non-detect except for one trace value.
- All recommendations are contingent upon stable plume status under current conditions.  
Changes in groundwater flow velocity or head may require increasing or decreasing sample locations and frequency.
- Sample locations are illustrated on Figure 7.
- \* = Recommended for exclusion by either qualitative or quantitative analysis, but retained after final evaluation.

**TABLE 7**  
**QUALITATIVE EVALUATION OF SOIL REMEDY AREA GROUNDWATER MONITORING NETWORK**  
**LONG-TERM MONITORING OPTIMIZATION**  
**CLARE WATER SUPPLY SUPERFUND SITE, MICHIGAN**

Well Name	Hydrologic Unit	Current Sampling Frequency	Qualitative Analysis			
			Exclude	Retain	Monitoring Frequency Recommendation	Rationale
DMW-1D	Deep	Semi-Annual		X	Annual	16 sampling events from 3/99 to 11/06. Missing PCE and VC data from 3/99 to 5/04. COCs non-detect in almost every case but increased cis-DCE in 11/06 (unvalidated data). Retain as deep sentry well downgradient of soil remedy cell. Frequency reduction justified based on historical monitoring results (primarily non-detect), assumed low groundwater flow velocity, presence of low-permeability sediments below soil cell and slurry wall around it, and deep screen interval (significant impacts at 70 ft bgs less likely).
DMW-1S	Shallow	Semi-Annual		X	Annual	16 sampling events from 3/99 to 11/06. Missing PCE and VC data from 3/99 to 5/04. Retain as downgradient shallow sentry well. TCE exhibits decreasing trend while cis-DCE exhibits no trend and variable concentrations with occasional cleanup goal exceedances. Reduce frequency to annual given assumed low groundwater flow velocity, lack of receptors, and lack of recent CUO exceedances (only 2 in previous 8 events up to 11/06) unless risks to potential receptors are perceived, justifying additional remedial action and/or sampling.
DMW-2D	Deep	Semi-Annual		X	Annual	Same as DMW-1D.
DMW-2S	Shallow	Semi-Annual		X	Annual	No CUO exceedances since 1999. Retain as downgradient shallow sentry well. Frequency reduction justified based on historical monitoring results (trace-level to non-detect), assumed low groundwater flow velocity, lack of receptors, and presence of slurry wall restricting migration of contaminants from soil cell into downgradient shallow zone groundwater.
DMW-3D	Deep	Semi-Annual		X	Semi-Annual*	Same as DMW-1D. However, data for 2005-2006 suggest possible increasing trend in chlorinated VOC concentrations; therefore, retain current sampling frequency to assess temporal trend. Consider frequency reduction to annual if future data demonstrate that concentrations are not increasing.
DMW-3S	Shallow	Semi-Annual		X	Semi-Annual*	16 sampling events from 3/99 to 11/06. Missing PCE and VC data from 3/99 to 5/04. TCE exceeded cleanup goals in most recent events. Overall decreasing trend, but November 05 and May 06 data suggest possible rebound. Retain as downgradient shallow sentry well. If results of one additional semi-annual event indicates resumption of either stable or decreasing trend, then reduce frequency to annual.
SW-5	Shallow	Semi-Annual	X		--	30 sampling events since 12/94; no cleanup goal exceedances since 1998. Upgradient to cross-gradient from Soil Remedy Cell; additional sampling would not provide useful data regarding Soil Remedy Area.
UMW-1D	Deep	Semi-Annual		X	every other year	Retain as upgradient deep zone well; low monitoring frequency justified by upgradient location and lack of historical COC detections over 16 monitoring events since 1999.
UMW-1S	Shallow	Semi-Annual		X	every other year	Retain as upgradient shallow zone well; frequency reduction justified by upgradient location and lack of historical COC detections over 16 monitoring events since 1999.
EW-1	Intermediate	Semi-Annual				No Data
EW-2	Intermediate	Semi-Annual				No Data
EW-3	Intermediate	Semi-Annual				No Data
EW-4	Intermediate	Semi-Annual				No Data
EW-5	Intermediate	Semi-Annual				No Data
EW-6	Intermediate	Semi-Annual				No Data
EW-7	Intermediate	Semi-Annual				No Data
EW-8	Intermediate	Semi-Annual				No Data
EW-9	Intermediate	Semi-Annual				No Data
EW-10	Intermediate	Semi-Annual				No Data
EW-11	Intermediate	Semi-Annual				No Data
EW-12	Intermediate	Semi-Annual				No Data
EW-13	Intermediate	Semi-Annual				No Data
215	Intermediate	Semi-Annual		X	Annual	Sampled 36 times from 3/94 to 11/06 with only scattered low-level detections and no CUO exceedances. Retain as downgradient intermediate-zone sentry well. Frequency reduction justified by monitoring history, distance from source area, assumed low groundwater flow velocity, lack of receptors, potential for DMW-1S/2S/3S to provide early warning of contaminant migration toward 215.

\* = conditional recommendation; see comments.

**TABLE 8**  
**WELL TREND SUMMARY RESULTS SOIL REMEDY AREA: 1999-2006**

**LONG-TERM MONITORING OPTIMIZATION**  
**CLARE WATER SUPPLY SUPERFUND SITE, MICHIGAN**

WellName	Number of Samples	Number of Detects	Maximum Result [mg/L]	Max Result Above MCL?	Average Result [mg/L]	Average Result Above MCL?	Mann Kendall Trend	Linear Regression Trend	Overall Trend Result	Preliminary Sample Frequency
<b>Trichloroethene Shallow Zone</b>										
DMW-1S	15	15	0.099	Yes	0.017	Yes	D	D	D	Annual
DMW-2S	14	7	0.048	Yes	0.0019	No	D	D	D	Annual
DMW-3S	15	15	0.007	Yes	0.021	Yes	D	D	D	Annual
UMW-1S	15	0	0.001	No	0.001	No	--	--	ND	Biennial
SW-5	13	0	0.001	No	0.001	No	--	--	ND	Biennial
<b>Trichloroethene Chloride Deep Zone</b>										
DMW-1D	15	1	0.001	No	0.001	No	--	--	ND*	Biennial
DMW-2D	15	0	0.001	No	0.001	No	--	--	ND	Biennial
DMW-3D	15	1	0.0016	No	0.00104	No	NT	NT	NT	Biennial
UMW-1D	15	0	0.001	No	0.001	No	--	--	ND	Biennial

**Notes**

- Trends were evaluated for data collected between 1/1/1999 and 5/30/2006.
- Shallow and Intermediate zone is approximately between 0 and 17 ft bgs. Deep zone is below 50 ft bgs.
- Number of Samples is the number of samples for the compound at this location.  
Number of Detects is the number of times the compound has been detected at this location.
- Maximum Result is the maximum concentration for the COC indicated between 1999 and 2006.
- CJO = Clean-up Objective, 0.015 mg/L. MCL = 0.005 mg/L for TCE. 'Above MCL' indicates that the result value is above the screening level.
- D = Decreasing; PD = Probably Decreasing; S = Stable; PI = Probably Increasing; I = Increasing; N/A = Insufficient Data to determine trend;  
NT = No Trend; ND = well has all non-detect results for COC; ND\* = Non-detect except for one trace value.
- Mann-Kendall trend results are illustrated on Figure 4.
- LOE = Lines of Evidence. The LOE trend is a combination of the Mann-Kendall and Linear Regression trends.
- Average Result is the average concentration at the monitoring location for all samples between 1999 and 2006.
- The Sampling Frequency is a preliminary result from the software algorithm. A final frequency should be determined after a qualitative evaluation of all site data.
- Location DMW-1D had only one detection of TCE and DCE in June 2000. The detection was not repeated in subsequent sample events.

**TABLE 9  
FINAL RECOMMENDED MONITORING NETWORK SOIL REMEDY AREA**

**LONG-TERM MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE, MICHIGAN**



WellName	Number of Samples	Number of Detects	Average Result [mg/L]	Average Result Above CUO?	TCE Mann Kendall Trend	TCE Linear Regression Trend	TCE Overall Trend Result	Recommendation After Qualitative and Quantitative Review		Rationale
								Sample Locations	Sample Frequency	
<b>Shallow and Intermediate Zone</b>										
DMW-1S	15	15	0.017	Yes	D	D	D	Retain	Annual	Downgradient shallow sentry well
DMW-2S	14	7	0.002	No	D	D	D	Retain	Annual	Downgradient shallow sentry well
DMW-3S	15	15	0.021	Yes	D	D	D	Retain	Semiannual*	Consider changing frequency to Annual if concentrations stable to decreasing over 2-3 sample events
UMW-1S	15	0	0.001	No	--	--	ND	Retain	Biennial	Monitors shallow zone upgradient of soil remedy.
215	15	3	0.001	No	NT	NT	NT	Retain	Annual	Sentry well for downgradient intermediate groundwater zone.
SW-5	13	0	0.001	No	ND	ND	ND	Exclude	--	Cross-gradient of Soil Remedy Cell and not providing useful data.
<b>Deep Zone</b>										
DMW-1D	15	1	0.001	No	--	--	ND*	Retain	Annual	Monitors for contaminant migration in deep zone
DMW-2D	15	0	0.001	No	--	--	ND	Retain	Annual	Monitors for contaminant migration in deep zone
DMW-3D	15	1	0.001	No	NT	NT	NT	Retain	Semiannual*	Consider changing frequency to Annual if concentrations stable to decreasing over 2-3 sample events
UMW-1D	15	0	0.001	No	--	--	ND	Retain	Biennial	Monitors deep groundwater zone upgradient of soil remedy

**Notes**

1. Shallow and Intermediate zone is approximately between 7 to 37 ft bgs (847 and 817 ft AMSL). Deep zone is below 40 ft bgs (below 817 ft AMSL).
2. Number of Samples is the number of samples during the recent time-frame for the compound at this location.  
Number of Detects is the number of times the compound has been detected for data consolidated by quarter at this location.
3. Average Result is the average concentration for TCE between 1999 and 2006.
4. CUO = Clean-up Objective is equal to MCL, 0.005 mg/L. 'Above CUO' indicates that the result value is above the objective standard.
5. D = Decreasing; PD = Probably Decreasing; S = Stable; PI = Probably Increasing; I = Increasing; N/A = Insufficient Data to determine trend;  
NT = No Trend; ND = well has all non-detect results for COC; ND\* = Non-detect except for one trace value.
6. All recommendations are contingent upon stable plume status under current conditions.  
Changes in groundwater flow velocity or head may require increasing or decreasing sample locations and frequency.
7. Sample locations are illustrated on Figure 9.
8. \* = Consider reducing frequency to Annual if concentration trends stable to decreasing.
9. SW-5 may provide useful information for the Site-Wide groundwater monitoring network, which was not evaluated here.



## Figures




### Legend

- Soil Remedy Area Wells
  - PRB Area Wells
- Well Depth
- Deep
  - ▲ Intermediate
  - Shallow
- Permeable Reactive Barrier

Notes:

1. Shallow zone is between 5 and 20 FT bgs. Intermediate zone is between 20 and 50 FT bgs. Deep zone is between 50 and 80 FT bgs.
2. Data source Progressive Environmental and Construction, August 2006.




### GROUNDWATER MONITORING LOCATIONS: PRB AND SOIL REMEDY AREAS


Clare Water Treatment Site  
Clare, Michigan

GSI Job No.	G-3138-105	Drawn by:	MV
Issued:	03/22/2007	Chk'd by:	MV
Figure 1		App'v'd by:	MV


**FIGURE 2A**  
**APPROXIMATE WELL SCREEN INTERVALS FOR PRB AREA**  
**LONG-TERM MONITORING OPTIMIZATION EVALUATION**  
**CLARE WATER SUPPLY SUPERFUND SITE, MICHIGAN**



**FIGURE 2B**  
**PROXIMATE WELL SCREEN INTERVALS FOR SOIL REMEDY AREA**  
**LONG-TERM MONITORING OPTIMIZATION EVALUATION**  
**CLARE WATER SUPPLY SUPERFUND SITE, MICHIGAN**



S:\ES\cad\744461\06DN0268.dwg\_03/21/2007 2:54PM JLH




**LEGEND**

- MW-302 ○ SHALLOW MONITORING WELL
- 300B □ INTERMEDIATE MONITORING WELL
- 220 ⊕ DEEP MONITORING WELL
- VAS-302 △ VERTICAL PROFILING BOREHOLE
- ND = NOT DETECTED
- \* = CONDITIONAL RECOMMENDATION, SEE COMMENTS IN TABLE 3
- ← INFERRED GROUNDWATER FLOW DIRECTION

**RECOMMENDED SAMPLE FREQUENCY**

- SEMIANNUAL
- EVERY OTHER YEAR
- ANNUAL
- EXCLUDE

NOTE:  
 VINYL CHLORIDE (VC) CONCENTRATIONS POSTED FOR MONITORING WELLS ARE FOR MAY 06. VC CONCENTRATIONS POSTED FOR VAS- SERIES BOREHOLES ARE MAXIMUM DETECTED IN JANUARY 05.




**FIGURE 3**

**QUALITATIVE EVALUATION RESULTS FOR PRB AREA**

Long-Term Monitoring Network Optimization  
 Clare Water Supply Superfund Site

**PARSONS**  
 Denver, Colorado



## Legend


Permeable Reactive Barrier

Groundwater Flow Direction

### MannKendall Trend Vinyl Chloride

- Decreasing
- Probably Decreasing
- Stable
- Increasing
- No Trend
- Non Detect


- Notes:
1. Concentration trends were determined for vinyl chloride data between 1999 and November 2006.
  2. All wells screened in shallow zone of aquifer except locations indicated.
  3. Data source Progressive Environmental and Construction, August 2006.



## TEMPORAL TREND RESULTS: VINYL CHLORIDE PRB AREA

Clare Water Treatment Site  
Clare, Michigan

GSI Job No.	G-3138-105	Drawn by:	MV
Issued:	03/22/2007	Chk'd by:	MV
Figure 4		Appv'd by:	MV



## Legend

### Average Concentration Vinyl Chloride


- ◆ 0.000946 - 0.001 mg/L
- ◆ 0.001 - 0.002 mg/L
- ◆ 0.002 - 0.01 mg/L
- ◆ 0.01 - 0.015 mg/L
- ◆ 0.015 - 0.925 mg/L

— Permeable Reactive Barrier

#### Notes:

1. Average concentrations for wells 1999-2006.
2. CUO = 0.015 mg/L;  
MCL = 0.002 mg/L.
3. All wells screened in shallow zone of aquifer except locations indicated.
4. Data source Progressive Environmental and Construction, August 2006.


Scale (ft)



## WELL SUFFICIENCY VINYL CHLORIDE PRB AREA

Clare Water Treatment Site  
Clare, Michigan

GSI Job No.	G-3138-105	Drawn by:	MV
Issued:	03/22/2007	Chk'd by:	MV
Figure 5		Appv'd by:	MV




## Legend

### Recommended Sample Frequency

- Semiannual
- Annual
- Biennial
- X Exclude
- Permeable Reactive Barrier

- Notes:
1. Analysis was conducted for vinyl chloride data between 1999 and 2006.
  2. All wells screened in shallow zone of aquifer except locations indicated.
  3. Data source Progressive Environmental and Construction, August 2006.




## FINAL RECOMMENDED MONITORING NETWORK PRB AREA

Clare Water Treatment Site  
Clare, Michigan

GSI Job No. G-3138-105	Drawn by: MV
Issued: 03/22/2007	Chkd by: MV
Figure 6	App'd by: MV





**LEGEND**

- DMW-1S ○ SHALLOW MONITORING WELL
- 215 □ INTERMEDIATE MONITORING WELL
- DMW-1D ⊕ DEEP MONITORING WELL
- ⊙ PASSIVE SOIL VENT
- ⊕ DUAL PHASE EXTRACTION WELL
- ND = NOT DETECTED
- \* = CONDITIONAL RECOMMENDATION, SEE COMMENTS IN TABLE 7


**LEGEND**

- POTENTIAL NEW SHALLOW MONITORING WELL
- POTENTIAL NEW INTERMEDIATE MONITORING WELL
- ⊕ POTENTIAL NEW DEEP MONITORING WELL
- ← INFERRED GROUNDWATER FLOW DIRECTION

NOTE:  
VALUES POSTED AT EACH WELL LOCATION  
ARE MAY 2006 TCE CONCENTRATIONS (µg/L)

**RECOMMENDED SAMPLE FREQUENCY**

- SEMIANNUAL
- ANNUAL
- EVERY OTHER YEAR
- EXCLUDE





**FIGURE 7**

**QUALITATIVE EVALUATION RESULTS  
FOR SOIL REMEDY AREA**

Long-Term Monitoring Network Optimization  
Clare Water Supply Superfund Site

**PARSONS**  
Denver, Colorado


S:\ES\cod\744461\060N0267.dwg 03/21/2007 3:07PM JLH



## Legend



- Mann-Kendall Trend  
Trichloroethene**
- Decreasing
  - Probably Decreasing
  - Stable
  - Probably Increasing
  - Increasing
  - No Trend
  - Non detect

- Notes:
1. Trends were determined for trichloroethene data between 1999 and 2006.
  2. All wells screened in shallow zone of aquifer except locations indicated.
  3. Data source Progressive Environmental and Construction, August 2006.
  4. \*Well DMW-1D had one detection of TCE that was not reproduced -- well may be non-detect for TCE.



### TEMPORAL TREND RESULTS: TCE SOIL REMEDY AREA Clare Water Supply Clare, Michigan

GSI Job No.	G-3138-105	Drawn by:	MV
Issued:	03/22/2007	Chk'd by:	MV
Figure 8		Appv'd by:	MV




## Legend

### Recommended Sampling Frequency

- Semiannual
- Annual
- Biennial
- Not Analyzed
- Exclude

- Notes:
1. Results represent a combination of qualitative and quantitative methods. See text for details.
  2. Analysis was conducted for trichloroethene data between 1999 and 2006.
  3. Data source Progressive Environmental and Construction, August 2006.




## FINAL RECOMMENDED MONITORING NETWORK SOIL REMEDY AREA

Clare Water Supply  
Clare, Michigan

GSI Job No.	G-3138-105	Drawn by:	MV
Issued:	03/22/2007	Chk'd by:	MV
Figure 9		Appv'd by:	MV

**Attachment A**  
**Geologic Cross-Sections**

US10 DRAINAGE DITCH  
ADJACENT (300A) SW



- NOTES:
1. GEO DATA FROM JULY/AUGUST 2000.
  2. VAS DATA FROM JANUARY 2005.
  3. SW SAMPLE FROM MAY 2000.
  4. BORING/SAMPLE LOCATIONS ARE APPROXIMATE, NOT SURVEYED.

SCALE: HORIZONTAL: 1" = 10'  
VERTICAL : 1" = 5'

NOTE: ALL LOCATIONS AND THICKNESSES ARE APPROXIMATE.

**LEGEND**

20	TCE (UG/L)		PRB WALL
1950	CIS-1,2-DCE (UG/L)		GRAY TILL
200	VC (UG/L)		SAND (BACKFILL)
	LAND SURFACE ELEVATION		NATIVE MATERIAL
	BORING/SAMPLE LOCATION		


**PROGRESSIVE**  
ENGINEERING & CONSTRUCTION, INC.

3912 W. Humphrey Street  
Tampa, Florida 33614  
Phone: (813) 930-0669  
Fax: (813) 930-9809  
E-mail: bmpec@tampabay.rr.com

LITHOLOGIC CROSS SECTION A-A'

CLARE WATER SUPPLY SUPERFUND SITE  
CLARE, MICHIGAN

DRAWN MPG	DATE 4/20/05	PROJECT MANAGER BSM	DEPARTMENT MANAGER BSM
REV.	DATE	DESCRIPTION	LEAD DESIGN PROF. VT
			CHECKED BSM
			PROJECT NUMBER
			DRAWING NUMBER 2
FILE:	CROSSAALITH.DWG		



- NOTES:
- GEO DATA FROM JULY/AUGUST 2000.
  - VAS DATA FROM JANUARY 2005.
  - BORING/SAMPLE LOCATIONS ARE APPROXIMATE, NOT SURVEYED.

SCALE: HORIZONTAL: 1" = 20'  
 VERTICAL : 1" = 5'

NOTE: ALL LOCATIONS AND THICKNESSES ARE APPROXIMATE.

LEGEND	
20	TCE (UG/L)
1950	CIS-1,2-DCE (UG/L)
200	VC (UG/L)
	LAND SURFACE ELEVATION
	BORING/SAMPLE LOCATION
	PRB WALL
	GRAY TILL
	SAND (BACKFILL)
	NATIVE MATERIAL

**PROGRESSIVE**  
 ENGINEERING & CONSTRUCTION, INC.  
 3912 W. Humphrey Street  
 Tampa, Florida 33614  
 Phone: (813) 930-0669  
 Fax: (813) 930-9809  
 E-mail: bmpec@tampabay.rr.com

## LITHOLOGIC CROSS SECTION B-B'

CLARE WATER SUPPLY SUPERFUND SITE  
 CLARE, MICHIGAN

DRAWN MPG	DATE 4/20/05	PROJECT MANAGER BSM	DEPARTMENT MANAGER BSM
REV.	DATE	DESCRIPTION	LEAD DESIGN PROF. VT
			CHECKED BSM
			DRAWING NUMBER
FILE:	CROSSBBLITH.DWG		3

FILCON FACILITY  
(FORMERLY MITCHELL)

SW-11



220

GEO-1

GEO-2

GEO-3

SUMP

GEO-6

300C

300B

SW-12

U.S. 10 DRAINAGE DITCH

AS-CONSTRUCTED  
PERMEABLE REACTIVE  
BARRIER (ICS MATERIAL)

UPSTREAM  
(300A) SW


ADJACENT  
(300A) SW

DOWNSTREAM  
(300A) SW

- GEO-7 ● GEOPROBE SAMPLE LOCATION (JULY/AUGUST 2000)
- VAS-ETI-3 ⊕ VAS SAMPLE LOCATION (JANUARY 2005)
- MW-308 ○ PROPOSED MONITORING WELL  
PER PRB MONITORING WORKPLAN
- 300A ⊕ EXISTING MONITORING WELL
- × SURFACE WATER SAMPLING LOCATION  
(MAY 2000)

PROPOSED MW	SCREEN INTERVAL (FT. BLS)
MW-301	SCREEN AT HIGHEST VAS CONCENTRATION INTERVAL
MW-302	10-15
MW-303	10-15
MW-304	10-15
MW-305	7-12
MW-300A	12-17 (EXISTING)
MW-306	12-17
MW-307	12-17
MW-308	7-12
MW-309	SCREEN AT HIGHEST VAS CONCENTRATION INTERVAL
MW-310	SAME AS MW-301
MW-311	5-10
209	SCREEN AT HIGHEST VAS CONCENTRATION INTERVAL

NOTE:  
BORING/SAMPLE LOCATIONS ARE  
APPROXIMATE, NOT SURVEYED



(ACTUAL LOCATION WILL BE  
209 APPROXIMATELY 20' DUE  
○ SOUTH OF LOCATION SHOWN)

**PROGRESSIVE**  
ENGINEERING & CONSTRUCTION, INC.

3912 W. Humphrey Street  
Tampa, Florida 33614  
Phone: (813) 930-0669  
Fax: (813) 930-9809


## CROSS SECTION LAYOUT

CLARE WATER SUPPLY SITE  
CLARE, MICHIGAN


DRAWN MPG	DATE 4/21/05	PROJECT MANAGER GJR	DEPARTMENT MANAGER BSM
REV.	DATE	DESCRIPTION	LEAD DESIGN PROF. BSM
			CHECKED BSM
			PROJECT NUMBER P-2116
			DRAWING NUMBER 1
FILE: CrossSections.dwg			

OCTOBER, 2004

- IMPERMEABLE LINER
- SHALLOW GROUNDWATER
- + + + VEGETATIVE COVER
- ▨ MITCHELL SOILS
- NATIVE SAND
- - - NATIVE CLAY
- ▧ GLACIAL TILL




25 0 25  
HORIZONTAL SCALE: 1" = 25'  
VERTICAL SCALE: EXAGGERATED 3 X

DRAWN BY: <u>DRM</u>	PREPARED BY: 	PREPARED FOR: <b>CLARE PRP GROUP</b>	<b>FIGURE 6</b>  SOIL REMEDY GROUNDWATER LEVEL CROSS-SECTION A-A'
CHECKED: _____	<b>SECOR</b>	PIONEER PARKWAY CLARE, MI	
APPROVED: _____	2321 CLUB MERIDIAN DR., SUITE E OKEMOS, MICHIGAN		
DATE: <u>2/7/05</u>			
JOB No.: <u>24UN.20015.0002</u>			
CAD FILE: <u>PRBBASE</u>			



OCTOBER, 2004



25 0 25  
HORIZONTAL SCALE: 1" = 25'  
VERTICAL SCALE: EXAGGERATED 3 X

DRAWN BY: DRM  
CHECKED: \_\_\_\_\_  
APPROVED: \_\_\_\_\_  
DATE: 2/7/05  
JOB No.: 24UN.20015.0002  
CAD FILE: PRBBASE

PREPARED BY:  
  
**SECOR**  
2321 CLUB MERIDIAN DR., SUITE E  
OKEMOS, MICHIGAN

PREPARED FOR:  
**CLARE PRP GROUP**  
  
PIONEER PARKWAY  
CLARE, MI

**FIGURE 7**

SOIL REMEDY  
GROUNDWATER LEVEL  
CROSS-SECTION B-B'

**Attachment B**  
**MAROS 2.2 Methodology**

# ATTACHMENT B MAROS 2.2 METHODOLOGY

## Contents

<b>1.0 MAROS Conceptual Model</b> .....	<b>1</b>
<b>2.0 Data Management</b> .....	<b>2</b>
<b>3.0 Site Details</b> .....	<b>2</b>
<b>4.0 Constituent Selection</b> .....	<b>3</b>
<b>5.0 Data Consolidation</b> .....	<b>3</b>
<b>6.0 Overview Statistics: Plume Trend Analysis</b> .....	<b>3</b>
6.1 Mann-Kendall Analysis.....	4
6.2 Linear Regression Analysis.....	4
6.3 Overall Plume Analysis .....	5
6.4 Moment Analysis.....	6
<b>7.0 Detailed Statistics: Optimization Analysis</b> .....	<b>8</b>
7.1 Well Redundancy Analysis- Delaunay Method .....	8
7.2 Well Sufficiency Analysis - Delaunay Method .....	9
7.3 Sampling Frequency - Modified CES Method .....	10
7.4 Data Sufficiency – Power Analysis.....	11

## Cited References

## Tables

- Table 1** Mann-Kendall Analysis Decision Matrix
- Table 2** Linear Regression Analysis Decision Matrix

## Figures

- Figure 1** MAROS Decision Support Tool Flow Chart
- Figure 2** MAROS Overview Statistics Trend Analysis Methodology
- Figure 3** Decision Matrix for Determining Provisional Frequency

## MAROS METHODOLOGY

MAROS is a collection of tools in one software package that is used in an explanatory, non-linear but linked fashion. The tool includes models, statistics, heuristic rules, and empirical relationships to assist the user in optimizing a groundwater monitoring network system. The final optimized network maintains adequate delineation while providing information on plume dynamics over time. Results generated from the software tool can be used to develop lines of evidence, which, in combination with expert opinion, can be used to inform regulatory decisions for safe and economical long-term monitoring of groundwater plumes. For a detailed description of the structure of the software and further utilities, refer to the MAROS 2.2 Manual (AFCEE, 2003; [http://www.gsi-net.com/software/MAROS\\_V2\\_1Manual.pdf](http://www.gsi-net.com/software/MAROS_V2_1Manual.pdf)) and Aziz et al., 2003.

### 1.0 MAROS Conceptual Model

In MAROS 2.2, two levels of analysis are used for optimizing long-term monitoring plans: 1) an overview statistical evaluation with interpretive trend analysis based on temporal trend analysis and plume stability information; and 2) a more detailed statistical optimization based on spatial and temporal redundancy reduction methods (see Figures A.1 and A.2 for further details). In general, the MAROS method applies to 2-D aquifers that have relatively simple site hydrogeology. However, for a multi-aquifer (3-D) system, the user has the option to apply the statistical analysis layer-by-layer.

The overview statistics or interpretive trend analysis assesses the general monitoring system category by considering individual well concentration trends, overall plume stability, hydrogeologic factors (e.g., seepage velocity, and current plume length), and the location of potential receptors (e.g., property boundaries or drinking water wells). The method relies on temporal trend analysis to assess plume stability, which is then used to determine the general monitoring system category. Since the monitoring system category is evaluated for both source and tail regions of the plume, the site wells are divided into two different zones: the source zone and the tail zone.

Source zone monitoring wells could include areas with non-aqueous phase liquids (NAPLs), contaminated vadose zone soils, and areas where aqueous-phase releases have been introduced into ground water. The source zone generally contains locations with historical high ground water concentrations of the COCs. The tail zone is usually the area downgradient of the contaminant source zone. Although this classification is a simplification of the plume conceptual model, this broadness makes the user aware on an individual well basis that the concentration trend results can have a different interpretation depending on the well location in and around the plume. The location and type of the individual wells allows further interpretation of the trend results, depending on what type of well is being analyzed (e.g., remediation well, leading plume edge well, or monitoring well). General recommendations for the monitoring network frequency and density are suggested based on heuristic rules applied to the source and tail trend results.

The detailed statistics level of analysis or sampling optimization consists of well redundancy and well sufficiency analyses using the Delaunay method, a sampling frequency analysis using the Modified Cost Effective Sampling (MCES) method and a data sufficiency analysis including statistical power analysis. The well redundancy analysis is designed to minimize monitoring locations and the Modified CES method is designed to minimize the frequency of sampling. The data sufficiency analysis uses simple statistical methods to assess the sampling record to determine if groundwater concentrations are statistically below target levels and if the current monitoring network and record is sufficient in terms of evaluating concentrations at downgradient locations.

## **2.0 Data Management**

In MAROS, ground water monitoring data can be imported from simple database-format Microsoft® Excel spreadsheets, Microsoft Access tables, previously created MAROS database archive files, or entered manually. Monitoring data interpretation in MAROS is based on historical analytical data from a consistent set of wells over a series of sampling events. The analytical data is composed of the well name, coordinate location, constituent, result, detection limit and associated data qualifiers. Statistical validity of the concentration trend analysis requires constraints on the minimum data input of at least four wells (ASTM 1998) in which COCs have been detected. Individual sampling locations need to include data from at least six most-recent sampling events. To ensure a meaningful comparison of COC concentrations over time and space, both data quality and data quantity need to be considered. Prior to statistical analysis, the user can consolidate irregularly sampled data or smooth data that might result from seasonal fluctuations or a change in site conditions. Because MAROS is a terminal analytical tool designed for long-term planning, impacts of seasonal variation in the water unit are treated on a broad scale, as they relate to multi-year trends.

Imported ground water monitoring data and the site-specific information entered in Site Details can be archived and exported as MAROS archive files. These archive files can be appended as new monitoring data becomes available, resulting in a dynamic long-term monitoring database that reflects the changing conditions at the site (i.e. biodegradation, compliance attainment, completion of remediation phase, etc.). For wells with a limited monitoring history, addition of information as it becomes available can change the frequency or identity of wells in the network.

## **3.0 Site Details**

Information needed for the MAROS analysis includes site-specific parameters such as seepage velocity and current plume length and width. Information on the location of potential receptors relative to the source and tail regions of the plume is entered at this point. Part of the trend analysis methodology applied in MAROS focuses on where the monitoring well is located, therefore the user needs to divide site wells into two different zones: the source zone or the tail zone. Although this classification is a simplification of the well function, this broadness makes the user aware on an individual well basis that the concentration trend results can have a different interpretation depending on the well location in and around the plume. It is up to the user to make further interpretation of the

trend results, depending on what type of well is being analyzed (e.g., remediation well, leading plume edge well, or monitoring well). The Site Details section of MAROS contains a preliminary map of well locations to confirm well coordinates.

#### **4.0 Constituent Selection**

A database with multiple COCs can be entered into the MAROS software. MAROS allows the analysis of up to 5 COCs concurrently and users can pick COCs from a list of compounds existing in the monitoring data. MAROS runs separate optimizations for each compound. For sites with a single source, the suggested strategy is to choose one to three priority COCs for the optimization. If, for example, the site contains multiple chlorinated volatile organic compounds (VOCs), the standard sample chemical analysis will evaluate all VOCs, so the sample locations and frequency should be based on the concentration trends of the most prevalent, toxic or mobile compounds. If different chemical classes are present, such as metals and chlorinated VOCs, choose and evaluate the priority constituent in each chemical class.

MAROS includes a short module that provides recommendations on prioritizing COCs based on toxicity, prevalence, and mobility of the compound. The toxicity ranking is determined by examining a representative concentration for each compound for the entire site. The representative concentration is then compared to the screening level (PRG or MCL) for that compound and the COCs are ranked according to the representative concentrations percent exceedence of the screening level. The evaluation of prevalence is performed by determining a representative concentration for each well location and evaluating the total exceedences (values above screening levels) compared to the total number of wells. Compounds found over screening levels are ranked for mobility based on  $K_d$  (sorption partition coefficient). The MAROS COC assessment provides the relative ranking of each COC, but the user must choose which COCs are included in the analysis.

#### **5.0 Data Consolidation**

Typically, raw data from long-term monitoring have been measured irregularly in time or contain many non-detects, trace level results, and duplicates. Therefore, before the data can be further analyzed, raw data are filtered, consolidated, transformed, and possibly smoothed to allow for a consistent dataset meeting the minimum data requirements for statistical analysis mentioned previously.

MAROS allows users to specify the period of interest in which data will be consolidated (i.e., monthly, bi-monthly, quarterly, semi-annual, yearly, or a biennial basis). In computing the representative value when consolidating, one of four statistics can be used: median, geometric mean, mean, and maximum. Non-detects can be transformed to one half the reporting or method detection limit (DL), the DL, or a fraction of the DL. Trace level results can be represented by their actual values, one half of the DL, the DL, or a fraction of their actual values. Duplicates are reduced in MAROS by one of three ways: assigning the average, maximum, or first value. The reduced data for each COC

and each well can be viewed as a time series in a graphical form on a linear or semi-log plot generated by the software.

## **6.0 Overview Statistics: Plume Trend Analysis**

Within the MAROS software there are historical data analyses that support a conclusion about plume stability (e.g., increasing plume, etc.) through statistical trend analysis of historical monitoring data. Plume stability results are assessed from time-series concentration data with the application of three statistical tools: Mann-Kendall Trend analysis, linear regression trend analysis and moment analysis. The two trend methods are used to estimate the concentration trend for each well and each COC based on a statistical trend analysis of concentrations versus time at each well. These trend analyses are then consolidated to give the user a general plume stability estimate and general monitoring frequency and density recommendations (see Figures A.1 through A.3 for further step-by-step details). Both qualitative and quantitative plume information can be gained by these evaluations of monitoring network historical data trends both spatially and temporally. The MAROS Overview Statistics are the foundation the user needs to make informed optimization decisions at the site. The Overview Statistics are designed to allow site personnel to develop a better understanding of the plume behavior over time and understand how the individual well concentration trends are spatially distributed within the plume. This step allows the user to gain information that will support a more informed decision to be made in the next level or detailed statistics optimization analysis.

### 6.1 Mann-Kendall Analysis

The Mann-Kendall test is a statistical procedure that is well suited for analyzing trends in data over time. The Mann-Kendall test can be viewed as a non-parametric test for zero slope of the first-order regression of time-ordered concentration data versus time. One advantage of the Mann-Kendall test is that it does not require any assumptions as to the statistical distribution of the data (e.g. normal, lognormal, etc.) and can be used with data sets which include irregular sampling intervals and missing data. The Mann-Kendall test is designed for analyzing a single groundwater constituent, multiple constituents are analyzed separately. The Mann-Kendall S statistic measures the trend in the data: positive values indicate an increase in concentrations over time and negative values indicate a decrease in concentrations over time. The strength of the trend is proportional to the magnitude of the Mann-Kendall statistic (i.e., a large value indicates a strong trend). The confidence in the trend is determined by consulting the S statistic and the sample size, n, in a Kendall probability table such as the one reported in Hollander and Wolfe (1973).

The concentration trend is determined for each well and each COC based on results of the S statistic, the confidence in the trend, and the Coefficient of Variation (COV). The decision matrix for this evaluation is shown in Table 3. A Mann-Kendall statistic that is greater than 0 combined with a confidence of greater than 95% is categorized as an Increasing trend while a Mann-Kendall statistic of less than 0 with a confidence between 90% and 95% is defined as a probably Increasing trend, and so on.

Depending on statistical indicators, the concentration trend is classified into six categories:

- Decreasing (D),
- Probably Decreasing (PD),
- Stable (S),
- No Trend (NT),
- Probably Increasing (PI)
- Increasing (I).

These trend estimates are then analyzed to identify the source and tail region overall stability category (see Figure 2 for further details).

## 6.2 Linear Regression Analysis

Linear Regression is a parametric statistical procedure that is typically used for analyzing trends in data over time. Using this type of analysis, a higher degree of scatter simply corresponds to a wider confidence interval about the average log-slope. Assuming the sign (i.e., positive or negative) of the estimated log-slope is correct, a level of confidence that the slope is not zero can be easily determined. Thus, despite a poor goodness of fit, the overall trend in the data may still be ascertained, where low levels of confidence correspond to “Stable” or “No Trend” conditions (depending on the degree of scatter) and higher levels of confidence indicate the stronger likelihood of a trend. The linear regression analysis is based on the first-order linear regression of the log-transformed concentration data versus time. The slope obtained from this log-transformed regression, the confidence level for this log-slope, and the COV of the untransformed data are used to determine the concentration trend. The decision matrix for this evaluation is shown in Table 4.

To estimate the confidence in the log-slope, the standard error of the log-slope is calculated. The coefficient of variation, defined as the standard deviation divided by the average, is used as a secondary measure of scatter to distinguish between “Stable” or “No Trend” conditions for negative slopes. The Linear Regression Analysis is designed for analyzing a single groundwater constituent; multiple constituents are analyzed separately, (up to five COCs simultaneously). For this evaluation, a decision matrix developed by Groundwater Services, Inc. is also used to determine the “Concentration Trend” category (plume stability) for each well.

Depending on statistical indicators, the concentration trend is classified into six categories:

- Decreasing (D),
- Probably Decreasing (PD),
- Stable (S),
- No Trend (NT),
- Probably Increasing (PI)
- Increasing (I).



The resulting confidence in the trend, together with the log-slope and the COV of the untransformed data, are used in the linear regression analysis decision matrix to determine the concentration trend. For example, a positive log-slope with a confidence of less than 90% is categorized as having No Trend whereas a negative log-slope is considered Stable if the COV is less than 1 and categorized as No Trend if the COV is greater than 1.

### 6.3 Overall Plume Analysis

General recommendations for the monitoring network frequency and density are suggested based on heuristic rules applied to the source and tail trend results. Individual well trend results are consolidated and weighted by the MAROS according to user input, and the direction and strength of contaminant concentration trends in the source zone and tail zone for each COC are determined. Based on

- i) the consolidated trend analysis,
- ii) hydrogeologic factors (e.g., seepage velocity), and
- iii) location of potential receptors (e.g., wells, discharge points, or property boundaries),

the software suggests a general optimization plan for the current monitoring system in order to efficiently but effectively monitor groundwater in the future. A flow chart utilizing the trend analysis results and other site-specific parameters to form a general sampling frequency and well density recommendation is outlined in Figure 2. For example, a generic plan for a shrinking petroleum hydrocarbon plume (BTEX) in a slow hydrogeologic environment (silt) with no nearby receptors would entail minimal, low frequency sampling of just a few indicators. On the other hand, the generic plan for a chlorinated solvent plume in a fast hydrogeologic environment that is expanding but has very erratic concentrations over time would entail more extensive, higher frequency sampling. The generic plan is based on a heuristically derived algorithm for assessing future sampling duration, location and density that takes into consideration plume stability. For a detailed description of the heuristic rules used in the MAROS software, refer to the MAROS 2.2 Manual (AFCEE, 2003).

### 6.4 Moment Analysis

An analysis of moments can help resolve plume trends, where the zeroth moment shows change in dissolved mass vs. time, the first moment shows the center of mass location vs. time, and the second moment shows the spread of the plume vs. time. Moment calculations can predict how the plume will change in the future if further statistical analysis is applied to the moments to identify a trend (in this case, Mann Kendall Trend Analysis is applied). The trend analysis of moments can be summarized as:

- Zeroth Moment: An estimate of the total mass of the constituent for each sample event
- First Moment: An estimate of the center of mass for each sample event
- Second Moment: An estimate of the spread of the plume around the center of mass

The role of moment analysis in MAROS is to provide a relative estimate of plume stability and condition within the context of results from other MAROS modules. The Moment analysis algorithms in MAROS are simple approximations of complex calculations and are meant to estimate changes in total mass, center of mass and spread of mass for complex well networks. The Moment Analysis module is sensitive to the number and arrangement of wells in each sampling event, so, changes in the number and identity of wells during monitoring events, and the parameters chosen for data consolidation can cause changes in the estimated moments.

Plume stability may vary by constituent, therefore the MAROS Moment analysis can be used to evaluate multiple COCs simultaneously which can be used to provide a quick way of comparing individual plume parameters to determine the size and movement of constituents relative to one another. Moment analysis in the MAROS software can also be used to assist the user in evaluating the impact on plume delineation in future sampling events by removing identified “redundant” wells from a long-term monitoring program (this analysis was not performed as part of this study, for more details on this application of moment analysis refer to the MAROS Users Manual (AFCEE, 2003)).

The **zeroth moment** is the sum of concentrations for all monitoring wells and is a mass estimate. The zeroth moment calculation can show high variability over time, largely due to the fluctuating concentrations at the most contaminated wells as well as varying monitoring well network. Plume analysis and delineation based exclusively on concentration can exhibit fluctuating temporal and spatial values. The mass estimate is also sensitive to the extent of the site monitoring well network over time. The zeroth moment trend over time is determined by using the Mann-Kendall Trend Methodology. The zeroth Moment trend test allows the user to understand how the plume mass has changed over time. Results for the trend include: Increasing, probably Increasing, no trend, stable, probably decreasing, decreasing or not applicable (N/A) (Insufficient Data). When considering the results of the zeroth moment trend, the following factors should be considered which could effect the calculation and interpretation of the plume mass over time: 1) Change in the spatial distribution of the wells sampled historically 2) Different wells sampled within the well network over time (addition and subtraction of well within the network). 3) Adequate versus inadequate delineation of the plume over time

The **first moment** estimates the center of mass, coordinates ( $X_c$  and  $Y_c$ ) for each sample event and COC. The changing center of mass locations indicate the movement of the center of mass over time. Whereas, the distance from the original source location to the center of mass locations indicate the movement of the center of mass over time relative to the original source. Calculation of the first moment normalizes the spread by the concentration indicating the center of mass. The first moment trend of the distance to the center of mass over time shows movement of the plume in relation to the original source location over time. Analysis of the movement of mass should be viewed as it relates to 1) the original source location of contamination 2) the direction of groundwater flow and/or 3) source removal or remediation. Spatial and temporal trends in the center of mass can indicate spreading or shrinking or transient movement based on season variation in rainfall or other hydraulic considerations. No appreciable movement or a neutral trend in the center of mass would indicate plume stability. However, changes in

the first moment over time do not necessarily completely characterize the changes in the concentration distribution (and the mass) over time. Therefore, in order to fully characterize the plume the First Moment trend should be compared to the zeroth moment trend (mass change over time).

The **second moment** indicates the spread of the contaminant about the center of mass ( $S_{xx}$  and  $S_{yy}$ ), or the distance of contamination from the center of mass for a particular COC and sample event. The Second Moment represents the spread of the plume over time in both the x and y directions. The Second Moment trend indicates the spread of the plume about the center of mass. Analysis of the spread of the plume should be viewed as it relates to the direction of groundwater flow. An Increasing trend in the second moment indicates an expanding plume, whereas a declining trend in the second moment indicates a shrinking plume. No appreciable movement or a neutral trend in the center of mass would indicate plume stability. The second moment provides a measure of the spread of the concentration distribution about the plume's center of mass. However, changes in the second moment over time do not necessarily completely characterize the changes in the concentration distribution (and the mass) over time. Therefore, in order to fully characterize the plume the Second Moment trend should be compared to the zeroth moment trend (mass change over time).

## **7.0 Detailed Statistics: Optimization Analysis**

Although the overall plume analysis shows a general recommendation regarding sampling frequency reduction and a general sampling density, a more detailed analysis is also available with the MAROS 2.2 software in order to allow for further reductions on a well-by-well basis for frequency, well redundancy, well sufficiency and sampling sufficiency. The MAROS Detailed Statistics allows for a quantitative analysis for spatial and temporal optimization of the well network on a well-by-well basis. The results from the Overview Statistics should be considered along with the MAROS optimization recommendations gained from the Detailed Statistical Analysis described previously. The MAROS Detailed Statistics results should be reassessed in view of site knowledge and regulatory requirements as well as in consideration of the Overview Statistics (Figure 2).

The Detailed Statistics or Sampling Optimization MAROS modules can be used to determine the minimal number of sampling locations and the lowest frequency of sampling that can still meet the requirements of sampling spatially and temporally for an existing monitoring program. It also provides an analysis of the sufficiency of data for the monitoring program.

Sampling optimization in MAROS consists of four parts:

- Well redundancy analysis using the Delaunay method
- Well sufficiency analysis using the Delaunay method
- Sampling frequency determination using the Modified CES method
- Data sufficiency analysis using statistical power analysis.

The well redundancy analysis using the Delaunay method identifies and eliminates redundant locations from the monitoring network. The well sufficiency analysis can determine the areas where new sampling locations might be needed. The Modified CES method determines the optimal sampling frequency for a sampling location based on the direction, magnitude, and uncertainty in its concentration trend. The data sufficiency analysis examines the risk-based site cleanup status and power and expected sample size associated with the cleanup status evaluation.

### 7.1 Well Redundancy Analysis – Delaunay Method

The well redundancy analysis using the Delaunay method is designed to select the minimum number of sampling locations based on the spatial analysis of the relative importance of each sampling location in the monitoring network. The approach allows elimination of sampling locations that have little impact on the historical characterization of a contaminant plume. An extended method or wells sufficiency analysis, based on the Delaunay method, can also be used for recommending new sampling locations. Details about the Delaunay method can be found in Appendix A.2 of the MAROS Manual (AFCEE, 2003).

Sampling Location determination uses the Delaunay triangulation method to determine the significance of the current sampling locations relative to the overall monitoring network. The Delaunay method calculates the network Area and Average concentration of the plume using data from multiple monitoring wells. A slope factor (SF) is calculated for each well to indicate the significance of this well in the system (i.e. how removing a well changes the average concentration.)

The Sampling Location optimization process is performed in a stepwise fashion. Step one involves assessing the significance of the well in the system, if a well has a small SF (little significance to the network), the well may be removed from the monitoring network. Step two involves evaluating the information loss of removing a well from the network. If one well has a small SF, it may or may not be eliminated depending on whether the information loss is significant. If the information loss is not significant, the well can be eliminated from the monitoring network and the process of optimization continues with fewer wells. However if the well information loss is significant then the optimization terminates. This sampling optimization process allows the user to assess “redundant” wells that will not incur significant information loss on a constituent-by-constituent basis for individual sampling events.

### 7.2 Well Sufficiency Analysis – Delaunay Method

The well sufficiency analysis, using the Delaunay method, is designed to recommend new sampling locations in areas *within* the existing monitoring network where there is a high level of uncertainty in contaminant concentration. Details about the well sufficiency analysis can be found in Appendix A.2 of the MAROS Manual (AFCEE, 2003).

In many cases, new sampling locations need to be added to the existing network to enhance the spatial plume characterization. If the MAROS algorithm calculates a high

level of uncertainty in predicting the constituent concentration for a particular area, a new sampling location is recommended. The Slope Factor (SF) values obtained from the redundancy evaluation described above are used to calculate the concentration estimation error for each triangle area formed in the Delaunay triangulation. The estimated SF value for each area is then classified into four levels: Small, Moderate, Large, or Extremely large (S, M, L, E) because the larger the estimated SF value, the higher the estimation error at this area. Therefore, the triangular areas with the estimated SF value at the Extremely large or Large level can be candidate regions for new sampling locations.

The results from the Delaunay method and the method for determining new sampling locations are derived solely from the spatial configuration of the monitoring network and the spatial pattern of the contaminant plume. No parameters such as the hydrogeologic conditions are considered in the analysis. Therefore, professional judgment and regulatory considerations must be used to make final decisions.

### 7.3 Sampling Frequency Determination - Modified CES Method

The Modified CES method optimizes sampling frequency for each sampling location based on the magnitude, direction, and uncertainty of its concentration trend derived from its recent and historical monitoring records. The Modified Cost Effective Sampling (MCES) estimates a conservative lowest-frequency sampling schedule for a given groundwater monitoring location that still provides needed information for regulatory and remedial decision-making. The MCES method was developed on the basis of the Cost Effective Sampling (CES) method developed by Ridley et al (1995). Details about the MCES method can be found in Appendix A.9 of the MAROS Manual (AFCEE, 2003).

In order to estimate the least frequent sampling schedule for a monitoring location that still provides enough information for regulatory and remedial decision-making, MCES employs three steps to determine the sampling frequency. The first step involves analyzing frequency based on recent trends. A preliminary location sampling frequency (PLSF) is developed based on the rate of change of well concentrations calculated by linear regression along with the Mann-Kendall trend analysis of the most recent monitoring data (see Figure 3). The variability within the sequential sampling data is accounted for by the Mann-Kendall analysis. The rate of change vs. trend result matrix categorizes wells as requiring annual, semi-annual or quarterly sampling. The PLSF is then reevaluated and adjusted based on overall trends. If the long-term history of change is significantly greater than the recent trend, the frequency may be reduced by one level.

The final step in the analysis involves reducing frequency based on risk, site-specific conditions, regulatory requirements or other external issues. Since not all compounds in the target being assessed are equally harmful, frequency is reduced by one level if recent maximum concentration for a compound of high risk is less than 1/2 of the Maximum Concentration Limit (MCL). The result of applying this method is a suggested sampling frequency based on recent sampling data trends and overall sampling data trends and expert judgment.

The final sampling frequency determined from the MCES method can be Quarterly, Semiannual, Annual, or Biennial. Users can further reduce the sampling frequency to, for example, once every three years, if the trend estimated from Biennial data (i.e., data drawn once every two years from the original data) is the same as that estimated from the original data.

#### 7.4 Data Sufficiency Analysis – Power Analysis


The MAROS Data Sufficiency module employs simple statistical methods to evaluate whether the collected data are adequate both in quantity and in quality for revealing changes in constituent concentrations. The first section of the module evaluates individual well concentrations to determine if they are statistically below a target screening level. The second section includes a simple calculation for estimating projected groundwater concentrations at a specified point downgradient of the plume. A statistical Power analysis is then applied to the projected concentrations to determine if the downgradient concentrations are statistically below the cleanup standard. If the number of projected concentrations is below the level to provide statistical significance, then the number of sample events required to statistically confirm concentrations below standards is estimated from the Power analysis.

Before testing the cleanup status for individual wells, the stability or trend of the contaminant plume should be evaluated. Only after the plume has reached stability or is reliably diminishing can we conduct a test to examine the cleanup status of wells. Applying the analysis to wells in an expanding plume may cause incorrect conclusions and is less meaningful.

Statistical power analysis is a technique for interpreting the results of statistical tests. The Power of a statistical test is a measure of the ability of the test to detect an effect given that the effect actually exists. The method provides additional information about a statistical test: 1) the power of the statistical test, i.e., the probability of finding a difference in the variable of interest when a difference truly exists; and 2) the expected sample size of a future sampling plan given the minimum detectable difference it is supposed to detect. For example, if the mean concentration is lower than the cleanup goal but a statistical test cannot prove this, the power and expected sample size can tell the reason and how many more samples are needed to result in a significant test. The additional samples can be obtained by a longer period of sampling or an increased sampling frequency. Details about the data sufficiency analysis can be found in Appendix A.6 of the MAROS Manual (AFCEE, 2003).

When applying the MAROS power analysis method, a hypothetical statistical compliance boundary (HSCB) is assigned to be a line perpendicular to the groundwater flow direction (see figure below). Monitoring well concentrations are projected onto the HSCB using the distance from each well to the compliance boundary along with a decay coefficient. The projected concentrations from each well and each sampling event are then used in the risk-based power analysis. Since there may be more than one sampling event selected by the user, the risk-based power analysis results are given on an event-

by-event basis. This power analysis can then indicate if target are statistically achieved at the HSCB. For instance, at a site where the historical monitoring record is short with few wells, the HSCB would be distant; whereas, at a site with longer duration of sampling with many wells, the HSCB would be close. Ultimately, at a site the goal would be to have the HSCB coincide with or be within the actual compliance boundary (typically the site property line).



In order to perform a risk-based cleanup status evaluation for the whole site, a strategy was developed as follows.

- Estimate concentration versus distance decay coefficient from plume centerline wells.
- Extrapolate concentration versus distance for each well using this decay coefficient.
- Comparing the extrapolated concentrations with the compliance concentration using power analysis.

Results from this analysis can be *Attained* or *Not Attained*, providing a statistical interpretation of whether the cleanup goal has been met on the site-scale from the risk-based point of view. The results as a function of time can be used to evaluate if the monitoring system has enough power at each step in the sampling record to indicate certainty of compliance by the plume location and condition relative to the compliance boundary. For example, if results are *Not Attained* at early sampling events but are *Attained* in recent sampling events, it indicates that the recent sampling record provides a powerful enough result to indicate compliance of the plume relative to the location of the receptor or compliance boundary.

## CITED REFERENCES

AFCEE 2003. Monitoring and Remediation Optimization System (MAROS) 2.1 Software Users Guide. Air Force Center for Environmental Excellence. [http://www.gsi-net.com/software/MAROS\\_V2\\_1Manual.pdf](http://www.gsi-net.com/software/MAROS_V2_1Manual.pdf)

AFCEE. 1997. Air Force Center for Environmental Excellence, AFCEE Long-Term Monitoring Optimization Guide, <http://www.afcee.brooks.af.mil>.

Aziz, J. A., C. J. Newell, M. Ling, H. S. Rifai and J. R. Gonzales (2003). "MAROS: A Decision Support System for Optimizing Monitoring Plans." Ground Water **41**(3): 355-367.

Gilbert, R. O., 1987, Statistical Methods for Environmental Pollution Monitoring, Van Nostrand Reinhold, New York, NY, ISBN 0-442-23050-8.

Hollander, M. and Wolfe, D. A. (1973). Nonparametric Statistical Methods, Wiley, New York, NY.

Ridley, M.N. et al., 1995. Cost-Effective Sampling of Groundwater Monitoring Wells, the Regents of UC/LLNL, Lawrence Livermore National Laboratory.

U.S. Environmental Protection Agency, 1992. Methods for Evaluating the Attainment of Cleanup Standards Volume 2: Ground Water.

Weight, W. D. and J. L. Sonderegger (2001). Manual of Applied Field Hydrogeology. New York, NY, McGraw-Hill.





<b>TABLE 1</b> <b>Mann-Kendall Analysis Decision Matrix (Aziz, et. al., 2003)</b>		
<b>Mann-Kendall Statistic</b>	<b>Confidence in the Trend</b>	<b>Concentration Trend</b>
$S > 0$	> 95%	Increasing
$S > 0$	90 - 95%	Probably Increasing
$S > 0$	< 90%	No Trend
$S \leq 0$	< 90% and $COV \geq 1$	No Trend
$S \leq 0$	< 90% and $COV < 1$	Stable
$S < 0$	90 - 95%	Probably Decreasing
$S < 0$	> 95%	Decreasing

<b>TABLE 2</b> <b>Linear Regression Analysis Decision Matrix (Aziz, et. al., 2003)</b>		
<b>Confidence in the Trend</b>	<b>Log-slope</b>	
	<b>Positive</b>	<b>Negative</b>
< 90%	No Trend	$COV < 1$ Stable
		$COV > 1$ No Trend
90 - 95%	Probably Increasing	Probably Decreasing
> 95%	Increasing	Decreasing



## MAROS: Decision Support Tool

MAROS is a collection of tools in one software package that is used in an explanatory, non-linear fashion. The tool includes models, geostatistics, heuristic rules, and empirical relationships to assist the user in optimizing a groundwater monitoring network system while maintaining adequate delineation of the plume as well as knowledge of the plume state over time. Different users utilize the tool in different ways and interpret the results from a different viewpoint.



### Overview Statistics

**What it is:** Simple, qualitative and quantitative plume information can be gained through evaluation of monitoring network historical data trends both spatially and temporally. The MAROS Overview Statistics are the foundation the user needs to make informed optimization decisions at the site.

**What it does:** The Overview Statistics are designed to allow site personnel to develop a better understanding of the plume behavior over time and understand how the individual well concentration trends are spatially distributed within the plume. This step allows the user to gain information that will support a more informed decision to be made in the next level of optimization analysis.

**What are the tools:** Overview Statistics includes two analytical tools:

- 1) **Trend Analysis:** includes Mann-Kendall and Linear Regression statistics for individual wells and results in general heuristically-derived monitoring categories with a suggested sampling density and monitoring frequency.
- 2) **Moment Analysis:** includes dissolved mass estimation (0<sup>th</sup> Moment), center of mass (1<sup>st</sup> Moment), and plume spread (2<sup>nd</sup> Moment) over time. Trends of these moments show the user another piece of information about the plume stability over time.

**What is the product:** A first-cut blueprint for a future long-term monitoring program that is intended to be a foundation for more detailed statistical analysis.



### Detailed Statistics

**What it is:** The MAROS Detailed Statistics allows for a quantitative analysis for spatial and temporal optimization of the well network on a well-by-well basis.


**What it does:** The results from the Overview Statistics should be considered along side the MAROS optimization recommendations gained from the Detailed Statistical Analysis. The MAROS Detailed Statistics results should be reassessed in view of site knowledge and regulatory requirements as well as the Overview Statistics.

**What are the tools:** Detailed Statistics includes four analytical tools:

- 1) **Sampling Frequency Optimization:** uses the Modified CES method to establish a recommended future sampling frequency.
- 2) **Well Redundancy Analysis:** uses the Delaunay Method to evaluate if any wells within the monitoring network are redundant and can be eliminated without any significant loss of plume information.
- 3) **Well Sufficiency Analysis:** uses the Delaunay Method to evaluate areas where new wells are recommended within the monitoring network due to high levels of concentration uncertainty.
- 4) **Data Sufficiency Analysis:** uses Power Analysis to assess if the historical monitoring data record has sufficient power to accurately reflect the location of the plume relative to the nearest receptor or compliance point.

**What is the product:** List of wells to remove from the monitoring program, locations where monitoring wells may need to be added, recommended frequency of sampling for each well, analysis if the overall system is statistically powerful to monitor the plume.

Figure 1. MAROS Decision Support Tool Flow Chart



**Figure 2:**  
MAROS Overview Statistics Trend Analysis Methodology




Figure 3. Decision Matrix for Determining Provisional Frequency (Figure A.3.1 of the MAROS Manual (AFCEE 2003))

**Attachment C**  
**MAROS Reports**

March 22, 2007

**LONG-TERM  
MONITORING NETWORK OPTIMIZATION  
PRB AND SOIL REMEDY AREAS**

Clare Water Supply Superfund Site  
Clare, Michigan

**ATTACHMENT C:**

---

**MAROS Reports**

*PRB Area:*

COC Assessment Report  
Mann-Kendall Reports Selected Wells  
(Including data from November 2006 monitoring event)

*Soil Remedy Area:*

COC Assessment Report  
Mann-Kendall Reports Selected Wells

# MAROS COC Assessment

**Project:** Clare Water Supply

**User Name:** MV

**Location:** Clare

**State:** Michigan

## Toxicity:

Contaminant of Concern	Representative Concentration (mg/L)	PRG (mg/L)	Percent Above PRG
VINYL CHLORIDE	1.2E-01	1.5E-02	713.2%
cis-1,2-DICHLOROETHYLENE	6.9E-02	6.1E-02	12.9%

Note: Top COCs by toxicity were determined by examining a representative concentration for each compound over the entire site. The compound representative concentrations are then compared with the chosen PRG for that compound, with the percentage exceedence from the PRG determining the compound's toxicity. All compounds above exceed the PRG.

## Prevalence:

Contaminant of Concern	Class	Total Wells	Total Excedences	Percent Excedences	Total detects
VINYL CHLORIDE	ORG	16	10	62.5%	15
cis-1,2-DICHLOROETHYLENE	ORG	16	3	18.8%	13

Note: Top COCs by prevalence were determined by examining a representative concentration for each well location at the site. The total exceedences (values above the chosen PRGs) are compared to the total number of wells to determine the prevalence of the compound.

## Mobility:

Contaminant of Concern	Kd
VINYL CHLORIDE	0.042
cis-1,2-DICHLOROETHYLENE	0.0724

Note: Top COCs by mobility were determined by examining each detected compound in the dataset and comparing their mobilities (Koc's for organics, assume foc = 0.001, and Kd's for metals).

## **Contaminants of Concern (COC's)**

---

VINYL CHLORIDE

cis-1,2-DICHLOROETHYLENE

# MAROS Statistical Trend Analysis Summary

**Project:** Clare

**User Name:** MV

**Location:** Clare

**State:** Michigan

**Time Period:** 3/23/1994 to 11/10/2006

**Consolidation Period:** No Time Consolidation

**Consolidation Type:** Median

**Duplicate Consolidation:** Average

**ND Values:** Specified Detection Limit

**J Flag Values :** Actual Value

Well	Source/ Tail	Number of Samples	Number of Detects	Average Conc. (mg/L)	Median Conc. (mg/L)	All Samples "ND" ?	Mann- Kendall Trend	Linear Regression Trend
<b>cis-1,2-DICHLOROETHYLENE</b>								
220	T	31	6	1.3E-03	5.0E-04	No	NT	NT
300A	S	15	15	4.1E-01	2.7E-01	No	S	NT
300B	S	13	13	5.6E-03	5.5E-03	No	I	I
300C	S	13	2	5.8E-04	5.0E-04	No	S	S
MW-301	T	5	3	8.8E-04	7.3E-04	No	S	S
MW-302	S	5	4	4.0E-02	3.1E-02	No	D	PD
MW-303	T	5	5	4.9E-01	6.1E-02	No	NT	D
MW-304	T	5	5	4.8E-03	4.6E-03	No	S	S
MW-305	S	5	5	1.2E-01	1.1E-01	No	S	S
MW-306	T	5	2	1.2E-03	5.0E-04	No	NT	NT
Mw-307	T	5	0	5.0E-04	5.0E-04	Yes	S	I
MW-308	T	5	5	8.4E-03	5.8E-03	No	S	S
Mw-309	T	5	5	3.3E-03	2.4E-03	No	NT	S
MW-310	T	5	1	6.6E-04	5.0E-04	No	S	S
MW-311	T	5	5	2.0E-02	8.9E-03	No	NT	NT
MW-312	T	5	1	5.4E-04	5.0E-04	No	S	S
MW-313	T	5	1	6.0E-04	5.0E-04	No	NT	NT
SW-11	T	10	0	5.0E-04	5.0E-04	Yes	S	D
SW-12	T	12	0	5.0E-04	5.0E-04	Yes	S	D
<b>VINYL CHLORIDE</b>								
220	T	35	1	9.8E-04	1.0E-03	No	S	PD
300A	S	16	16	8.8E-01	7.2E-01	No	I	PI
300B	S	14	14	6.1E-02	3.6E-02	No	I	I
300C	S	14	9	8.0E-03	1.3E-03	No	I	I
MW-301	T	6	5	1.2E-03	1.3E-03	No	S	D
MW-302	S	6	6	6.8E-02	5.7E-02	No	S	NT
MW-303	T	6	6	5.2E-01	1.2E-01	No	D	D
MW-304	T	6	6	2.0E-02	1.9E-02	No	PD	D
MW-305	S	6	6	1.5E-01	1.5E-01	No	S	NT
MW-306	T	6	6	4.5E-03	2.3E-03	No	D	D
Mw-307	T	6	5	1.1E-02	9.1E-03	No	S	S
MW-308	T	6	6	3.8E-02	3.6E-02	No	S	S
Mw-309	T	6	6	2.1E-02	1.7E-02	No	S	D
MW-310	T	6	6	1.7E-02	2.0E-02	No	NT	NT



# MAROS Statistical Trend Analysis Summary

Well	Source/ Tail	Number of Samples	Number of Detects	Average Conc. (mg/L)	Median Conc. (mg/L)	All Samples "ND" ?	Mann- Kendall Trend	Linear Regression Trend
VINYL CHLORIDE								
MW-311	T	6	6	2.8E-02	2.2E-02	No	S	PD
MW-312	T	6	0	1.0E-03	1.0E-03	Yes	S	S
MW-313	T	6	1	9.6E-04	1.0E-03	No	NT	NT
SW-11	T	12	0	1.0E-03	1.0E-03	Yes	S	S
SW-12	T	14	1	1.0E-03	1.0E-03	No	S	D


Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); No Detectable Concentration (NDC)

The Number of Samples and Number of Detects shown above are post-consolidation values.

# MAROS Mann-Kendall Statistics Summary

Well: 300A  
 Well Type: S  
 COC: VINYL CHLORIDE

Time Period: to  
 Consolidation Period: Other  
 Consolidation Type: Maximum  
 Duplicate Consolidation: First  
 ND Values: Specified Detection Limit  
 J Flag Values : Fraction of Actual Value



Mann Kendall S Statistic:

41

Confidence in Trend:

96.5%

Coefficient of Variation:

0.75

Mann Kendall Concentration Trend: (See Note)

I

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
300A	S	12/12/1999	VINYL CHLORIDE	2.9E-01		2	2
300A	S	6/28/2000	VINYL CHLORIDE	3.3E-01		1	1
300A	S	12/6/2000	VINYL CHLORIDE	6.6E-01		1	1
300A	S	10/30/2001	VINYL CHLORIDE	3.9E-01		1	1
300A	S	5/1/2002	VINYL CHLORIDE	7.0E-01		2	2
300A	S	10/29/2002	VINYL CHLORIDE	7.3E-01		1	1
300A	S	4/22/2003	VINYL CHLORIDE	9.8E-01		1	1
300A	S	10/21/2003	VINYL CHLORIDE	9.0E-01		1	1
300A	S	4/27/2004	VINYL CHLORIDE	9.4E-01		1	1
300A	S	10/27/2004	VINYL CHLORIDE	9.4E-01		1	1
300A	S	5/24/2005	VINYL CHLORIDE	1.4E+00		1	1
300A	S	8/11/2005	VINYL CHLORIDE	1.5E+00		1	1
300A	S	11/9/2005	VINYL CHLORIDE	3.0E+00		2	2
300A	S	3/15/2006	VINYL CHLORIDE	5.5E-01		1	1
300A	S	5/15/2006	VINYL CHLORIDE	6.1E-01		1	1
300A	S	11/15/2006	VINYL CHLORIDE	2.2E-01		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: 300B  
 Well Type: S  
 COC: VINYL CHLORIDE

Time Period: to  
 Consolidation Period: Other  
 Consolidation Type: Maximum  
 Duplicate Consolidation: First  
 ND Values: Specified Detection Limit  
 J Flag Values : Fraction of Actual Value



Mann Kendall S Statistic:

71

Confidence in Trend:

100.0%

Coefficient of Variation:

1.02

Mann Kendall Concentration Trend: (See Note)

I

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
300B	S	12/12/1999	VINYL CHLORIDE	1.4E-02		1	1
300B	S	6/28/2000	VINYL CHLORIDE	2.0E-02		1	1
300B	S	12/6/2000	VINYL CHLORIDE	7.2E-03		1	1
300B	S	10/30/2001	VINYL CHLORIDE	3.6E-03		1	1
300B	S	5/1/2002	VINYL CHLORIDE	1.0E-02		1	1
300B	S	10/29/2002	VINYL CHLORIDE	2.4E-02		1	1
300B	S	4/22/2003	VINYL CHLORIDE	3.4E-02		1	1
300B	S	10/21/2003	VINYL CHLORIDE	3.7E-02		1	1
300B	S	4/27/2004	VINYL CHLORIDE	6.2E-02		1	1
300B	S	10/27/2004	VINYL CHLORIDE	4.8E-02		1	1
300B	S	5/24/2005	VINYL CHLORIDE	1.1E-01		1	1
300B	S	11/9/2005	VINYL CHLORIDE	1.4E-01		1	1
300B	S	5/15/2006	VINYL CHLORIDE	2.0E-01		1	1
300B	S	11/15/2006	VINYL CHLORIDE	1.4E-01		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: 300C  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: to  
 Consolidation Period: Other  
 Consolidation Type: Maximum  
 Duplicate Consolidation: First  
 ND Values: Specified Detection Limit  
 J Flag Values : Fraction of Actual Value



Mann Kendall S Statistic:

48

Confidence in Trend:

99.6%

Coefficient of Variation:

1.27

Mann Kendall Concentration Trend: (See Note)

I

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
300C	T	12/12/1999	VINYL CHLORIDE	1.0E-03	ND	1	0
300C	T	7/21/2000	VINYL CHLORIDE	7.3E-04		1	1
300C	T	12/6/2000	VINYL CHLORIDE	2.9E-04		1	1
300C	T	10/30/2001	VINYL CHLORIDE	1.0E-03	ND	1	0
300C	T	5/1/2002	VINYL CHLORIDE	1.0E-03	ND	1	0
300C	T	10/29/2002	VINYL CHLORIDE	3.2E-03		1	1
300C	T	4/22/2003	VINYL CHLORIDE	1.0E-03	ND	1	0
300C	T	10/21/2003	VINYL CHLORIDE	1.3E-02		1	1
300C	T	4/27/2004	VINYL CHLORIDE	1.6E-03		1	1
300C	T	10/27/2004	VINYL CHLORIDE	2.4E-02		1	1
300C	T	5/24/2005	VINYL CHLORIDE	2.4E-02		1	1
300C	T	11/9/2005	VINYL CHLORIDE	2.7E-02		1	1
300C	T	5/15/2006	VINYL CHLORIDE	1.0E-03	ND	1	0
300C	T	11/15/2006	VINYL CHLORIDE	1.3E-02		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-303  
 Well Type: S  
 COC: VINYL CHLORIDE

Time Period: to  
 Consolidation Period: Other  
 Consolidation Type: Maximum  
 Duplicate Consolidation: First  
 ND Values: Specified Detection Limit  
 J Flag Values : Fraction of Actual Value



Mann Kendall S Statistic:

-11

Confidence in Trend:

97.2%

Coefficient of Variation:

1.29

Mann Kendall Concentration Trend: (See Note)

D

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-303	S	5/24/2005	VINYL CHLORIDE	1.6E+00		1	1
MW-303	S	8/11/2005	VINYL CHLORIDE	1.1E+00		1	1
MW-303	S	11/9/2005	VINYL CHLORIDE	9.1E-02		1	1
MW-303	S	3/15/2006	VINYL CHLORIDE	1.2E-01		1	1
MW-303	S	5/15/2006	VINYL CHLORIDE	1.1E-01		1	1
MW-303	S	11/15/2006	VINYL CHLORIDE	7.6E-02		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-304  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: to  
 Consolidation Period: Other  
 Consolidation Type: Maximum  
 Duplicate Consolidation: First  
 ND Values: Specified Detection Limit  
 J Flag Values : Fraction of Actual Value



Mann Kendall S Statistic:

-9

Confidence in Trend:

93.2%

Coefficient of Variation:

0.68

Mann Kendall Concentration Trend: (See Note)

PD

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-304	T	5/24/2005	VINYL CHLORIDE	4.1E-02		1	1
MW-304	T	8/11/2005	VINYL CHLORIDE	2.8E-02		1	1
MW-304	T	11/9/2005	VINYL CHLORIDE	8.5E-03		1	1
MW-304	T	3/15/2006	VINYL CHLORIDE	1.8E-02		1	1
MW-304	T	5/15/2006	VINYL CHLORIDE	2.0E-02		1	1
MW-304	T	11/15/2006	VINYL CHLORIDE	3.7E-03		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-305  
 Well Type: S  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 11/15/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-2

Confidence in Trend:

57.0%

Coefficient of Variation:

0.63

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-305	S	5/24/2005	VINYL CHLORIDE	2.4E-01		1	1
MW-305	S	8/11/2005	VINYL CHLORIDE	6.8E-02		1	1
MW-305	S	11/9/2005	VINYL CHLORIDE	2.3E-02		1	1
MW-305	S	3/15/2006	VINYL CHLORIDE	2.4E-01		1	1
MW-305	S	5/15/2006	VINYL CHLORIDE	1.9E-01		1	1
MW-305	S	11/15/2006	VINYL CHLORIDE	1.1E-01		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-306  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: to  
 Consolidation Period: Other  
 Consolidation Type: Maximum  
 Duplicate Consolidation: First  
 ND Values: Specified Detection Limit  
 J Flag Values : Fraction of Actual Value



Mann Kendall S Statistic:

-13

Confidence in Trend:

99.2%

Coefficient of Variation:

1.17

Mann Kendall Concentration Trend: (See Note)

D

## Data Table:

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-306	T	5/24/2005	VINYL CHLORIDE	1.5E-02		1	1
MW-306	T	8/11/2005	VINYL CHLORIDE	4.4E-03		1	1
MW-306	T	11/9/2005	VINYL CHLORIDE	2.4E-03		1	1
MW-306	T	3/15/2006	VINYL CHLORIDE	2.0E-03		1	1
MW-306	T	5/15/2006	VINYL CHLORIDE	2.1E-03		1	1
MW-306	T	11/15/2006	VINYL CHLORIDE	1.1E-03		1	1


Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect



# MAROS Mann-Kendall Statistics Summary

Well: Mw-307  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: to  
 Consolidation Period: Other  
 Consolidation Type: Maximum  
 Duplicate Consolidation: First  
 ND Values: Specified Detection Limit  
 J Flag Values : Fraction of Actual Value



Mann Kendall S Statistic:

-5

Confidence in Trend:

76.5%

Coefficient of Variation:

0.99

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
Mw-307	T	5/24/2005	VINYL CHLORIDE	3.3E-02		1	1
Mw-307	T	8/11/2005	VINYL CHLORIDE	1.1E-02		1	1
Mw-307	T	11/9/2005	VINYL CHLORIDE	1.0E-03	ND	1	0
Mw-307	T	3/15/2006	VINYL CHLORIDE	5.0E-03		1	1
Mw-307	T	5/15/2006	VINYL CHLORIDE	1.0E-02		1	1
Mw-307	T	11/15/2006	VINYL CHLORIDE	8.1E-03		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-308  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: to  
 Consolidation Period: Other  
 Consolidation Type: Maximum  
 Duplicate Consolidation: First  
 ND Values: Specified Detection Limit  
 J Flag Values : Fraction of Actual Value



Mann Kendall S Statistic:

-3

Confidence in Trend:

64.0%

Coefficient of Variation:

0.45

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-308	T	5/24/2005	VINYL CHLORIDE	5.5E-02		1	1
MW-308	T	8/11/2005	VINYL CHLORIDE	2.6E-02		1	1
MW-308	T	11/9/2005	VINYL CHLORIDE	2.3E-02		1	1
MW-308	T	3/15/2006	VINYL CHLORIDE	4.5E-02		1	1
MW-308	T	5/15/2006	VINYL CHLORIDE	5.8E-02		1	1
MW-308	T	11/15/2006	VINYL CHLORIDE	2.0E-02		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: Mw-309  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: to  
 Consolidation Period: Other  
 Consolidation Type: Maximum  
 Duplicate Consolidation: First  
 ND Values: Specified Detection Limit  
 J Flag Values : Fraction of Actual Value



Mann Kendall S Statistic:

-3

Confidence in Trend:

64.0%

Coefficient of Variation:

0.75

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
Mw-309	T	5/24/2005	VINYL CHLORIDE	4.8E-02		1	1
Mw-309	T	8/11/2005	VINYL CHLORIDE	1.4E-02		1	1
Mw-309	T	11/9/2005	VINYL CHLORIDE	1.6E-02		1	1
Mw-309	T	3/15/2006	VINYL CHLORIDE	1.8E-02		1	1
Mw-309	T	5/15/2006	VINYL CHLORIDE	2.5E-02		1	1
Mw-309	T	11/15/2006	VINYL CHLORIDE	2.2E-03		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS COC Assessment

**Project:** Soil Remedy

**User Name:** MV

**Location:** Clare

**State:** Michigan

## Toxicity:

Contaminant of Concern	Representative Concentration (mg/L)	PRG (mg/L)	Percent Above PRG
TRICHLOROETHYLENE (TCE)	5.3E-03	5.0E-03	6.9%

Note: Top COCs by toxicity were determined by examining a representative concentration for each compound over the entire site. The compound representative concentrations are then compared with the chosen PRG for that compound, with the percentage exceedence from the PRG determining the compound's toxicity. All compounds above exceed the PRG.

## Prevalence:

Contaminant of Concern	Class	Total Wells	Total Excedences	Percent Excedences	Total detects
TRICHLOROETHYLENE (TCE)	ORG	8	2	25.0%	5

Note: Top COCs by prevalence were determined by examining a representative concentration for each well location at the site. The total exceedences (values above the chosen PRGs) are compared to the total number of wells to determine the prevalence of the compound.

## Mobility:

Contaminant of Concern	Kd
TRICHLOROETHYLENE (TCE)	0.297

Note: Top COCs by mobility were determined by examining each detected compound in the dataset and comparing their mobilities (Koc's for organics, assume foc = 0.001, and Kd's for metals).

## **Contaminants of Concern (COC's)**

---

VINYL CHLORIDE


TRICHLOROETHYLENE (TCE)

cis-1,2-DICHLOROETHYLENE

# MAROS Mann-Kendall Statistics Summary

Well: UMW-1S  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

0

Confidence in Trend:

48.0%

Coefficient of Variation:

0.00

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
UMW-1S	T	3/24/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	6/23/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	10/30/2001	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	5/1/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	10/28/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: DMW-1S  
 Well Type: S  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 3/24/1999 to 5/16/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-93

Confidence in Trend:

100.0%

Coefficient of Variation:

1.61

Mann Kendall Concentration Trend: (See Note)

D

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-1S	S	3/24/1999	TRICHLOROETHYLENE (TCE)	9.9E-02		1	1
DMW-1S	S	6/23/1999	TRICHLOROETHYLENE (TCE)	6.7E-02		1	1
DMW-1S	S	12/21/1999	TRICHLOROETHYLENE (TCE)	1.4E-02		1	1
DMW-1S	S	6/28/2000	TRICHLOROETHYLENE (TCE)	1.3E-02		1	1
DMW-1S	S	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-02		1	1
DMW-1S	S	10/30/2001	TRICHLOROETHYLENE (TCE)	9.0E-03		1	1
DMW-1S	S	5/1/2002	TRICHLOROETHYLENE (TCE)	7.0E-03		1	1
DMW-1S	S	10/28/2002	TRICHLOROETHYLENE (TCE)	7.0E-03		1	1
DMW-1S	S	4/22/2003	TRICHLOROETHYLENE (TCE)	9.0E-03		1	1
DMW-1S	S	10/21/2003	TRICHLOROETHYLENE (TCE)	4.0E-03		1	1
DMW-1S	S	4/27/2004	TRICHLOROETHYLENE (TCE)	4.0E-03		1	1
DMW-1S	S	10/26/2004	TRICHLOROETHYLENE (TCE)	4.0E-03		1	1
DMW-1S	S	5/20/2005	TRICHLOROETHYLENE (TCE)	4.0E-03		1	1
DMW-1S	S	11/8/2005	TRICHLOROETHYLENE (TCE)	3.2E-03		1	1
DMW-1S	S	5/16/2006	TRICHLOROETHYLENE (TCE)	2.9E-03		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: DMW-1S  
 Well Type: S  
 COC: cis-1,2-DICHLOROETHYLENE

Time Period: 3/24/1999 to 5/16/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-19

Confidence in Trend:

81.0%

Coefficient of Variation:

1.62

Mann Kendall Concentration Trend: (See Note)

NT

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-1S	S	3/24/1999	cis-1,2-DICHLOROETHYLENE	2.4E-02		1	1
DMW-1S	S	6/23/1999	cis-1,2-DICHLOROETHYLENE	8.0E-03		1	1
DMW-1S	S	12/21/1999	cis-1,2-DICHLOROETHYLENE	4.0E-03		1	1
DMW-1S	S	6/28/2000	cis-1,2-DICHLOROETHYLENE	3.0E-03		1	1
DMW-1S	S	12/6/2000	cis-1,2-DICHLOROETHYLENE	2.3E-02		1	1
DMW-1S	S	10/30/2001	cis-1,2-DICHLOROETHYLENE	6.7E-02		1	1
DMW-1S	S	5/1/2002	cis-1,2-DICHLOROETHYLENE	6.0E-03		1	1
DMW-1S	S	10/28/2002	cis-1,2-DICHLOROETHYLENE	1.8E-01		1	1
DMW-1S	S	4/22/2003	cis-1,2-DICHLOROETHYLENE	2.0E-02		1	1
DMW-1S	S	10/21/2003	cis-1,2-DICHLOROETHYLENE	9.0E-03		1	1
DMW-1S	S	4/27/2004	cis-1,2-DICHLOROETHYLENE	5.0E-03		1	1
DMW-1S	S	10/26/2004	cis-1,2-DICHLOROETHYLENE	9.3E-02		1	1
DMW-1S	S	5/20/2005	cis-1,2-DICHLOROETHYLENE	5.9E-03		1	1
DMW-1S	S	11/8/2005	cis-1,2-DICHLOROETHYLENE	5.5E-03		1	1
DMW-1S	S	5/16/2006	cis-1,2-DICHLOROETHYLENE	2.9E-03		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: DMW-2S  
 Well Type: S  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 3/24/1999 to 5/16/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-45

Confidence in Trend:

99.3%

Coefficient of Variation:

0.95

Mann Kendall Concentration Trend: (See Note)

D

## Data Table:

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-2S	S	3/24/1999	TRICHLOROETHYLENE (TCE)	5.0E-03		1	1
DMW-2S	S	6/23/1999	TRICHLOROETHYLENE (TCE)	7.0E-03		1	1
DMW-2S	S	12/21/1999	TRICHLOROETHYLENE (TCE)	2.0E-03		1	1
DMW-2S	S	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	10/30/2001	TRICHLOROETHYLENE (TCE)	2.0E-03		1	1
DMW-2S	S	5/1/2002	TRICHLOROETHYLENE (TCE)	1.0E-03		1	1
DMW-2S	S	10/28/2002	TRICHLOROETHYLENE (TCE)	2.0E-03		1	1
DMW-2S	S	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	5/20/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	5/16/2006	TRICHLOROETHYLENE (TCE)	7.9E-04		1	1


Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect



# MAROS Mann-Kendall Statistics Summary

Well: DMW-3S  
 Well Type: S  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 3/24/1999 to 5/16/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-35

Confidence in Trend:

95.4%

Coefficient of Variation:

0.58

Mann Kendall Concentration Trend: (See Note)

D

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-3S	S	3/24/1999	TRICHLOROETHYLENE (TCE)	3.1E-02		1	1
DMW-3S	S	6/23/1999	TRICHLOROETHYLENE (TCE)	4.8E-02		1	1
DMW-3S	S	12/21/1999	TRICHLOROETHYLENE (TCE)	1.5E-02		1	1
DMW-3S	S	6/28/2000	TRICHLOROETHYLENE (TCE)	3.0E-02		1	1
DMW-3S	S	12/6/2000	TRICHLOROETHYLENE (TCE)	2.1E-02		1	1
DMW-3S	S	10/30/2001	TRICHLOROETHYLENE (TCE)	3.1E-02		1	1
DMW-3S	S	5/1/2002	TRICHLOROETHYLENE (TCE)	3.6E-02		1	1
DMW-3S	S	10/28/2002	TRICHLOROETHYLENE (TCE)	6.0E-03		1	1
DMW-3S	S	4/22/2003	TRICHLOROETHYLENE (TCE)	2.3E-02		1	1
DMW-3S	S	10/21/2003	TRICHLOROETHYLENE (TCE)	8.0E-03		1	1
DMW-3S	S	4/27/2004	TRICHLOROETHYLENE (TCE)	1.2E-02		1	1
DMW-3S	S	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-02		1	1
DMW-3S	S	5/20/2005	TRICHLOROETHYLENE (TCE)	4.5E-03		1	1
DMW-3S	S	11/8/2005	TRICHLOROETHYLENE (TCE)	2.2E-02		1	1
DMW-3S	S	5/16/2006	TRICHLOROETHYLENE (TCE)	2.3E-02		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: DMW-1D  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

8

Confidence in Trend:

63.3%

Coefficient of Variation:

0.00

Mann Kendall Concentration Trend: (See Note)

NT

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-1D	T	3/24/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	6/23/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	1
DMW-1D	T	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	10/30/2001	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	5/1/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	10/28/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: UMW-1D  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

0

Confidence in Trend:

48.0%

Coefficient of Variation:

0.00

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
UMW-1D	T	3/24/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	6/23/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	10/30/2001	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	5/1/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	10/28/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: DMW-2D  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

0

Confidence in Trend:

48.0%

Coefficient of Variation:

0.00

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-2D	T	3/24/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	6/23/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	10/30/2001	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	5/1/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	10/28/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: DMW-3D  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

10

Confidence in Trend:

66.9%

Coefficient of Variation:

0.15

Mann Kendall Concentration Trend: (See Note)

NT

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-3D	T	3/24/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	6/23/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	10/30/2001	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	5/1/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	10/28/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.6E-03		1	1
DMW-3D	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: 215  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 6/1/1988 to 5/16/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-61

Confidence in Trend:

81.2%

Coefficient of Variation:

0.37

Mann Kendall Concentration Trend:  
 (See Note)

S

## Data Table:

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
215	T	3/21/1994	TRICHLOROETHYLENE (TCE)	1.0E-03		1	1
215	T	6/28/1994	TRICHLOROETHYLENE (TCE)	2.1E-03		2	2
215	T	9/21/1994	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	12/19/1994	TRICHLOROETHYLENE (TCE)	1.3E-03		1	1
215	T	3/21/1995	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	6/27/1995	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	9/19/1995	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	12/19/1995	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	3/26/1996	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	6/19/1996	TRICHLOROETHYLENE (TCE)	1.3E-03		1	1
215	T	9/17/1996	TRICHLOROETHYLENE (TCE)	7.4E-04		1	1
215	T	12/17/1996	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	3/25/1997	TRICHLOROETHYLENE (TCE)	5.5E-04		1	1
215	T	6/24/1997	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	9/23/1997	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	12/16/1997	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	3/24/1998	TRICHLOROETHYLENE (TCE)	4.0E-04		2	2
215	T	6/17/1998	TRICHLOROETHYLENE (TCE)	4.4E-04		1	1
215	T	10/1/1998	TRICHLOROETHYLENE (TCE)	3.8E-04		2	2
215	T	3/24/1999	TRICHLOROETHYLENE (TCE)	2.9E-04		1	1
215	T	6/23/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0

# MAROS Mann-Kendall Statistics Summary


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
215	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	12/6/2000	TRICHLOROETHYLENE (TCE)	6.5E-04		2	1
215	T	10/30/2001	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	5/1/2002	TRICHLOROETHYLENE (TCE)	1.4E-04		1	1
215	T	10/28/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: SW-9  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 6/1/1988 to 5/16/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

22

Confidence in Trend:

61.2%

Coefficient of Variation:

0.91

Mann Kendall Concentration Trend: (See Note)

NT

## Data Table:

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
SW-9	T	6/1/1988	TRICHLOROETHYLENE (TCE)	4.0E-03		1	1
SW-9	T	6/1/1989	TRICHLOROETHYLENE (TCE)	2.0E-03		1	1
SW-9	T	3/21/1994	TRICHLOROETHYLENE (TCE)	4.1E-03		1	1
SW-9	T	6/28/1994	TRICHLOROETHYLENE (TCE)	4.6E-03		2	2
SW-9	T	9/21/1994	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
SW-9	T	12/19/1994	TRICHLOROETHYLENE (TCE)	1.8E-03		1	1
SW-9	T	3/21/1995	TRICHLOROETHYLENE (TCE)	2.8E-03		1	1
SW-9	T	6/27/1995	TRICHLOROETHYLENE (TCE)	1.5E-03		2	1
SW-9	T	9/19/1995	TRICHLOROETHYLENE (TCE)	3.3E-03		1	1
SW-9	T	12/19/1995	TRICHLOROETHYLENE (TCE)	1.9E-03		1	1
SW-9	T	3/26/1996	TRICHLOROETHYLENE (TCE)	2.0E-03		1	1
SW-9	T	6/19/1996	TRICHLOROETHYLENE (TCE)	9.5E-04		2	1
SW-9	T	9/17/1996	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
SW-9	T	12/17/1996	TRICHLOROETHYLENE (TCE)	2.4E-03		1	1
SW-9	T	3/25/1997	TRICHLOROETHYLENE (TCE)	1.1E-03		1	1
SW-9	T	6/24/1997	TRICHLOROETHYLENE (TCE)	8.8E-04		3	3
SW-9	T	9/23/1997	TRICHLOROETHYLENE (TCE)	1.9E-03		1	1
SW-9	T	12/16/1997	TRICHLOROETHYLENE (TCE)	1.6E-03		1	1
SW-9	T	3/24/1998	TRICHLOROETHYLENE (TCE)	8.6E-04		1	1
SW-9	T	6/17/1998	TRICHLOROETHYLENE (TCE)	1.5E-03		1	1
SW-9	T	10/1/1998	TRICHLOROETHYLENE (TCE)	1.1E-03		2	2
SW-9	T	3/24/1999	TRICHLOROETHYLENE (TCE)	1.2E-02		1	1



# MAROS Mann-Kendall Statistics Summary

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
SW-9	T	6/23/1999	TRICHLOROETHYLENE (TCE)	9.2E-03		1	1
SW-9	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.2E-02		1	1
SW-9	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.1E-02		1	1
SW-9	T	12/6/2000	TRICHLOROETHYLENE (TCE)	7.0E-03		1	1
SW-9	T	10/30/2001	TRICHLOROETHYLENE (TCE)	4.4E-03		1	1
SW-9	T	5/1/2002	TRICHLOROETHYLENE (TCE)	4.8E-03		1	1
SW-9	T	10/28/2002	TRICHLOROETHYLENE (TCE)	6.1E-03		1	1
SW-9	T	4/22/2003	TRICHLOROETHYLENE (TCE)	6.4E-03		1	1
SW-9	T	10/21/2003	TRICHLOROETHYLENE (TCE)	2.0E-03		1	1
SW-9	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.5E-03		2	1
SW-9	T	10/26/2004	TRICHLOROETHYLENE (TCE)	2.7E-03		1	1
SW-9	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.8E-03		1	1
SW-9	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.7E-03		1	1
SW-9	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.3E-03		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

November 7, 2006

**LONG-TERM  
MONITORING NETWORK OPTIMIZATION  
PRB AND SOIL REMEDY AREAS**

Clare Water Supply Superfund Site  
Clare, Michigan

**APPENDIX B:**

---

**MAROS Reports**

*PRB Area:*

COC Assessment Report  
Mann-Kendall Reports Selected Wells

*Soil Remedy Area:*

COC Assessment Report  
Mann-Kendall Reports Selected Wells

# MAROS COC Assessment

**Project:** Clare Water Supply

**User Name:** MV

**Location:** Clare

**State:** Michigan

## Toxicity:

Contaminant of Concern	Representative Concentration (mg/L)	PRG (mg/L)	Percent Above PRG
VINYL CHLORIDE	1.2E-01	1.5E-02	713.2%
cis-1,2-DICHLOROETHYLENE	6.9E-02	6.1E-02	12.9%

Note: Top COCs by toxicity were determined by examining a representative concentration for each compound over the entire site. The compound representative concentrations are then compared with the chosen PRG for that compound, with the percentage exceedence from the PRG determining the compound's toxicity. All compounds above exceed the PRG.

## Prevalence:

Contaminant of Concern	Class	Total Wells	Total Excedences	Percent Excedences	Total detects
VINYL CHLORIDE	ORG	16	10	62.5%	15
cis-1,2-DICHLOROETHYLENE	ORG	16	3	18.8%	13

Note: Top COCs by prevalence were determined by examining a representative concentration for each well location at the site. The total exceedences (values above the chosen PRGs) are compared to the total number of wells to determine the prevalence of the compound.

## Mobility:

Contaminant of Concern	Kd
VINYL CHLORIDE	0.042
cis-1,2-DICHLOROETHYLENE	0.0724

Note: Top COCs by mobility were determined by examining each detected compound in the dataset and comparing their mobilities (Koc's for organics, assume foc = 0.001, and Kd's for metals).

## **Contaminants of Concern (COC's)**

---


VINYL CHLORIDE

cis-1,2-DICHLOROETHYLENE

# MAROS Mann-Kendall Statistics Summary

Well: MW-301  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/17/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-3

Confidence in Trend:

67.5%

Coefficient of Variation:

0.18

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-301	T	5/24/2005	VINYL CHLORIDE	1.5E-03		1	1
MW-301	T	8/11/2005	VINYL CHLORIDE	1.5E-03		1	1
MW-301	T	11/9/2005	VINYL CHLORIDE	1.0E-03	ND	1	0
MW-301	T	3/15/2006	VINYL CHLORIDE	1.1E-03		1	1
MW-301	T	5/17/2006	VINYL CHLORIDE	1.4E-03		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-302  
 Well Type: S  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/17/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-6

Confidence in Trend:

88.3%

Coefficient of Variation:

0.41

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-302	S	5/24/2005	VINYL CHLORIDE	9.9E-02		1	1
MW-302	S	8/11/2005	VINYL CHLORIDE	5.0E-02		1	1
MW-302	S	11/9/2005	VINYL CHLORIDE	5.9E-02		1	1
MW-302	S	3/15/2006	VINYL CHLORIDE	5.4E-02		1	1
MW-302	S	5/17/2006	VINYL CHLORIDE	3.3E-02		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-303  
 Well Type: S  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/17/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-6

Confidence in Trend:

88.3%

Coefficient of Variation:

1.16

Mann Kendall Concentration Trend: (See Note)

NT

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-303	S	5/24/2005	VINYL CHLORIDE	1.6E+00		1	1
MW-303	S	8/11/2005	VINYL CHLORIDE	1.1E+00		1	1
MW-303	S	11/9/2005	VINYL CHLORIDE	9.1E-02		1	1
MW-303	S	3/15/2006	VINYL CHLORIDE	1.2E-01		1	1
MW-303	S	5/17/2006	VINYL CHLORIDE	1.1E-01		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-304  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/17/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-4

Confidence in Trend:

75.8%

Coefficient of Variation:

0.53

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-304	T	5/24/2005	VINYL CHLORIDE	4.1E-02		1	1
MW-304	T	8/11/2005	VINYL CHLORIDE	2.8E-02		1	1
MW-304	T	11/9/2005	VINYL CHLORIDE	8.5E-03		1	1
MW-304	T	3/15/2006	VINYL CHLORIDE	1.8E-02		1	1
MW-304	T	5/17/2006	VINYL CHLORIDE	2.0E-02		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-305  
 Well Type: S  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/17/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-1

Confidence in Trend:

50.0%

Coefficient of Variation:

0.66

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-305	S	5/24/2005	VINYL CHLORIDE	2.4E-01		1	1
MW-305	S	8/11/2005	VINYL CHLORIDE	6.8E-02		1	1
MW-305	S	11/9/2005	VINYL CHLORIDE	2.3E-02		1	1
MW-305	S	3/15/2006	VINYL CHLORIDE	2.4E-01		1	1
MW-305	S	5/17/2006	VINYL CHLORIDE	1.9E-01		1	1


Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect



# MAROS Mann-Kendall Statistics Summary

Well: MW-306  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/17/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-8

Confidence in Trend:

95.8%

Coefficient of Variation:

1.08

Mann Kendall Concentration Trend: (See Note)

D

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-306	T	5/24/2005	VINYL CHLORIDE	1.5E-02		1	1
MW-306	T	8/11/2005	VINYL CHLORIDE	4.4E-03		1	1
MW-306	T	11/9/2005	VINYL CHLORIDE	2.4E-03		1	1
MW-306	T	3/15/2006	VINYL CHLORIDE	2.0E-03		1	1
MW-306	T	5/17/2006	VINYL CHLORIDE	2.1E-03		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: Mw-307  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/17/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-4

Confidence in Trend:

75.8%

Coefficient of Variation:

1.03

Mann Kendall Concentration Trend: (See Note)

NT

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
Mw-307	T	5/24/2005	VINYL CHLORIDE	3.3E-02		1	1
Mw-307	T	8/11/2005	VINYL CHLORIDE	1.1E-02		1	1
Mw-307	T	11/9/2005	VINYL CHLORIDE	1.0E-03	ND	1	0
Mw-307	T	3/15/2006	VINYL CHLORIDE	5.0E-03		1	1
Mw-307	T	5/17/2006	VINYL CHLORIDE	1.0E-02		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-308  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/17/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

2

Confidence in Trend:

59.2%

Coefficient of Variation:

0.39

Mann Kendall Concentration Trend: (See Note)

NT

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-308	T	5/24/2005	VINYL CHLORIDE	5.5E-02		1	1
MW-308	T	8/11/2005	VINYL CHLORIDE	2.6E-02		1	1
MW-308	T	11/9/2005	VINYL CHLORIDE	2.3E-02		1	1
MW-308	T	3/15/2006	VINYL CHLORIDE	4.5E-02		1	1
MW-308	T	5/17/2006	VINYL CHLORIDE	5.8E-02		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: Mw-309  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/17/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

2

Confidence in Trend:

59.2%

Coefficient of Variation:

0.58

Mann Kendall Concentration Trend: (See Note)

NT

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
Mw-309	T	5/24/2005	VINYL CHLORIDE	4.8E-02		1	1
Mw-309	T	8/11/2005	VINYL CHLORIDE	1.4E-02		1	1
Mw-309	T	11/9/2005	VINYL CHLORIDE	1.6E-02		1	1
Mw-309	T	3/15/2006	VINYL CHLORIDE	1.8E-02		1	1
Mw-309	T	5/17/2006	VINYL CHLORIDE	2.5E-02		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-310  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/17/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

6

Confidence in Trend:

88.3%

Coefficient of Variation:

0.60

Mann Kendall Concentration Trend: (See Note)

NT

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-310	T	5/24/2005	VINYL CHLORIDE	7.1E-03		1	1
MW-310	T	8/11/2005	VINYL CHLORIDE	1.9E-02		1	1
MW-310	T	11/9/2005	VINYL CHLORIDE	5.2E-03		1	1
MW-310	T	3/15/2006	VINYL CHLORIDE	2.5E-02		1	1
MW-310	T	5/17/2006	VINYL CHLORIDE	2.7E-02		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-311  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/17/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-2

Confidence in Trend:

59.2%

Coefficient of Variation:

0.70

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-311	T	5/24/2005	VINYL CHLORIDE	2.9E-02		1	1
MW-311	T	8/11/2005	VINYL CHLORIDE	6.9E-02		1	1
MW-311	T	11/9/2005	VINYL CHLORIDE	1.5E-02		1	1
MW-311	T	3/15/2006	VINYL CHLORIDE	1.7E-02		1	1
MW-311	T	5/17/2006	VINYL CHLORIDE	2.6E-02		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-312  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

0

Confidence in Trend:

40.8%

Coefficient of Variation:

0.00

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-312	T	5/24/2005	VINYL CHLORIDE	1.0E-03	ND	1	0
MW-312	T	8/11/2005	VINYL CHLORIDE	1.0E-03	ND	1	0
MW-312	T	11/9/2005	VINYL CHLORIDE	1.0E-03	ND	1	0
MW-312	T	3/15/2006	VINYL CHLORIDE	1.0E-03	ND	1	0
MW-312	T	5/17/2006	VINYL CHLORIDE	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: MW-313  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

4

Confidence in Trend:

75.8%

Coefficient of Variation:

0.13

Mann Kendall Concentration Trend:  
(See Note)

NT

## Data Table:

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
MW-313	T	5/24/2005	VINYL CHLORIDE	7.3E-04		1	1
MW-313	T	8/11/2005	VINYL CHLORIDE	1.0E-03	ND	1	0
MW-313	T	11/9/2005	VINYL CHLORIDE	1.0E-03	ND	1	0
MW-313	T	3/15/2006	VINYL CHLORIDE	1.0E-03	ND	1	0
MW-313	T	5/17/2006	VINYL CHLORIDE	1.0E-03	ND	1	0


Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect



# MAROS Mann-Kendall Statistics Summary

Well: 300A  
 Well Type: S  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/17/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

56

Confidence in Trend:

99.8%

Coefficient of Variation:

0.72

Mann Kendall Concentration Trend:  
(See Note)

I

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
300A	S	12/12/1999	VINYL CHLORIDE	2.9E-01		2	2
300A	S	6/28/2000	VINYL CHLORIDE	3.3E-01		1	1
300A	S	12/6/2000	VINYL CHLORIDE	6.6E-01		1	1
300A	S	10/30/2001	VINYL CHLORIDE	3.9E-01		1	1
300A	S	5/1/2002	VINYL CHLORIDE	7.0E-01		2	2
300A	S	10/29/2002	VINYL CHLORIDE	7.3E-01		1	1
300A	S	4/22/2003	VINYL CHLORIDE	9.8E-01		1	1
300A	S	10/21/2003	VINYL CHLORIDE	9.0E-01		1	1
300A	S	4/27/2004	VINYL CHLORIDE	9.4E-01		1	1
300A	S	10/27/2004	VINYL CHLORIDE	9.4E-01		1	1
300A	S	5/24/2005	VINYL CHLORIDE	1.4E+00		1	1
300A	S	8/11/2005	VINYL CHLORIDE	1.5E+00		1	1
300A	S	11/9/2005	VINYL CHLORIDE	3.0E+00		2	2
300A	S	3/15/2006	VINYL CHLORIDE	5.5E-01		1	1
300A	S	5/17/2006	VINYL CHLORIDE	6.1E-01		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: 300B  
 Well Type: S  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/17/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

62

Confidence in Trend:

100.0%

Coefficient of Variation:

1.10

Mann Kendall Concentration Trend:  
(See Note)

I

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
300B	S	12/12/1999	VINYL CHLORIDE	1.4E-02		1	1
300B	S	6/28/2000	VINYL CHLORIDE	2.0E-02		1	1
300B	S	12/6/2000	VINYL CHLORIDE	7.2E-03		1	1
300B	S	10/30/2001	VINYL CHLORIDE	3.6E-03		1	1
300B	S	5/1/2002	VINYL CHLORIDE	1.0E-02		1	1
300B	S	10/29/2002	VINYL CHLORIDE	2.4E-02		1	1
300B	S	4/22/2003	VINYL CHLORIDE	3.4E-02		1	1
300B	S	10/21/2003	VINYL CHLORIDE	3.7E-02		1	1
300B	S	4/27/2004	VINYL CHLORIDE	6.2E-02		1	1
300B	S	10/27/2004	VINYL CHLORIDE	4.8E-02		1	1
300B	S	5/24/2005	VINYL CHLORIDE	1.1E-01		1	1
300B	S	11/9/2005	VINYL CHLORIDE	1.4E-01		1	1
300B	S	5/17/2006	VINYL CHLORIDE	2.0E-01		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: 300C  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

43

Confidence in Trend:

99.6%

Coefficient of Variation:

1.38

Mann Kendall Concentration Trend: (See Note)

I

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
300C	T	12/12/1999	VINYL CHLORIDE	1.0E-03	ND	1	0
300C	T	7/21/2000	VINYL CHLORIDE	7.3E-04		1	1
300C	T	12/6/2000	VINYL CHLORIDE	2.9E-04		1	1
300C	T	10/30/2001	VINYL CHLORIDE	1.0E-03	ND	1	0
300C	T	5/1/2002	VINYL CHLORIDE	1.0E-03	ND	1	0
300C	T	10/29/2002	VINYL CHLORIDE	3.2E-03		1	1
300C	T	4/22/2003	VINYL CHLORIDE	1.0E-03	ND	1	0
300C	T	10/21/2003	VINYL CHLORIDE	1.3E-02		1	1
300C	T	4/27/2004	VINYL CHLORIDE	1.6E-03		1	1
300C	T	10/27/2004	VINYL CHLORIDE	2.4E-02		1	1
300C	T	5/24/2005	VINYL CHLORIDE	2.4E-02		1	1
300C	T	11/9/2005	VINYL CHLORIDE	2.7E-02		1	1
300C	T	5/17/2006	VINYL CHLORIDE	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: 220  
 Well Type: T  
 COC: VINYL CHLORIDE

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-8

Confidence in Trend:

63.3%

Coefficient of Variation:

0.19

Mann Kendall Concentration Trend:  
(See Note)

S

## Data Table:

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
220	T	3/24/1999	VINYL CHLORIDE	1.0E-03	ND	1	0
220	T	6/23/1999	VINYL CHLORIDE	1.0E-03	ND	1	0
220	T	12/12/1999	VINYL CHLORIDE	1.0E-03	ND	1	0
220	T	6/28/2000	VINYL CHLORIDE	1.0E-03	ND	2	0
220	T	12/6/2000	VINYL CHLORIDE	1.0E-03	ND	1	0
220	T	10/30/2001	VINYL CHLORIDE	1.0E-03	ND	2	0
220	T	5/1/2002	VINYL CHLORIDE	1.0E-03	ND	1	0
220	T	10/29/2002	VINYL CHLORIDE	1.0E-03	ND	1	0
220	T	4/22/2003	VINYL CHLORIDE	1.0E-03	ND	1	0
220	T	10/21/2003	VINYL CHLORIDE	1.0E-03	ND	1	0
220	T	4/27/2004	VINYL CHLORIDE	1.0E-03	ND	1	0
220	T	10/27/2004	VINYL CHLORIDE	3.1E-04		1	1
220	T	5/24/2005	VINYL CHLORIDE	1.0E-03	ND	1	0
220	T	11/9/2005	VINYL CHLORIDE	1.0E-03	ND	1	0
220	T	5/17/2006	VINYL CHLORIDE	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS COC Assessment

**Project:** Soil Remedy

**User Name:** MV

**Location:** Clare

**State:** Michigan

## Toxicity:

Contaminant of Concern	Representative Concentration (mg/L)	PRG (mg/L)	Percent Above PRG
TRICHLOROETHYLENE (TCE)	5.3E-03	5.0E-03	6.9%

Note: Top COCs by toxicity were determined by examining a representative concentration for each compound over the entire site. The compound representative concentrations are then compared with the chosen PRG for that compound, with the percentage exceedence from the PRG determining the compound's toxicity. All compounds above exceed the PRG.

## Prevalence:

Contaminant of Concern	Class	Total Wells	Total Excedences	Percent Excedences	Total detects
TRICHLOROETHYLENE (TCE)	ORG	8	2	25.0%	5

Note: Top COCs by prevalence were determined by examining a representative concentration for each well location at the site. The total exceedences (values above the chosen PRGs) are compared to the total number of wells to determine the prevalence of the compound.

## Mobility:

Contaminant of Concern	Kd
TRICHLOROETHYLENE (TCE)	0.297

Note: Top COCs by mobility were determined by examining each detected compound in the dataset and comparing their mobilities (Koc's for organics, assume foc = 0.001, and Kd's for metals).

## **Contaminants of Concern (COC's)**

---

VINYL CHLORIDE


TRICHLOROETHYLENE (TCE)

cis-1,2-DICHLOROETHYLENE

# MAROS Mann-Kendall Statistics Summary

Well: UMW-1S  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

0

Confidence in Trend:

48.0%

Coefficient of Variation:

0.00

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
UMW-1S	T	3/24/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	6/23/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	10/30/2001	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	5/1/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	10/28/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1S	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: DMW-1S  
 Well Type: S  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 3/24/1999 to 5/16/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-93

Confidence in Trend:

100.0%

Coefficient of Variation:

1.61

Mann Kendall Concentration Trend: (See Note)

D

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-1S	S	3/24/1999	TRICHLOROETHYLENE (TCE)	9.9E-02		1	1
DMW-1S	S	6/23/1999	TRICHLOROETHYLENE (TCE)	6.7E-02		1	1
DMW-1S	S	12/21/1999	TRICHLOROETHYLENE (TCE)	1.4E-02		1	1
DMW-1S	S	6/28/2000	TRICHLOROETHYLENE (TCE)	1.3E-02		1	1
DMW-1S	S	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-02		1	1
DMW-1S	S	10/30/2001	TRICHLOROETHYLENE (TCE)	9.0E-03		1	1
DMW-1S	S	5/1/2002	TRICHLOROETHYLENE (TCE)	7.0E-03		1	1
DMW-1S	S	10/28/2002	TRICHLOROETHYLENE (TCE)	7.0E-03		1	1
DMW-1S	S	4/22/2003	TRICHLOROETHYLENE (TCE)	9.0E-03		1	1
DMW-1S	S	10/21/2003	TRICHLOROETHYLENE (TCE)	4.0E-03		1	1
DMW-1S	S	4/27/2004	TRICHLOROETHYLENE (TCE)	4.0E-03		1	1
DMW-1S	S	10/26/2004	TRICHLOROETHYLENE (TCE)	4.0E-03		1	1
DMW-1S	S	5/20/2005	TRICHLOROETHYLENE (TCE)	4.0E-03		1	1
DMW-1S	S	11/8/2005	TRICHLOROETHYLENE (TCE)	3.2E-03		1	1
DMW-1S	S	5/16/2006	TRICHLOROETHYLENE (TCE)	2.9E-03		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: DMW-1S  
 Well Type: S  
 COC: cis-1,2-DICHLOROETHYLENE

Time Period: 3/24/1999 to 5/16/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-19

Confidence in Trend:

81.0%

Coefficient of Variation:

1.62

Mann Kendall Concentration Trend: (See Note)

NT

## Data Table:

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-1S	S	3/24/1999	cis-1,2-DICHLOROETHYLENE	2.4E-02		1	1
DMW-1S	S	6/23/1999	cis-1,2-DICHLOROETHYLENE	8.0E-03		1	1
DMW-1S	S	12/21/1999	cis-1,2-DICHLOROETHYLENE	4.0E-03		1	1
DMW-1S	S	6/28/2000	cis-1,2-DICHLOROETHYLENE	3.0E-03		1	1
DMW-1S	S	12/6/2000	cis-1,2-DICHLOROETHYLENE	2.3E-02		1	1
DMW-1S	S	10/30/2001	cis-1,2-DICHLOROETHYLENE	6.7E-02		1	1
DMW-1S	S	5/1/2002	cis-1,2-DICHLOROETHYLENE	6.0E-03		1	1
DMW-1S	S	10/28/2002	cis-1,2-DICHLOROETHYLENE	1.8E-01		1	1
DMW-1S	S	4/22/2003	cis-1,2-DICHLOROETHYLENE	2.0E-02		1	1
DMW-1S	S	10/21/2003	cis-1,2-DICHLOROETHYLENE	9.0E-03		1	1
DMW-1S	S	4/27/2004	cis-1,2-DICHLOROETHYLENE	5.0E-03		1	1
DMW-1S	S	10/26/2004	cis-1,2-DICHLOROETHYLENE	9.3E-02		1	1
DMW-1S	S	5/20/2005	cis-1,2-DICHLOROETHYLENE	5.9E-03		1	1
DMW-1S	S	11/8/2005	cis-1,2-DICHLOROETHYLENE	5.5E-03		1	1
DMW-1S	S	5/16/2006	cis-1,2-DICHLOROETHYLENE	2.9E-03		1	1


Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect



# MAROS Mann-Kendall Statistics Summary

Well: DMW-2S  
 Well Type: S  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 3/24/1999 to 5/16/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-45

Confidence in Trend:

99.3%

Coefficient of Variation:

0.95

Mann Kendall Concentration Trend: (See Note)

D

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-2S	S	3/24/1999	TRICHLOROETHYLENE (TCE)	5.0E-03		1	1
DMW-2S	S	6/23/1999	TRICHLOROETHYLENE (TCE)	7.0E-03		1	1
DMW-2S	S	12/21/1999	TRICHLOROETHYLENE (TCE)	2.0E-03		1	1
DMW-2S	S	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	10/30/2001	TRICHLOROETHYLENE (TCE)	2.0E-03		1	1
DMW-2S	S	5/1/2002	TRICHLOROETHYLENE (TCE)	1.0E-03		1	1
DMW-2S	S	10/28/2002	TRICHLOROETHYLENE (TCE)	2.0E-03		1	1
DMW-2S	S	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	5/20/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2S	S	5/16/2006	TRICHLOROETHYLENE (TCE)	7.9E-04		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: DMW-3S  
 Well Type: S  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 3/24/1999 to 5/16/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-35

Confidence in Trend:

95.4%

Coefficient of Variation:

0.58

Mann Kendall Concentration Trend: (See Note)

D

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-3S	S	3/24/1999	TRICHLOROETHYLENE (TCE)	3.1E-02		1	1
DMW-3S	S	6/23/1999	TRICHLOROETHYLENE (TCE)	4.8E-02		1	1
DMW-3S	S	12/21/1999	TRICHLOROETHYLENE (TCE)	1.5E-02		1	1
DMW-3S	S	6/28/2000	TRICHLOROETHYLENE (TCE)	3.0E-02		1	1
DMW-3S	S	12/6/2000	TRICHLOROETHYLENE (TCE)	2.1E-02		1	1
DMW-3S	S	10/30/2001	TRICHLOROETHYLENE (TCE)	3.1E-02		1	1
DMW-3S	S	5/1/2002	TRICHLOROETHYLENE (TCE)	3.6E-02		1	1
DMW-3S	S	10/28/2002	TRICHLOROETHYLENE (TCE)	6.0E-03		1	1
DMW-3S	S	4/22/2003	TRICHLOROETHYLENE (TCE)	2.3E-02		1	1
DMW-3S	S	10/21/2003	TRICHLOROETHYLENE (TCE)	8.0E-03		1	1
DMW-3S	S	4/27/2004	TRICHLOROETHYLENE (TCE)	1.2E-02		1	1
DMW-3S	S	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-02		1	1
DMW-3S	S	5/20/2005	TRICHLOROETHYLENE (TCE)	4.5E-03		1	1
DMW-3S	S	11/8/2005	TRICHLOROETHYLENE (TCE)	2.2E-02		1	1
DMW-3S	S	5/16/2006	TRICHLOROETHYLENE (TCE)	2.3E-02		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: DMW-1D  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

8

Confidence in Trend:

63.3%

Coefficient of Variation:

0.00

Mann Kendall Concentration Trend: (See Note)

NT

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-1D	T	3/24/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	6/23/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	1
DMW-1D	T	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	10/30/2001	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	5/1/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	10/28/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-1D	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: UMW-1D  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

0

Confidence in Trend:

48.0%

Coefficient of Variation:

0.00

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
UMW-1D	T	3/24/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	6/23/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	10/30/2001	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	5/1/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	10/28/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
UMW-1D	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: DMW-2D  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

0

Confidence in Trend:

48.0%

Coefficient of Variation:

0.00

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-2D	T	3/24/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	6/23/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	10/30/2001	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	5/1/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	10/28/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-2D	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: DMW-3D  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 1/1/1999 to 5/18/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

10

Confidence in Trend:

66.9%

Coefficient of Variation:

0.15

Mann Kendall Concentration Trend: (See Note)

NT

## Data Table:


Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
DMW-3D	T	3/24/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	6/23/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	12/6/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	10/30/2001	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	5/1/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	10/28/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.6E-03		1	1
DMW-3D	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
DMW-3D	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

# MAROS Mann-Kendall Statistics Summary

Well: 215  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 6/1/1988 to 5/16/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

-61

Confidence in Trend:

81.2%

Coefficient of Variation:

0.37

Mann Kendall Concentration Trend: (See Note)

S

## Data Table:

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
215	T	3/21/1994	TRICHLOROETHYLENE (TCE)	1.0E-03		1	1
215	T	6/28/1994	TRICHLOROETHYLENE (TCE)	2.1E-03		2	2
215	T	9/21/1994	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	12/19/1994	TRICHLOROETHYLENE (TCE)	1.3E-03		1	1
215	T	3/21/1995	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	6/27/1995	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	9/19/1995	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	12/19/1995	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	3/26/1996	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	6/19/1996	TRICHLOROETHYLENE (TCE)	1.3E-03		1	1
215	T	9/17/1996	TRICHLOROETHYLENE (TCE)	7.4E-04		1	1
215	T	12/17/1996	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	3/25/1997	TRICHLOROETHYLENE (TCE)	5.5E-04		1	1
215	T	6/24/1997	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	9/23/1997	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	12/16/1997	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	3/24/1998	TRICHLOROETHYLENE (TCE)	4.0E-04		2	2
215	T	6/17/1998	TRICHLOROETHYLENE (TCE)	4.4E-04		1	1
215	T	10/1/1998	TRICHLOROETHYLENE (TCE)	3.8E-04		2	2
215	T	3/24/1999	TRICHLOROETHYLENE (TCE)	2.9E-04		1	1
215	T	6/23/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0

# MAROS Mann-Kendall Statistics Summary

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
215	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	12/6/2000	TRICHLOROETHYLENE (TCE)	6.5E-04		2	1
215	T	10/30/2001	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	5/1/2002	TRICHLOROETHYLENE (TCE)	1.4E-04		1	1
215	T	10/28/2002	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	4/22/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	10/21/2003	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	10/26/2004	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
215	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0


Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect



# MAROS Mann-Kendall Statistics Summary

Well: SW-9  
 Well Type: T  
 COC: TRICHLOROETHYLENE (TCE)

Time Period: 6/1/1988 to 5/16/2006  
 Consolidation Period: No Time Consolidation  
 Consolidation Type: Median  
 Duplicate Consolidation: Average  
 ND Values: Specified Detection Limit  
 J Flag Values : Actual Value



Mann Kendall S Statistic:

22

Confidence in Trend:

61.2%

Coefficient of Variation:

0.91

Mann Kendall Concentration Trend: (See Note)

NT

## Data Table:

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
SW-9	T	6/1/1988	TRICHLOROETHYLENE (TCE)	4.0E-03		1	1
SW-9	T	6/1/1989	TRICHLOROETHYLENE (TCE)	2.0E-03		1	1
SW-9	T	3/21/1994	TRICHLOROETHYLENE (TCE)	4.1E-03		1	1
SW-9	T	6/28/1994	TRICHLOROETHYLENE (TCE)	4.6E-03		2	2
SW-9	T	9/21/1994	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
SW-9	T	12/19/1994	TRICHLOROETHYLENE (TCE)	1.8E-03		1	1
SW-9	T	3/21/1995	TRICHLOROETHYLENE (TCE)	2.8E-03		1	1
SW-9	T	6/27/1995	TRICHLOROETHYLENE (TCE)	1.5E-03		2	1
SW-9	T	9/19/1995	TRICHLOROETHYLENE (TCE)	3.3E-03		1	1
SW-9	T	12/19/1995	TRICHLOROETHYLENE (TCE)	1.9E-03		1	1
SW-9	T	3/26/1996	TRICHLOROETHYLENE (TCE)	2.0E-03		1	1
SW-9	T	6/19/1996	TRICHLOROETHYLENE (TCE)	9.5E-04		2	1
SW-9	T	9/17/1996	TRICHLOROETHYLENE (TCE)	1.0E-03	ND	1	0
SW-9	T	12/17/1996	TRICHLOROETHYLENE (TCE)	2.4E-03		1	1
SW-9	T	3/25/1997	TRICHLOROETHYLENE (TCE)	1.1E-03		1	1
SW-9	T	6/24/1997	TRICHLOROETHYLENE (TCE)	8.8E-04		3	3
SW-9	T	9/23/1997	TRICHLOROETHYLENE (TCE)	1.9E-03		1	1
SW-9	T	12/16/1997	TRICHLOROETHYLENE (TCE)	1.6E-03		1	1
SW-9	T	3/24/1998	TRICHLOROETHYLENE (TCE)	8.6E-04		1	1
SW-9	T	6/17/1998	TRICHLOROETHYLENE (TCE)	1.5E-03		1	1
SW-9	T	10/1/1998	TRICHLOROETHYLENE (TCE)	1.1E-03		2	2
SW-9	T	3/24/1999	TRICHLOROETHYLENE (TCE)	1.2E-02		1	1

# MAROS Mann-Kendall Statistics Summary

Well	Well Type	Effective Date	Constituent	Result (mg/L)	Flag	Number of Samples	Number of Detects
SW-9	T	6/23/1999	TRICHLOROETHYLENE (TCE)	9.2E-03		1	1
SW-9	T	12/21/1999	TRICHLOROETHYLENE (TCE)	1.2E-02		1	1
SW-9	T	6/28/2000	TRICHLOROETHYLENE (TCE)	1.1E-02		1	1
SW-9	T	12/6/2000	TRICHLOROETHYLENE (TCE)	7.0E-03		1	1
SW-9	T	10/30/2001	TRICHLOROETHYLENE (TCE)	4.4E-03		1	1
SW-9	T	5/1/2002	TRICHLOROETHYLENE (TCE)	4.8E-03		1	1
SW-9	T	10/28/2002	TRICHLOROETHYLENE (TCE)	6.1E-03		1	1
SW-9	T	4/22/2003	TRICHLOROETHYLENE (TCE)	6.4E-03		1	1
SW-9	T	10/21/2003	TRICHLOROETHYLENE (TCE)	2.0E-03		1	1
SW-9	T	4/27/2004	TRICHLOROETHYLENE (TCE)	1.5E-03		2	1
SW-9	T	10/26/2004	TRICHLOROETHYLENE (TCE)	2.7E-03		1	1
SW-9	T	5/20/2005	TRICHLOROETHYLENE (TCE)	1.8E-03		1	1
SW-9	T	11/8/2005	TRICHLOROETHYLENE (TCE)	1.7E-03		1	1
SW-9	T	5/16/2006	TRICHLOROETHYLENE (TCE)	1.3E-03		1	1

Note: Increasing (I); Probably Increasing (PI); Stable (S); Probably Decreasing (PD); Decreasing (D); No Trend (NT); Not Applicable (N/A) - Due to insufficient Data (< 4 sampling events); ND = Non-detect

**Attachment D**

**Electronic Database**

**(provided on CD in hardcopy report)**

**Attachment E**  
**Selected November 2006 Data**

FILCON FACILITY  
(FORMERLY MITCHELL)

SW-11	
SW11	11/06
PCE	<1
TCE	<1
CIS-1,2	<1
VC	<1
1,1-DCA	<1



220	5/05	8/05	11/05	5/06	11/06
PCE	<1	NM	<1	<1	<1
TCE	<1	NM	<1	<1	<1
CIS-1,2	<1	NM	<1	<1	<1
VC	<1	NM	<1	<1	<1
1,1-DCA	4.9	NM	4.5	3.6	3.1

MW-301	5/05	8/05	11/05	3/06	5/06	11/06
PCE	1.8	<1	<1	<1	<1	<1
TCE	0.9J	<1	<1	<1	<1	<1
CIS-1,2	1.9	<1	<1	0.77J	0.73J	0.5J
VC	1.5	1.5	<1	1.1	1.4	0.5J
1,1-DCA	0.98J	<1	<1	0.36J	<1	0.55J

MW-302	5/05	8/05	11/05	3/06	5/06	11/06
PCE	<1	<1	<1	<1	<1	<1
TCE	1.0	<1	<1	0.52J	<1	0.46J
CIS-1,2	110D	31	33	27	<1	44
VC	99D	50	59	54	33	110
1,1-DCA	88D	97	85	120D	92	190

300C	5/05	11/05	5/06	11/06
PCE	<1	<1	<1	<1
TCE	<1	<1	<1	<1
CIS-1,2	<1	<1	<1	<1
VC	24	27	<1	13
1,1-DCA	4.9	7.5	<1	2.7

300B	5/05	11/05	5/06	11/06
PCE	<1	<1	<1	<1
TCE	<1	<1	<1	<1
CIS-1,2	6.8	7.7	10	8.7
VC	110	140D	200D	140
1,1-DCA	1.2	1.4	2.7	2.3

MW-310	5/05	8/05	11/05	3/06	5/06	11/06
PCE	<1	<1	<1	<1	<1	<1
TCE	<1	<1	<1	<1	<1	<1
CIS-1,2	1.3	<1	<1	<1	<1	<1
VC	7.1	19	5.2	25	27	21
1,1-DCA	<1	<1	<1	<1	<1	<1

MW-303	5/05	8/05	11/05	3/06	5/06	11/06
PCE	0.68J	<1	<1	<1	<1	<1
TCE	20	20	8.4	2.2	2.2	0.86J
CIS-1,2	1,400D	880D	41D	61	52	16
VC	1,600D	1,100D	91D	120D	110D	76
1,1-DCA	500D	350D	130D	95D	93D	91

MW-305	5/05	8/05	11/05	3/06	5/06	11/06
PCE	0.73J	<1	<1	<10	<1	<1
TCE	33	7.4	1.7	<10	1.5	0.58J
CIS-1,2	240D	69	17	140	110D	34
VC	240D	68	23	240	190D	110
1,1-DCA	80	33	16	78	96	73

MW-309	5/05	8/05	11/05	3/06	5/06	11/06
PCE	0.63J	<1	<1	<1	<1	<1
TCE	<1	<1	<1	<1	<1	<1
CIS-1,2	6.8	1.7	1.7	2.4	3.7	0.44J
VC	48	14	16	18	25	2.2
1,1-DCA	1	<1	<1	0.54J	0.88J	<1

SW-12	5/05	11/05	5/06	11/06
PCE	<1	<1	<1	<1
TCE	<1	<1	<1	<1
CIS-1,2	<1	<1	<1	<1
VC	<1	<1	<1	<1
1,1-DCA	<1	<1	<1	<1

MW-304	5/05	8/05	11/05	3/06	5/06	11/06
PCE	<1	<1	<1	<1	<1	<1
TCE	<1	<1	<1	<1	<1	<1
CIS-1,2	6.8	4.6	2.7	3	6.9	<1
VC	41	28	8.5	18	20	3.7
1,1-DCA	7.2	5.3	4.7	5.5	22	7.1

MW-311	5/05	8/05	11/05	3/06	5/06	11/06
PCE	<1	<1	<1	<1	<1	<1
TCE	8.8	10	2.4	2.9	4.9	0.53J
CIS-1,2	20	58	6.9	6.3	8.9	3.1
VC	29	69	15	17	26	10
1,1-DCA	13	20	11	7.6	10	5.3

MW-308	5/05	8/05	11/05	3/06	5/06	11/06
PCE	<1	<1	<1	<1	<1	<1
TCE	8.6	2.0	1.7	1.6	2.1	1.4
CIS-1,2	19	5.8	5.2	5.7	6.5	3.5
VC	55	26	23	45	58	20
1,1-DCA	18	8.4	9.6	13	15	9.7

MW-307	5/05	8/05	11/05	3/06	5/06	11/06
PCE	<1	<1	<1	<1	<1	<1
TCE	<1	<1	<1	<1	<1	<1
CIS-1,2	<1	<1	<1	<1	<1	<1
VC	33	11	<1	5	10	8.1
1,1-DCA	6	2.2	1.2	1.5	7.4	8.1

300A	5/05	8/05	12/05	3/06	5/06	11/06
PCE	<1	<1	<1	<1	<1	<1
TCE	0.72J	<1	<1	<1	<1	<1
CIS-1,2	430D	510D	190D	210D	190D	89
VC	1,400D	1,500D	720D	550D	610D	220
1,1-DCA	1,300D	1,500D	950D	890D	890D	590

MW-306	5/05	8/05	11/05	3/06	5/06	11/06
PCE	<1	<1	<1	<1	<1	<1
TCE	<1	<1	<1	<1	<1	<1
CIS-1,2	3.8	<1	<1	<1	0.81J	<1
VC	15	4.4	2.4	2	2.1	1.1
1,1-DCA	1.8	<1	<1	<1	<1	<1

MW-312	5/05	8/05	11/05	3/06	5/06	11/06
PCE	0.81J	<1	<1	<1	<1	<1
TCE	<1	<1	<1	<1	<1	<1
CIS-1,2	0.70J	<1	<1	<1	<1	<1
VC	<1	<1	<1	<1	<1	<1
1,1-DCA	<1	<1	<1	<1	<1	<1

**LEGEND**

MW-308 ○ MONITORING WELL

PRB


SW-12	GSI	5/05
PCE	45	<1
TCE	200	<1
CIS-1,2	620	<1
VC	15	<1
1,1-DCA	740	<1

PCE - TETRACHLOROETHYLENE  
TCE - TRICHLOROETHYLENE  
CIS-1,2 - CIS-1,2-DICHLOROETHYLENE  
VC - VINYL CHLORIDE  
1,1-DCA - 1,1 DICHLOROETHANE  
GSI - GROUNDWATER SURFACE WATER  
INTERFACE CRITERIA & RBLS

**NOTES:**

1. NOVEMBER 2005 SAMPLE RESULTS FOR 300A UNUSABLE PER DATA VALIDATION; LOCATION WAS RESAMPLED IN DECEMBER 2005.

2. NOVEMBER 2006 SAMPLE RESULTS ARE CONSIDERED PRELIMINARY AS DATA VALIDATION HAS NOT BEEN COMPLETED AS OF THE ISSUANCE OF THIS DRAWING.



SCALE: 1" = 30'

**PROGRESSIVE**

ENGINEERING & CONSTRUCTION, INC.  
Phone: (813) 930-0669 Fax: (813) 930-9809  
3912 W. Humphrey Street Tampa, Florida 33614  
E-mail: info@progressiveec.com  
Web Site: http://www.progressiveec.com

NO.	REVISION DETAILS	DATE
1	ADDED 1,1-DCA RESULTS	8/2/06
2	ADD NOV 2006 DATA	12/6/06

**SUMMARY OF VOCs IN  
PRB AREA GROUNDWATER**  
CLARE WATER SUPPLY SUPERFUND SITE  
CLARE, MICHIGAN

DATE: 12/14/05  
DRAWN: BER

DRAWING NUMBER:  
**FIGURE 22**

Summary of Groundwater Quality Data for November 2006

Clare Water Supply Site  
Clare, Michigan

CONSTITUENT:	SITE:		103	104	109	110	111	210D	210S	211
	LAB ID:	DATE:	A751880	A752317	A751893	A751892	A752288	A752291	A752293	A751895
	TDL	CUO	11/7/2006	11/8/2006	11/8/2006	11/8/2006	11/8/2006	11/8/2006	11/8/2006	11/8/2006
COCs										
Benzene	1	5	<1	<1	<1	<1	<1	<1	<1	<1
1,1-Dichloroethane	1	880	<1	<1	<1	<1	<1	<1	14	2.1
1,2-Dichloroethane	1	5	<1	<1	0.45J	0.6J	<1	<1	<1	<1
cis-1,2-Dichloroethene	1	70	4.1	<1	200	<1	4.2	<1	0.48J	3.7
trans-1,2-Dichloroethene	1	100	<1	<1	3	<1	1.1	<1	<1	<1
Ethylbenzene	1	700	<1	<1	<1	<1	<1	<1	<1	<1
Methylene Chloride	2	5	<2	<2	<2	<2	<2	<2	<2	<2
Styrene	1	100	<1	<1	<1	<1	<1	<1	<1	<1
Tetrachloroethene	1	5	<1	<1	<1	<1	<1	<1	<1	<1
Toluene	1	1000	0.81J	0.64J	1.1	2	<1	0.6J	0.65J	0.53J
1,1,1-Trichloroethane	1	200	<1	<1	<1	<1	<1	<1	<1	<1
1,1,2-Trichloroethane	1	5	<1	<1	<1	<1	<1	<1	<1	<1
Trichloroethene	1	5	3.2	<1	2.2	<1	3.1	<1	<1	<1
Vinyl Chloride	1	2	<1	<1	100	<1	<1	<1	<1	<1
Xylenes (total)	3	100000	<3	<3	<3	<3	<3	<3	<3	<3

Notes on last page.

Summary of Groundwater Quality Data for November 2006

Clare Water Supply Site

Clare, Michigan

CONSTITUENT:	SITE:		215	220	300A	300B	300C	D-106	D-107	DMW-1D
	LAB ID:	DATE:	A751874	A752297	A752313	A752311	A752310	A752292	A751894	A751876
	TDL	CUO	11/7/2006	11/9/2006	11/10/2006	11/10/2006	11/10/2006	11/8/2006	11/8/2006	11/7/2006
Benzene	1	5	<1	<1	<1	<1	<1	<1	<1	<1
1,1-Dichloroethane	1	880	<1	3.1	590	2.3	2.7	<1	<1	<1
1,2-Dichloroethane	1	5	<1	<1	<1	<1	<1	<1	<1	<1
cis-1,2-Dichloroethene	1	70	<1	<1	89	8.7	<1	1.9	<1	20
trans-1,2-Dichloroethene	1	100	<1	<1	<1	<1	<1	<1	<1	<1
Ethylbenzene	1	700	<1	<1	<1	<1	<1	<1	<1	<1
Methylene Chloride	2	5	<2	<2	<2	<2	<2	<2	<2	<2
Styrene	1	100	<1	<1	<1	<1	<1	<1	<1	<1
Tetrachloroethene	1	5	<1	<1	<1	<1	<1	<1	<1	<1
Toluene	1	1000	1.5	1.5	<1	0.89J	1.3	<1	1.3	0.95J
1,1,1-Trichloroethane	1	200	<1	<1	<1	<1	<1	<1	<1	<1
1,1,2-Trichloroethane	1	5	<1	<1	<1	<1	<1	<1	<1	<1
Trichloroethene	1	5	<1	<1	<1	<1	<1	2.5	<1	<1
Vinyl Chloride	1	2	<1	<1	220	140	13	<1	<1	<1
Xylenes (total)	3	100000	<3	<3	<3	<3	<3	<3	<3	<3

Notes on last page.

Summary of Groundwater Quality Data for November 2006

Clare Water Supply Site  
Clare, Michigan

CONSTITUENT:	SITE:		DMW-1S	DMW-2D	DMW-2S	DMW-3D	DMW-3S	MW-301	MW-302	MW-303
	LAB ID:	DATE:	A751873	A751882	A751872	A751877	A751879	A752299	A752305	A752306
	TDL	CUO	11/7/2006	11/7/2006	11/7/2006	11/7/2006	11/7/2006	11/9/2006	11/9/2006	11/9/2006
COCs										
Benzene	1	5	<1	<1	<1	<1	<1	<1	<1	<1
1,1-Dichloroethane	1	880	<1	<1	<1	<1	<1	0.55J	190	91
1,2-Dichloroethane	1	5	<1	<1	<1	<1	<1	<1	<1	<1
cis-1,2-Dichloroethene	1	70	49	1.2	<1	<1	0.52J	0.5J	44	16
trans-1,2-Dichloroethene	1	100	<1	<1	<1	<1	<1	<1	<1	<1
Ethylbenzene	1	700	<1	<1	<1	<1	<1	<1	<1	<1
Methylene Chloride	2	5	<2	<2	<2	<2	<2	<2	<2	<2
Styrene	1	100	<1	<1	<1	<1	<1	<1	<1	<1
Tetrachloroethene	1	5	<1	<1	<1	<1	<1	<1	<1	<1
Toluene	1	1000	2.1	1.2	<1	1.4	1.3	0.42J	0.98J	0.89J
1,1,1-Trichloroethane	1	200	<1	<1	<1	<1	<1	<1	1.9	<1
1,1,2-Trichloroethane	1	5	<1	<1	<1	<1	<1	<1	<1	<1
Trichloroethene	1	5	5.1	<1	1	<1	13	<1	0.46J	0.86J
Vinyl Chloride	1	2	<1	<1	<1	<1	<1	0.5J	110	76
Xylenes (total)	3	100000	<3	<3	<3	<3	<3	<3	<3	<3

Notes on last page.



Summary of Groundwater Quality Data for November 2006

Clare Water Supply Site  
Clare, Michigan

CONSTITUENT:	SITE:		MW-304	MW-305	MW-306	MW-307	MW-308	MW-309	MW-310	MW-311
	LAB ID:	DATE:	A752300	A752314	A752312	A752307	A752308	A752309	A752304	A752303
	TDL	CUO	11/9/2006	11/10/2006	11/10/2006	11/10/2006	11/10/2006	11/10/2006	11/9/2006	11/9/2006
Benzene	1	5	<1	<1	<1	<1	<1	<1	<1	<1
1,1-Dichloroethane	1	880	7.1	73	<1	8.1	9.7	<1	<1	5.3
1,2-Dichloroethane	1	5	<1	<1	<1	<1	<1	<1	<1	<1
cis-1,2-Dichloroethene	1	70	<1	34	<1	<1	3.5	0.44J	<1	3.1
trans-1,2-Dichloroethene	1	100	<1	<1	<1	<1	<1	<1	<1	<1
Ethylbenzene	1	700	<1	<1	<1	<1	<1	<1	<1	<1
Methylene Chloride	2	5	<2	<2	<2	<2	<2	<2	<2	<2
Styrene	1	100	<1	<1	<1	<1	<1	<1	<1	<1
Tetrachloroethene	1	5	<1	<1	<1	<1	<1	<1	<1	<1
Toluene	1	1000	<1	<1	<1	<1	0.54J	<1	1.2	0.44J
1,1,1-Trichloroethane	1	200	<1	<1	<1	<1	<1	<1	<1	<1
1,1,2-Trichloroethane	1	5	<1	<1	<1	<1	<1	<1	<1	<1
Trichloroethene	1	5	<1	0.58J	<1	<1	1.4	<1	<1	0.53J
Vinyl Chloride	1	2	3.7	110	1.1	8.1	20	2.2	21	10
Xylenes (total)	3	100000	<3	<3	<3	<3	<3	<3	<3	<3

Notes on last page.

Summary of Groundwater Quality Data for November 2006

Clare Water Supply Site  
Clare, Michigan

		SITE:	MW-312	MW-313	MW-5	MW-6	MW-7	MW-8	P-202	SW-11
		LAB ID:	A752296	A752301	A751889	A751871	A751870	A751890	A752294	A752298
CONSTITUENT:		DATE:	11/9/2006	11/9/2006	11/7/2006	11/7/2006	11/7/2006	11/8/2006	11/8/2006	11/9/2006
COCs	TDL	CJO								
Benzene	1	5	<1	<1	<1	<1	<1	<1	<1	<1
1,1-Dichloroethane	1	880	<1	<1	0.63J	<1	<1	0.43J	<1	<1
1,2-Dichloroethane	1	5	<1	<1	<1	<1	<1	<1	<1	<1
cis-1,2-Dichloroethene	1	70	<1	<1	6.9	<1	<1	29	1.5	<1
trans-1,2-Dichloroethene	1	100	<1	<1	0.47J	<1	<1	1.3	<1	<1
Ethylbenzene	1	700	<1	<1	<1	<1	<1	<1	<1	<1
Methylene Chloride	2	5	<2	<2	<2	<2	<2	<2	<2	<2
Styrene	1	100	<1	<1	<1	<1	<1	<1	<1	<1
Tetrachloroethene	1	5	<1	<1	<1	<1	<1	<1	<1	<1
Toluene	1	1000	<1	0.9J	1.2	1.2	1.2	1.2	1.3	1.2
1,1,1-Trichloroethane	1	200	<1	<1	<1	<1	<1	<1	<1	<1
1,1,2-Trichloroethane	1	5	<1	<1	<1	<1	<1	<1	<1	<1
Trichloroethene	1	5	<1	<1	5.7	<1	<1	0.56J	9.4	<1
Vinyl Chloride	1	2	<1	<1	<1	<1	<1	0.79J	<1	<1
Xylenes (total)	3	100000	<3	<3	<3	<3	<3	<3	<3	<3

Notes on last page.

Summary of Groundwater Quality Data for November 2006

Clare Water Supply Site  
Clare, Michigan

		SITE:	SW-12	SW-5	SW-9	UMW-1D	UMW-1S	W-6	W-9	WD-10
		LAB ID:	A752302	A751886	A751878	A751875	A751887	A751891	A752318	A751881
CONSTITUENT:		DATE:	11/9/2006	11/7/2006	11/7/2006	11/7/2006	11/7/2006	11/8/2006	11/8/2006	11/7/2006
COCs	TDL	CJO								
Benzene	1	5	<1	<b>8.4</b>	<1	<1	<1	<1	<1	<1
1,1-Dichloroethane	1	880	<1	<1	1	<1	<1	<1	<1	<1
1,2-Dichloroethane	1	5	<1	<1	<1	<1	<1	<1	<1	<1
cis-1,2-Dichloroethene	1	70	<1	1.5	1.8	<1	<1	<1	<1	<1
trans-1,2-Dichloroethene	1	100	<1	<1	<1	<1	<1	<1	<1	<1
Ethylbenzene	1	700	<1	21	<1	<1	<1	<1	<1	<1
Methylene Chloride	2	5	<2	<2	<2	<2	<2	<2	<2	<2
Styrene	1	100	<1	<1	<1	<1	<1	<1	<1	<1
Tetrachloroethene	1	5	<1	<1	<1	<1	<1	<1	<b>7.7</b>	<1
Toluene	1	1000	0.66J	2.6	1.4	1.1	1.8	1.1	0.74J	1.5
1,1,1-Trichloroethane	1	200	<1	<1	<1	<1	<1	<1	<1	<1
1,1,2-Trichloroethane	1	5	<1	<1	<1	<1	<1	<1	<1	<1
Trichloroethene	1	5	<1	<1	1.1	<1	<1	<1	<1	<1
Vinyl Chloride	1	2	<1	1.2	<b>5.7</b>	<1	<1	<1	<1	<1
Xylenes (total)	3	100000	<3	<3	<3	<3	<3	<3	<3	<3

Notes on last page.

## Summary of Groundwater Quality Data for November 2006

Clare Water Supply Site

Clare, Michigan

CONSTITUENT:	SITE:		WD-8	WS-10	WS-5
	TDL	CUO	A751888	A751883	A751902
			11/7/2006	11/7/2006	11/8/2006
COCs	TDL	CUO			
Benzene	1	5	<1	<1	<1
1,1-Dichloroethane	1	880	<1	<1	11
1,2-Dichloroethane	1	5	<1	<1	<1
cis-1,2-Dichloroethene	1	70	<b>130</b>	1.3	<b>150</b>
trans-1,2-Dichloroethene	1	100	9.7	<1	4.6
Ethylbenzene	1	700	<1	<1	<1
Methylene Chloride	2	5	<2	<2	<2
Styrene	1	100	<1	<1	<1
Tetrachloroethene	1	5	<1	<1	<1
Toluene	1	1000	1.5	1.7	0.5J
1,1,1-Trichloroethane	1	200	<1	<1	<1
1,1,2-Trichloroethane	1	5	<1	<1	<1
Trichloroethene	1	5	<b>8.7</b>	5	<b>14</b>
Vinyl Chloride	1	2	0.84J	<1	0.95J
Xylenes (total)	3	100000	<3	<3	<3

-- Not analyzed.

NA Not applicable.

J Estimated value; analyte was observed at a value less than the detection limit.

< Analyte was not detected; result is reported as less than the detection limit.

CUO - Clean up objective as specified in ROD.

**BOLD** indicates detected value is above the CUO.

Known Contaminant of Concern - as listed in ROD.

ug/L Micrograms per liter.

Note: Toluene results are a laboratory artifact (for most samples).

Toluene was present in all samples, trip blanks and equipment blanks.

Data validation has not yet been completed.

**Attachment F**  
**Review Comments and Responses**

**RESPONSE TO PROGRESSIVE ENGINEERING & CONSTRUCTION, INC.'s COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE PRB AND SOIL REMEDY AREAS, DATED NOVEMBER 8, 2006**

Item No.	Section	Page/Line/Para	Comment	Response
1	Section 2.1	pg 2, 4 <sup>th</sup> paragraph	Report references the drainage swale in the vicinity of the PRB as having a depth of 7-8 feet below land surface (ft bls). Survey data for the swale ranges from 840.49 to 840.15 feet above mean sea level (ft amsl) from west to east along the proximity of the PRB remedy compared to the top-of-ground data for the monitor wells nearest the swale (MW-308 and MW-311) of 843.3 and 842.4 ft amsl, respectively. Therefore, survey data indicate that the swale, in the vicinity of the PRB, is approximately 2-3 ft. deep.	The depth of 7-8 feet was taken from Lithologic Cross Section A-A' obtained from Progressive. If the cross section is incorrect, then the text will be revised to indicate a 2-3 foot depth. This shallow depth may explain why there is so little flow in the swale—it may receive very little to no groundwater discharge.
2	Section 2.2	pg 3, 4 <sup>th</sup> paragraph	Text should clarify who's professional judgment is being referenced here. Also, Progressive offers the following additional information regarding seepage velocities in the proximity of the soil remedy which may/may not impact the implication made in this paragraph: laboratory permeameter tests conducted by Dames and Moore (in 1990) on cores from borings SW-12 (4'-6'), SW-28 (8'-10') and B-29 (6'-8') yielded an average hydraulic conductivity for the clay layer of $4.3 \times 10^{-5}$ cm/sec; laboratory tests on cores from borings 208, 212 and B-29 yielded an average hydraulic conductivity for the underlying glacial till in the range of $1 \times 10^{-5}$ cm/sec; and based upon the November 2006 hydraulic data, this would put groundwater seepage velocity in the range of 2.3E-5 ft/day and 3.5E-5 ft/day for the clay and underlying glacial till layers, respectively.	Text regarding professional judgment will be clarified. Laboratory permeability tests on discrete soil samples may not provide an accurate representation of the hydraulic conductivity of the larger <i>in situ</i> water-bearing zone. For example, flow may occur through fracture networks that are not well-represented in the tested soil samples. Groundwater velocity estimates should be derived using hydraulic conductivity data from site-specific field tests (i.e., slug tests, pumping tests, tracer tests).
3	Section 3.3	pg 5, 1 <sup>st</sup> paragraph	Recommend that the final sentence of this paragraph be moved (and reworded as appropriate) to after the third sentence of same paragraph.	Change will be made.

**RESPONSE TO PROGRESSIVE ENGINEERING & CONSTRUCTION, INC.'s COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE PRB AND SOIL REMEDY AREAS, DATED NOVEMBER 8, 2006  
(Continued)**

Item No.	Section	Page/Line/Para	Comment	Response
4	Section 4.0		Groundwater quality data collected in November 2006 are available and attached for inclusion in the evaluation. The November data demonstrate significant concentration decreases for the overwhelming majority of the monitoring network.	The November 2006 data can be used by interested parties to evaluate the conclusions and recommendations made in the LTMO report. There is insufficient budget remaining to fully incorporate the new data into the evaluation and revise the report accordingly. However, the data will be reviewed qualitatively to determine the impact, if any, on the recommendations made. In addition, the data will be included in the final report as an attachment.
5	Section 4.1	pg 7, 1 <sup>st</sup> bullet	It should be noted that quarterly data were collected for a duration of 1 year, not two years as indicated, the frequency was then changed to semiannual.	Text and tables will be revised.
6	Section 4.1	pg 7, 2 <sup>nd</sup> bullet	Progressive would like to clarify that vertical aquifer sampling (VAS) was performed just subsequent to the PRB installation by Secor. The resultant data was used by Progressive prior to installation of the new PRB monitor wells (MW-301 to MW-313) to identify which borings should undergo VAS during monitor well installation for purposes of selecting the proper screened intervals. During the installation of MW-301 to MW-313, Progressive performed VAS at select locations and placed well screens within the vertical zone exhibiting the highest concentrations of contaminants of concern. Due to the VAS performed during the monitor well installation activities and given that the water table in this area has exhibited seasonal fluctuations of up to 5 ft at some locations, the 5-ft screens used are of an appropriate length to best monitor water quality in this area.	Comment noted. The referenced text in the 2 <sup>nd</sup> bullet still appears to be accurate and appropriate and no changes are proposed.

**RESPONSE TO PROGRESSIVE ENGINEERING & CONSTRUCTION, INC.'s COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE PRB AND SOIL REMEDY AREAS, DATED NOVEMBER 8, 2006  
(Continued)**

Item No.	Section	Page/Line/Para	Comment	Response
7	Section 4.1	pg 7, 5 <sup>th</sup> bullet and pg 8, 1 bullet	Progressive agrees with elimination of monitoring for MI 10 metals and reducing the frequency of monitoring for ferrous iron.	Comment noted.
8	Section 4.1	pg 8, 3 <sup>rd</sup> and 4 bullets	As stated above, the reference to the drainage swale depth being 7-8 ft is erroneous; actual depth is 2-3 ft based upon survey data. In addition, the swale is typically dry, and has only been observed to contain flowing water immediately subsequent to precipitation events and during periods of snow melt. Regarding the extent of definition of downgradient VOCs, Progressive asserts that as long as the concentrations exhibited in the monitor wells located south of the PRB continue to decline, monitoring further downgradient is unnecessary. Also, there is no need to monitor the area south of the swale due to existing MW-312 and SW-23. As of November 2006 analytical data for all wells south of the PRB exhibited VC concentrations less than the GSI criteria, with one exception, MW-308 which had a VC concentration of 20 ug/L, just 5 parts per billion above the GSI criteria. For these reasons, Progressive continues to maintain that the PRB area shallow groundwater monitor well network, installed pursuant to the <i>Final PRB Monitoring Work Plan</i> (dated 5/2/05) as approved with comments by USEPA (letter dated 5/11/05), is sufficient to provide the data necessary to monitor the performance of the PRB remedy. As decreasing concentrations have been the norm at all downgradient monitor locations, and there are no possible receptors in the near vicinity, there is no basis to support expansion of the shallow monitor network at this time.	<p>Depth of swale will be corrected if necessary as described in response to comment #1.</p> <p>The report did not contain definite recommendations for downgradient monitoring. The extent of definition of downgradient VOCs was presented as a potential data gap for stakeholder consideration. We agree that the November 2006 results are promising. However, some VC that exceeds the cleanup goal is bypassing the PRBs in the shallow zone, especially at MW-310 (21 to 27 µg/L in May and November 2006). There are no wells installed that could be used to define the downgradient extent of this contamination based on inferred groundwater flow directions for the shallow zone. It is likely that concentrations of concern are not migrating to the Clare site boundary to the south given the low magnitude of the concentrations and the fact the VC can degrade under a variety of geochemical conditions.</p> <p>Typically, the downgradient extent of contaminant concentrations exceeding cleanup goals is defined upfront during the site characterization stage, so that informed remedial decisions can be made based on knowledge of the plume extent and plume dynamics (i.e., is plume expanding, stable, or decreasing?).</p>



**RESPONSE TO PROGRESSIVE ENGINEERING & CONSTRUCTION, INC.'s COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE PRB AND SOIL REMEDY AREAS, DATED NOVEMBER 8, 2006  
(Continued)**

Item No.	Section	Page/Line/Para	Comment	Response
9	Section 4.1	pg 8, 5 <sup>th</sup> bullet	<p>The PRB was not designed to treat water in the intermediate and/or deep aquifers; references to the likeliness of the PRB treating these deeper aquifers are, therefore, not applicable. With regard to the extent of delineation of the intermediate and deep aquifers, it should be noted that historical data provides additional useful information for these aquifers. Monitor well 207 (located in the source area upgradient of the PRB and screened from 57-62 ft bls) exhibited non-detect results when it was last sampled in March 1994. Also, well W-4 (located approximately 400 ft downgradient of the PRB area and screened from 45-50 ft bls) exhibited concentrations all below 1 ppb when it was last sampled in June 1998. For your use, the coordinates of wells W-4 and 207 were 678713.39, 4854167.96 and 678562.58, 4854213.37, respectively. If installation of any additional wells were to be considered in this area, they would be installed for MNA use only.</p>	<p>Whether or not the PRB was designed to treat water in the intermediate or deep aquifers is not the point of this text. The text simply presents an observation that is relevant to the LTMO evaluation—namely that contaminants detected in the intermediate zone at 300B are not treated.</p> <p>Regarding the extent of delineation in the intermediate and deep zones, here are some relevant observations:</p> <ul style="list-style-type: none"> <li>--200 µg/L of VC was detected in well 300B in May 2006 (140 µg/L in November 2006), in groundwater that is not treated by the PRB. VC concentrations at this well were found to be statistically increasing based on data collected through November 2006.</li> <li>--Potentiometric maps in the 2005 Annual Report show this well to be located near the center of a potentiometric high, with flow occurring radially outwards in all directions from this area. Therefore, the flow direction in the intermediate zone at well 300B is not known with certainty. These maps indicate that there is not sufficient well control to confidently delineate the groundwater flow direction in the intermediate zone in this area.</li> <li>--There is not sufficient well control to confidently delineate the migration direction and extent of VC in the intermediate zone in this area.</li> <li>--VC is a relatively volatile and toxic compound that can pose an inhalation risk to occupants of overlying structures in some situations.</li> <li>--Therefore, the situation is that there is a VC plume containing concentrations that substantially exceed the CUO that is of unknown extent and migration</li> </ul>

**RESPONSE TO PROGRESSIVE ENGINEERING & CONSTRUCTION, INC.'s COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE PRB AND SOIL REMEDY AREAS, DATED NOVEMBER 8, 2006  
(Continued)**

Item No.	Section	Page/Line/Para	Comment	Response
				direction. Whether these information gaps are significant is a question for the stakeholders to determine based on risk analysis. Could these concentrations pose an inhalation risk to any potential indoor air receptors? Can this question be answered given the current level of characterization? These are the types of questions that need to be considered. It is our opinion that the historical data for wells 207 and W-4 do not provide definitive answers to these questions.
10	Section 4.2	pg 9 and 10, 4 bullet	Progressive maintains that there is no need to delineate south of the PRB per the above comments regarding Section 4.1, pg 8, 3 and 4 bullets. Progressive also reiterates that monitoring of the PRB area was performed on a quarterly basis for only one year, not two.	See responses to comments 5 and 8. The sampling frequency was corrected in the text and tables.
11	Section 4.3	pg 10, <sup>st</sup> and 2 bullets	Progressive agrees with the proposed semiannual sampling frequency, and we are also willing to perform semi-annual sampling at the wells (MW-312 and MW-313) where an annual frequency was recommended. Progressive agrees with the recommendations to eliminate MI 10 metals sampling and reduce the ferrous iron sampling frequency. The recent data (attached hereto) continue to demonstrate decreasing concentration trends at most PRB area wells; the inclusion of this data in your evaluation should alleviate the concern you identified of possible increasing concentration trends at MW-309 and MW-310. Progressive believes that performing hydraulic monitoring on a semi-annual basis should be sufficient for this area, and is interested to see the results of the GSI/Parsons evaluation of the hydraulic data (sent on 12/6/06 and attached to this memo for reference) to see which, if any, locations are identified	Evaluation of the hydraulic data submitted by Progressive is beyond the scope of what Parsons and GSI are budgeted to perform. In general, hydraulic monitoring for all wells located within the area of interest and screened within the depth zones of interest is recommended to maximize the accuracy of potentiometric surface maps. This recommendation is based on the observation that measurement of water levels in monitoring wells is generally relatively fast and inexpensive relative to water quality monitoring, and provides very important site characterization information. However, if multiple wells screened at similar depths are clustered in a small area and have similar groundwater elevations, one or more could be considered for removal from the hydraulic monitoring program unless more detailed

**RESPONSE TO PROGRESSIVE ENGINEERING & CONSTRUCTION, INC.'s COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE PRB AND SOIL REMEDY AREAS, DATED NOVEMBER 8, 2006  
(Continued)**

Item No.	Section	Page/Line/Para	Comment	Response
			for omission from the current hydraulic monitoring list due to redundancy.	delineation of local groundwater flow patterns is desired. At least two years of quarterly hydraulic monitoring is recommended to determine seasonal impacts on the potentiometric surface. After that, semiannual hydraulic monitoring during relatively wet and dry times (e.g., spring and fall) should be sufficient unless the quarterly monitoring results indicate significant seasonal variability that needs to be monitored more frequently. Hydraulic monitoring of all wells at the PRB and Soil Remedy areas is recommended. Text regarding hydraulic monitoring recommendations will be added to the LTMO report.
12	Section 4.3	pg 10, 3 <sup>rd</sup> bullet	Again, for the reasons stated above (see comments regarding: Section 3.3, pg 5, 1 paragraph; Section 4.0; Section 4.1, pg 7, 2 bullet; Section 4.1, pg 8, 3 and 4 bullets; and Section 4.1, pg 8, 5 bullet) Progressive disagrees that any further action is needed at the PRB area. However, we are prepared to reassess the adequacy of the program after two additional years (4 semi-annual events) of monitoring are performed in this area.	See responses to previous comments that pertain to this issue.
13	Section 5.0		As previously mentioned, the groundwater analytical data generated from November 2006 sampling are now available and are attached for your use and/or inclusion in your evaluation.	See response to comment #4.
14	Section 5.1	pg 10 and 11, 1 bullet	Progressive agrees that a reduction in the monitoring frequency at the identified locations is prudent.	Comment noted.
15	Section	pg 11, 3 <sup>rd</sup>	It should be noted that residual impacts were left in place outside of the slurry wall/cap when it was installed.	The report did not contain definite recommendations for additional monitoring downgradient of the

**RESPONSE TO PROGRESSIVE ENGINEERING & CONSTRUCTION, INC.'s COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE PRB AND SOIL REMEDY AREAS, DATED NOVEMBER 8, 2006  
(Continued)**

Item No.	Section	Page/Line/Para	Comment	Response
	5.1	bullet	<p>Placement of the slurry wall was restricted due to the presence of existing utilities and, therefore, containment of impacted soil and groundwater north of the remedy wasn't possible. Due to the lack of receptors in the vicinity, and the results of the most recent groundwater sampling event (November 2006) which exhibit stable to decreasing concentrations within the shallow aquifer, Progressive asserts that the monitor wells immediately outside the containment cell are sufficient to evaluate the performance of the remedy; and, if groundwater concentrations at these wells do not remain stable to decreasing further sampling/wells may be considered.</p>	<p>existing shallow well network. The extent of definition of downgradient VOCs was presented as a potential data gap for stakeholder consideration. The proximity of the Soil Remedy Area to the site boundary to the north makes it more important to confirm that TCE concentrations of concern are not migrating out of the area of institutional controls. In addition, there appear to be buildings across Highway 10 to the north; could there be vapor intrusion concerns that need to be considered given the presence of TCE north of the slurry wall? Stable TCE concentrations could indicate the presence of a continuing source that could potentially be feeding an expanding TCE plume. This is all conjecture of course but there are no downgradient data to either support or refute this observation.</p>

**RESPONSE TO PROGRESSIVE ENGINEERING & CONSTRUCTION, INC.'s COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE PRB AND SOIL REMEDY AREAS, DATED NOVEMBER 8, 2006  
(Continued)**

Item No.	Section	Page/Line/Para	Comment	Response
16	Section 5.1	pg 11, 4 <sup>th</sup> bullet	<p>Progressive agrees with the contention that the current number of intermediate wells in this vicinity lends to somewhat speculative hydraulic data evaluation. However, based upon the non-detect concentrations in downgradient intermediate wells 104 and 215 indicating no significant impacts in the intermediate aquifer, the deeps wells DMW-1D, DMW-2D, DMW-3D and UMW-1D all exhibiting concentrations below cleanup objectives, the lack of risk to receptors from possible impacts to the intermediate aquifer and the fact that additional water quality data from this area would not change the operation of the remedy, Progressive does not believe that additional characterization is necessary in this aquifer. Progressive would also like to note that the interpretation of the regional groundwater flow direction in this area may be skewed by the seemingly anomalous hydraulic data from 300B located at the PRB area. A depiction of the intermediate aquifer potentiometric surface that was generated with omission of data from 300B is attached for your consideration (we also attached a map depicting the potentiometric surface with 300B included for reference). This interpretation suggests that installation of three intermediate monitor wells along the north side of the containment cell (where the aquifer is currently monitored by intermediate wells 215 and to some extent 104) would not be helpful. However, Progressive is willing to install one intermediate well for hydraulic monitoring purposes in the area adjacent to the southeast corner of the soil remedy building.</p>	<p>Parsons does not agree that data for wells 104 and 215 lead to the conclusion that there are no significant impacts to the intermediate aquifer. These wells are approximately 440 ft apart, and they are screened at differing elevations (25 to 30 feet bgs for 215 and 42.6 to 47.6 ft bgs for 104). If a CAH plume in the intermediate zone was emanating from the soil remedy area it would not necessarily be detected in these wells.</p> <p>The alternate interpretation of the intermediate groundwater potentiometric surface provided by Progressive suggests that wells 215 and 104 may not be useful in determining impacts to intermediate zone groundwater quality. If this alternate interpretation is correct, then installation of two intermediate wells east (downgradient) of the soil remedy cell should be considered. In addition, installation of at least one intermediate well on the north side still seems reasonable to determine the vertical extent of identified contamination given the presence of a continuing source in that area.</p> <p>The reason for recommending one additional deep well was to allow monitoring of groundwater quality in the full range of potential groundwater flow directions from the soil remedy cell and to help confirm groundwater flow directions in the deep zone. Any additional wells could potentially be installed as temporary wells to allow collection of a groundwater sample and a water level elevation; they could then be abandoned if the results did not indicate cause for concern.</p>

**RESPONSE TO PROGRESSIVE ENGINEERING & CONSTRUCTION, INC.'s COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE PRB AND SOIL REMEDY AREAS, DATED NOVEMBER 8, 2006  
(Continued)**

Item No.	Section	Page/Line/Para	Comment	Response
17	Section 5.1	pg 12, 1 <sup>st</sup> bullet	<p>This bullet discusses shallow groundwater migration out of the soil cell based on 2005 groundwater level data. Please note that Progressive has since identified a flaw in the collection process of the hydraulic data within the containment cell that renders the soil remedy area shallow aquifer potentiometric contours suspect; i.e., field personnel were not allowing proper time for water levels to stabilize after breaking the vacuum seal of the extraction wells. Progressive has included the most recent (properly collected) hydraulic data contours for your use/information, and that map depicts a significant inward hydraulic gradient around the entire containment cell. Therefore, based upon the historically consistent operation of the soil remedy (lack of [unplanned] downtime), historical groundwater level data, the most recently collected shallow groundwater data, and the fact that the slurry wall is keyed into the clay, Progressive believes that this inward gradient has likely been maintained since installation of the remedy and seepage out of the cell in the shallow aquifer is unlikely. As such, there is no need to install another shallow well NW of the containment cell, and continued monitoring of existing wells DMW-1S, DMW-2S and DMW-3S will provide sufficient detail regarding the fate of residual impacts outside the cell.</p>	<p>Given the current operational schedule of 1 month on/5 months off and the inferred regional shallow groundwater flow direction toward the north-northwest, installation of one additional shallow well as indicated in the LTMO report does not appear unreasonable or excessive to confirm that the remedy is remaining protective over time.</p>

**RESPONSE TO PROGRESSIVE ENGINEERING & CONSTRUCTION, INC.'s COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE PRB AND SOIL REMEDY AREAS, DATED NOVEMBER 8, 2006  
(Continued)**

Item No.	Section	Page/Line/Para	Comment	Response
18	Section 5.1	pg 12, 2 <sup>nod</sup> bullet	Progressive agrees that the current number of deep wells in this vicinity lends to somewhat speculative hydraulic data evaluation, however, since there is no evidence that any significant impacts (above cleanup objectives) have migrated into the deep aquifer as exemplified by the historic concentrations exhibited at wells DMW-1D, DMW-2D, DMW-3D, UMW-1D, and the same can be said for the intermediate aquifer in this vicinity given the historic results for 104 and 215, there does not appear to be any justification for additional characterization of this aquifer.	Data for wells 104 and 215 may not be relevant for determining impacts to the intermediate zone given the alternate potentiometric surface map prepared by Progressive (showing a hydraulic gradient to the east). See also response to comment #16. The objective of the additional well installations recommended for consideration was simply to more fully cover the range of potential flow directions indicated by the available data. The justifications for addition of another deep well are stated in the report and include: 1) more accurate and site-specific determination of groundwater flow direction and vertical hydraulic gradient, and 2) obtaining groundwater quality data along a potential flowline from the soil remedy cell that is not currently monitored. How can we be sure that the existing deep wells are properly positioned if the hydraulic data are sparse and the potentiometric surface interpretation is somewhat speculative as a result?
19	Section 5.1	pg 12, 3 <sup>rd</sup> bullet	Based upon the most recent groundwater elevation data showing an inward hydraulic gradient around the containment cell in the shallow aquifer, it is likely that seepage out of the containment cell in the shallow aquifer is insignificant. Per the additional information provided above (see comment on Section 2.2), the groundwater seepage velocity is likely in the range of 2.3E-5 ft/day and 3.5E-5 ft/day for the clay and underlying glacial till layers, respectively. Impacts detected in groundwater outside of the containment cell are likely from residual source material that was left in place as previously discussed.	See response to comment #2.

**RESPONSE TO PROGRESSIVE ENGINEERING & CONSTRUCTION, INC.'s COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE PRB AND SOIL REMEDY AREAS, DATED NOVEMBER 8, 2006  
(Continued)**

Item No.	Section	Page/Line/Para	Comment	Response
20	Section 5.1	pg 12, 4 <sup>th</sup> bullet	There is no threshold value or trigger concentration for additional assessment. So long as routine monitoring results continue to exhibit stable or non-increasing trends (below the pre-startup levels), there is no reason for additional assessment.	Comment noted.
21	Section 5.1	pg 13, 1 <sup>st</sup> bullet	It should be noted that the operating frequency of the soil remedy has been reduced to 1-month on / 5-months off (as of November 2006, per EPA approval). Should sample results indicate that influent concentrations have significantly rebounded when the system is restarted in May 2007, Progressive will sample the individual extraction wells to assist with further optimization of the remedy.	Comment noted.
22	Section 5.3	pg 14, 1 <sup>st</sup> bullet	Progressive agrees with the recommended sampling frequencies. Progressive believes that performing hydraulic monitoring on a semiannual basis should provide sufficient hydraulic information for this area, and is interested to see the results of the GSI/Parsons evaluation of the hydraulic data (sent on 12/6/06 and attached to this memo for reference) to see which, if any, locations are identified for omission from the current hydraulic monitoring list due to redundancy.	See response to comment #11. Given the already sparse density of water level measurements in this area and resulting uncertainty regarding groundwater flow directions, particularly in deeper zones, periodic collection of water level measurements in all wells associated with the soil remedy area and all nearby wells is recommended.



**RESPONSE TO PROGRESSIVE ENGINEERING & CONSTRUCTION, INC.'s COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE PRB AND SOIL REMEDY AREAS, DATED NOVEMBER 8, 2006  
(Continued)**

Item No.	Section	Page/Line/Para	Comment	Response
23	Section 5.3	pg 14, 2 <sup>nd</sup> and 3 <sup>rd</sup> bullet	<p>Progressive does not agree that further characterization of the shallow aquifer is warranted based upon the hydraulic performance of the remedy (as demonstrated for November 2006 in the attached figure), the stable to decreasing concentrations exhibited by the shallow aquifer monitoring and the lack of risk to receptors. Progressive does not agree that further characterization of the intermediate aquifer is necessary based upon the non-detect concentrations in downgradient intermediate wells 104 and 215 indicating no significant impacts in the intermediate aquifer, the concentrations all below cleanup objectives exhibited by deep wells DMW-1D, DMW-2D, DMW-3D and UMW-1D, the lack of risk to receptors from possible impacts to the intermediate aquifer and the fact that additional water quality data from this area would not change the operation of the remedy. However, Progressive will agree to install one new intermediate monitor well for hydraulic monitoring purposes, and suggests locating that well adjacent to the southeast side of the soil remedy building to improve the hydraulic monitoring network in that area.</p>	See above responses to comments pertaining to these issues.
24	General		<p>Progressive does not agree that further characterization of the deep aquifer is necessary since there is no evidence that any significant impacts (above cleanup objectives) have migrated into the deep aquifer as exemplified by the historic concentrations exhibited at wells DMW-1D, DMW-2D, DMW-3D, UMW-1D, and the same can be said for the intermediate aquifer in this vicinity given the historic results for 104 and 215.</p>	See above responses to comments pertaining to these issues.

**RESPONSE TO MDEQ COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE**

Comments on the preliminary Long-Term Monitoring Optimization memoranda for the Stageright, PRB and Soil Remedy areas of the Clare Water Supply Superfund site were received from three parties at MDEQ: Barbara Vetort, Mark Henry and John Spielberg. The comments are addressed below, with comments grouped according to similar topic areas.

Commenter	Area	Page/Lin e/Para	Comment	Response
<p>JS Comment 1a</p> <p>BV Comment 4 (page 2 paragraph 3)</p>	<p>General</p>		<p>(JS) The agencies and the PRPs would really benefit from having data in electronic format all in one place. The data should include all the source areas: Mitchell, Ex-Cell-O, StageRight, American Dry Cleaners, Stanley Oil, Standard Oil, MDOT bulk storage, etc. The data should be raw data as reported by the laboratories, including detection limits and qualifiers. CAS numbers for the parameters tested is also a good idea. Most laboratories can provide data in electronic, database format.</p> <p>(BV) The recommendation to combine groundwater elevation data collected from Stageright wells with data collected from the rest of the site wells to facilitate a more complete picture of groundwater hydraulics east of Stageright should be implemented. The current level of plume definition is not acceptable in the Stageright area.</p>	<p>The authors agree that all site analytical data should be maintained in an electronic database, accessible to all stakeholders. Proper data management is central to all site optimization efforts. Progressive Engineering is maintaining a <i>site-wide electronic database</i>, and they have done an excellent job under the circumstances. The Progressive database contains both analytical and hydraulic monitoring data for the entire site. The authors suggest that the site database be made available to all stakeholders. An updated database should be distributed to stakeholders after the results of each sample event are added.</p> <p>Inclusion of validated data in the database as opposed to raw data (assuming that data validation is performed) is recommended.</p> <p>The database used for the LTMO efforts will be included on CD in the final report.</p> <p>As a general observation, the addition of current and future monitoring data to the database is a fairly simple matter as data are now delivered in electronic format from most labs.</p> <p>The addition of historic information to the electronic database is more problematic. Often, these data are only available in hard-copy and must be added</p>

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
				<p>manually. Frequently, data are missing detection limits, method names or data flags. Manual addition of data is an expensive process and the opportunity for introducing transcription errors is extremely high. Specific elements of the historic data set should be prioritized and added to the database as time and budgets permit. Priority data include concentrations of constituents that exceed screening levels and detected compounds.</p> <p>The authors would also suggest that a sample location table be maintained in the site database. Sample locations tables generally include information such as the well name (and any historic names), the depth, top of casing, screened intervals, geographic coordinates, and date of installation. A location table can be useful for documenting details such as VAS. A table with groundwater parameters such as K values would be extremely helpful for a site this complex.</p>
<p>JS Comment 2a</p>	<p>Stageright</p>		<p>The MDEQ believes this area is the highest priority area at the site to be dealt with</p>	<p>The authors agree.</p>
<p>JS Comment 2b</p>	<p>Stageright</p>		<p>The MDEQ supports the objective of determining whether this area was characterized sufficiently. One way this can be evaluated is by finding out which wells were vertically sampled prior to setting the well screens. If vertical aquifer sampling (VAS) was insufficient, then this may need to be completed prior to implementing an LTMO in this area, or in conjunction with the LTMO.</p>	<p>Generally speaking, characterization of the vertical extent of contamination is desirable. Vertical sampling is generally part of site characterization. The authors were not provided with VAS information.</p> <p>Some sites benefit from a formal <i>conceptual site model</i> document detailing well installation details, groundwater parameters, source areas, transport mechanisms, geotechnical evaluations, receptors etc. It can be very useful to put all of the site data in one location for all stakeholders.</p>

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
				In most cases, consensus on site characterization and site conceptual model should be largely complete <i>before</i> monitoring networks are optimized. As a general rule, the LTMO scope of work is limited to determining if a sufficient number of wells exist spatially to achieve monitoring objectives. The authors are not funded or scoped to performed a detailed review of the site investigation as part of the LTMO evaluation.
JS Comment 2c	Stageright		The MDEQ agrees that the shallow zone has not been well characterized. This zone needs better definition. The shallow water-bearing zone and the vadose zone above it may potentially contain a smear zone containing a continuing source of TCE and other contaminants. Past contamination near the water table could have moved up and down with rising and falling water levels, thus causing the vertical smearing of contamination in this zone.	See comment 2b above. A 'smear zone' is typically present at sites that have had floating free product (e.g., petroleum product), whereas TCE does not float on the groundwater surface. Continuing sources of contamination would be an element included in a conceptual site model.
JS Comment 2d	Stageright		Any new wells installed should be completed with the benefit of VAS to determine the zones of highest contamination	Comment noted. The authors agree that long-term monitoring wells should be screened within the zone containing the highest dissolved contaminant concentrations to the extent practical.
JS Comment 2e	Stageright		MDEQ agrees that chloride, alkalinity and TDS sampling and analysis can be reduced	Comment noted.
JS Comment 2f and BV	Stageright		(JS) Would be best to have the complete data set for this area rather than just summaries that show exceedances of cleanup objectives. Electronic format data in spreadsheets would be better than hard copy.	See comment 1a, above.

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
Comment (page 1 paragraph 3)			(BV) The MDEQ Superfund staff has not received the majority of the necessary TCRA data to include the boring logs and analytical data. Therefore, the MDEQ Superfund staff cannot verify the technical information used for the optimization.	
JS  Comment 2f  And BV Comment 2 (page 2, paragraph 1)	Stageright		<p>(JS) An assumption was made by the optimizers that missing data meant that concentrations were non-detect. MDEQ agrees that evaluating this assumption with more complete historical data is a good idea.</p> <p>(BV) This report states that Progressive Engineering provided the data for optimization. Progressive Engineering is not the Stageright TCRA consultant. This report states that not all the data collected by the Stageright consultant, MACTEC, was included, therefore the Optimizers assumed the results were non-detect. The Optimizers state that historical constituent concentrations should be confirmed before the Long-Term Monitoring Program is finalized. The Agencies need to confirm that all the Stageright data and well logs are comprehensive and accurate.</p>	<p>Many times it is difficult to track historic data from former or uncooperative consultants and to translate it from hard-copy to electronic data. (See comment 1a above).</p> <p>The authors were told by Progressive that 'missing data' were assumed to be non-detect results. The authors did not have access to hard-copy data from previous site investigations to verify concentrations and detection limits, so, had to accept the dataset as delivered.</p> <p>As a general note, most LTM networks are optimized for one to two major contaminants of concern (COCs), when the less prevalent contaminants are contained within the plume of the priority COCs. In the case of Stageright, TCE is the parent compound, and appears to be most widespread with the most exceedances. Data for TCE in the Stageright area are recorded in the site database, and include non-detect results. For this reason, the authors proceeded with the analysis. The optimization was performed for TCE with other compounds considered qualitatively to evaluate and confirm recommendations.</p>

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
<p style="text-align: center;">JS</p> <p>Comment 2g</p> <p>And BV Comment 3 (page 2, paragraph 2)</p>	<p style="text-align: center;">Stageright</p>		<p>(JS): Exclusion of site-wide monitoring wells in this area (e.g., 211, D-106, D-107, WD-10) should not be assumed to mean they should be excluded from site-wide monitoring.</p> <p>(BV): I agree with the majority of recommendations that are outlined on pages eight and nine. One exception, the recommendations include excluding wells that are not associated with the Stageright TCRA. Therefore, excluding wells 211, D106, D107, and WD10 is not appropriate for the well field remedial action.</p>	<p>One of the central activities of LTMO is to determine to what extent an individual monitoring location provides unique information in support of <i>site monitoring objectives</i>.</p> <p>A major issue of the Clare Water Supply ROD and associated documents is that groundwater monitoring objectives are not explicitly defined. Without explicit monitoring objectives the goal and significance of monitoring any individual location can be interpreted differently by each stakeholder.</p> <p>Based on qualitative and statistical evaluation, the deep wells recommended for removal from routine monitoring did not provide unique information significant to Stageright site management decisions. However, as MDEQ has expressed concern over removal of these locations, their contribution and suggested sample frequency will be revisited and any recommendations will be better explained in the final report. Even if these wells are not recommended for further sampling connected to the Stageright site, they could be retained for the site-wide monitoring program, which was not evaluated.</p>
<p style="text-align: center;">JS</p> <p>Comment 2h</p>	<p style="text-align: center;">Stageright</p>		<p>Deep zone well P-202 is too close to municipal well MW-5 to be useful as a sentinel well. The optimizers say this area is not well monitored. Therefore, better characterization of this zone is needed. Another deep zone well should be installed near the east edge of the StageRight parking lot, just south of MW-8-97.</p>	<p>Given an estimated deep aquifer seepage velocity of approximately 18 ft/d, all current wells are too close to MW-5 to function as sentinel wells in the short term. Well MW-10-97 is approximately 2 weeks travel time to MW-5. Most analytical samples require at least 2 weeks to process. Data review is usually much slower than analysis, and action, slower, yet.</p> <p>With these limitations, sampling P-202 provides a</p>

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
				<p>long-term, well-documented metric of plume stability. The well shows decreasing trends. Installation of another deep zone well should be accompanied by an explicit monitoring objective the well will fulfill and, if necessary, expedited chemical analysis to achieve the objective.</p>
<p>JS Comment 2i</p>			<p>MDEQ would like an explanation of how the average TCE concentration reported in Tables 4 and 7 is used. Is it used in any other calculation or statistic? Or, is it just a benchmark to compare against the CUO and MCL?</p>	<p>Average TCE concentration is a simple statistical benchmark used in a general way to identify high, medium and low concentration wells relative to the regulatory screening levels.</p> <p>Taken together with the maximum concentration, sample size, and concentration trend, the average concentration provides a summary of information relevant to defining the area of regulatory concern and the function of the location in the monitoring network.</p>
<p>JS Comment 2j and 3a</p>			<p>The new municipal well, MW-8, was not mentioned. It should be noted on the site maps, and considered in the LTMO evaluation. Even though this well is outside the StageRight area, it is a potential receptor of contaminants from StageRight. Because of this, it should be considered in the evaluation.</p>	<p>The new municipal well was installed as we finished the draft report. The authors were not informed of its construction until after the analysis was performed.</p> <p>We do not have the coordinates for the well or any information on its screened interval, pumping rate or preliminary concentrations of priority COCs. Because this well was installed near an existing contaminant plume, it should be sampled periodically same as other nearby active water supply wells.</p>
<p>BV Comment 1 (page 1,</p>	<p>Stageright</p>	<p>General</p>	<p>There is no site conceptual model presented to provide the basis for the optimization effort. Were the remedial design MODFLOW files used for this project? Since they</p>	<p>As far as the authors know, there is no single document describing a consensus site conceptual model for the areas of concern. (For further discussion of site conceptual model and site</p>

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
paragraph 2)			were not cited, we assume these files were not used.	<p>characterization, see Comment 2b)</p> <p>The site conceptual model was not detailed in the draft memorandum for the Stageright Area (or PRB/Soil Remedy). A brief summary of relevant conceptual model information provided to the authors will be included in the final memorandum.</p> <p>The authors reviewed the data received, which included the RODs, 5-year review, potentiometric surface maps, cross-sections and analytical database. Supplemental data on seepage velocity, porosity, groundwater flow direction, etc. were supplied by Progressive.</p> <p>LTMO is not generally a groundwater flow modeling effort. MODFLOW files were neither requested nor made available to us, nor were the results of site modeling made available.</p>
BV Comment 4 (page 2, paragraph 4)	Stageright		The Long-Term Monitoring Optimization (LTMO) states that a change in site conditions might warrant resumption of monitoring at some time in the future at wells that are not currently recommended for continued sampling. A contingency plan specifying this should be a part of any changes to the groundwater monitoring program. In addition, every five years a complete round of analytical sampling for all wells should be performed to verify that the LTMO remains effective. This comprehensive monitoring was stated as a requirement by the former Potentially Responsible Party's consultant in the 1994 Remedial Design Remedial Action Work Plan.	<p>The authors agree.</p> <p>Contingency plans should be related to the stated monitoring objectives. Both should be published in a site management document.</p>
BV Comment 5	PRB Area		I am concerned that the MDEQ technical support staff was not given adequate input on the site conceptual	CSM information was provided to the authors by Progressive and the USEPA, and is summarized in



**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
(page 2 paragraph 5)			model used as the basis for the LTMO.	Section 2 of the LTMO report. Groundwater input parameters are listed in Table 2 of the LTMO report.
BV Comment 6 (page 2 paragraph 6)	PRB Area		For example, in Section 2.1 PRB area, it states that the shallow groundwater flow direction is south-to-southeast across the PRBs. This has not been verified by existing site data. The remedial investigation reports the shallow aquifer permeabilities range from $10^{-3}$ to $10^{-5}$ , rather than $10^{-7}$ .	<p>Existing potentiometric surface data indicate that the groundwater flow direction is roughly S/SE in the vicinity of the PRB; however, the authors concur that the site is not fully characterized as detailed in Section 4.1 of the LTMO report. The hydraulic gradient information derived from water level measurements was used to infer the groundwater flow direction; this is the standard practice at a majority of contaminated sites.</p> <p>It appears that a range of aquifer hydraulic conductivities have been reported for various geologic units; consensus values should be determined as part of the CSM review. At least some of the K values reported in the RI report appear to have been derived from laboratory tests of soil samples, and may not accurately represent field-scale K values. The range of 1E-07 to 5E-07 cm/sec given in the text of the report was derived from lithologic cross-sections provided by Progressive and contained in Attachment A of the report. The Dames &amp; Moore RI report states that the till has a hydraulic conductivity on the order of <math>10^{-7}</math> cm/sec.</p>
BV Comment 7 (page 3 paragraph 1)	PRB Area		The PRB remedial action area is still completing the first two years of remedial action monitoring. The MDEQ Superfund staff has stated that the PRB should not be optimized until the remedy is demonstrated to be operating effectively. It is premature to optimize the monitoring program at the PRB area. The current level of plume definition is not acceptable in this area.	<p>Comment noted. The authors concur, for the most part. Concrete metrics should be developed for determining if the remedy is operating effectively.</p> <p>As a general note, given a sufficiently long sample record, recommendations for <i>current</i> sampling locations and frequency can be made while site characterization efforts are on-going. While areas of site characterization uncertainty can be <i>identified</i> during LTMO, specific actions to address site</p>

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
				characterization must be based on stakeholder consensus. The authors believe that the LTMO recommendations made in the report are reasonable; however, they should be reassessed as noew data are obtained.
BV Comment 8 (page 3 paragraph 3)	Soil Remedy		The last sentence in the second paragraph states that the groundwater monitoring wells DMW1S, DMW2S, and DMW3S, in May and November 2005 ranged from 8 to 13 feet bgs. The report states this is a few feet below the bottom of the emplaced soils and near the top of the till. The emplaced soils (soil from Mitchell area) are essentially at the former ground surface, the till is below the upper aquifer. Please clarify this sentence.	A reference to cross-sections drawn by Secor and contained in Appendix A will be added to this text. These cross-sections show the water table being present a few feet below the bottom of the emplaced 'Mitchell' soils.
BV Comment 9 (page 3 paragraph 4)	Soil Remedy		The receptors for the upper aquifer are the municipal well field. The seepage velocities for this area are too low. The Dames & Moore Remedial Investigation (RI) reports the upper aquifer to be 10 <sup>-5</sup> .	Seepage velocities appear to vary across the site. Consensus representative velocities are needed for LTMO, and should be supplied by the stakeholders. As stated in Section 2.2 of the report, we agree that the seepage velocity obtained from Progressive for the area outside the soil treatment cell is too low.
BV Comment 10 (page 3 paragraph 5)	Soil Remedy		The Optimizers state that they did not have a complete data set for Vinyl Chloride for this area. The soil remedy area should have a complete data set for the wells discussed, back to their installation date, which is the same as the soil remedy completion date, circa 1999. RI wells are present around the soil remedy area, were their data sets complete? Some of the issues with the data set are related to Quality Assurance/Quality Control problems that were experienced during the groundwater monitoring sampling events.	For wells DMW 1S-3S and 1D-3D, the site database contains vinyl chloride results from 2005 – 2006. TCE data are recorded from 1999 -2006. (See Comment 1a). Other wells in the area have a more complete data set for vinyl chloride, with results for SW-9 extending to 1988. These wells are not closely associated with the soil remedy area.
BV Comment 11 (page 3 paragraph 6)	Soil Remedy		I agree with the recommendations for the Soil Remedy Area. However, I recommend annual rather than biennial sampling for UMW1D and UMW1S.  This evaluation does not look at any data older than 1999. There is data for many of the existing wells that	Annual sampling for UMW1D and UMW1S to address 'background' water quality or to determine if constituents from outside the soil remedy area are migrating toward it is potentially reasonable. However, if the groundwater flow velocity in this area is indeed very low, then annual sampling may

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
			goes back to the 1980s. Why isn't this data evaluated for at least some key wells? The current level of plume definition seems adequate in this area.	<p>be overkill because abrupt changes in upgradient groundwater quality that could impact the soil remedy area would be unlikely.</p> <p>For LTMO, 'recent' analytical data are given higher priority as historic data may have been collected under different sampling or analysis protocols. Often historic data have higher detection limits, and outliers that can skew statistics. Recent data are more likely to be comparable. Of the wells evaluated, only well 215 had data collected prior to 1999; these data were used in the qualitative evaluation of this well.</p>
MH Comment 1	Stageright General Comment		1) From the information provided it seems that there are very few shallow monitoring wells associated with the part of the site. Has the shallow of the aquifer been shown to be clean? The data indicates that a rather substantial source of contamination exists at the site. If this source material is in the vadose zone, then there would be substantial contamination in the shallow portion of the aquifer which could discharge to the nearby wetlands.	Comment noted, see Comment 2b on site characterization.
MH Comment 2	Stageright General Comment		2) Since this document deals with optimization of the monitoring well network, it would be best if the Agencies took into account whether or not the individual monitoring well locations had been characterized using vertical aquifer sampling (VAS) techniques. More weight should be placed on the value of the data from a particular part of the site where VAS has been used to define the vertical and horizontal extent of contamination. MACTEC should be able to provide this information.	<p>Comment noted, see Comment 2b on site characterization.</p> <p>Well weighting is possible for both qualitative and MAROS evaluations.</p>
MH Comment 3	Stageright		3) There is a column in Table 4 that indicates the average concentrations found in the individual wells. I'm not sure that the average concentrations are very	Comment noted. See comment response 2i above.

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
	General Comment		appropriate for decision making purposes unless the geochemistry at that location is at steady-state.	
MH Comment 4	Stageright  General Comment		4) The documentation for the MAROS software package (Appendix B) that was used for the evaluation does not speak to the basic assumption that the site is well characterized and that the existing monitoring well network actually represents the plume. This presumed assumption has been violated at each of the 3 source areas (Stageright, Mitchell and ExCello). At each of these areas there exists groundwater contamination that has not been delineated in magnitude or area. Integral to a “moment analysis” would be a thorough understanding of the distribution of that mass. The MAROS evaluations of these areas identified these deficiencies. The MAROS evaluations reinforce the fact that these sources are not fully defined – especially in the deeper portions of the aquifer. The lack of definition of the individual sources precludes an understanding of the interactions between them, or the cumulative effects of the three.	Comment noted, see Comment 2b on site characterization and BV Comment 7.  While the extent of all identified groundwater contamination has not been fully delineated (based on data supplied to the authors) sufficient data are available for a subset of wells to optimize the monitoring approach in limited areas.  Collecting more data than is needed in one area does not help the lack of data in another. The authors maintain that some current locations can be monitored at a reduced frequency while the site undergoes further characterization.
MH Comment 5	Stageright  General Comment		5) There has been no discussion of the capture zone of the municipal wells in the vicinity of the site. I suspect that all parts of the site are within the capture zone of the municipal system.	No data were provided on the pumping rate and capture zone of the public supply wells. The authors assumed (based on gw flow velocity and potentiometric surface) that the capture zone extended across the entire Stageright area. It was also assumed that the Stageright plume does not extend east of the municipal well MW-2.
MH Comment 6	Stageright  General Comment		6) This optimization process should be repeated once the site-wide data gaps have been filled and we have a better understanding of the contaminant distributions and transport pathways.	Comment noted; the authors concur with this comment. Optimization should be a dynamic process and LTMO conclusions and recommendations should be reassessed as new data are obtained.

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

<b>Commenter</b>	<b>Area</b>	<b>Page/Lin e/Para</b>	<b>Comment</b>	<b>Response</b>
MH Specific Comment 1	Stageright  Specific Comment		1) Page 4, pp 1; The documents states that there was an assumption made that all the missing data are non-detect. This should be checked into, and if found not to be true, the entire process should be reevaluated.	Comment noted. The authors do not have access to the missing data, which may be in hard copy form.
MH Specific Comment 2	Stageright  Specific Comment		2) Page 4, pp 3; The end of the paragraph states that the number of wells screened in the shallow zone was insufficient to perform a statistical analysis. From this one could conclude that the contamination in the shallow zones cannot be statistically evaluated using the software employed.	The number of wells screened in the shallow zone was insufficient to perform a spatial statistical analysis using MAROS. Concentration trends at individual well locations could be evaluated if there were sufficient sample events, but these wells have not been sampled regularly.  Is there a reason these wells are not sampled? Dry?
MH Specific Comment 3	Stageright  Specific Comment		3) Page 5, pp 1; This paragraph discusses the recommendations being based on the assumption that the "relatively rapid [groundwater] velocity will continue in the future". I also suggest that the In this part of the facility, the groundwater velocity is high because of its proximity to municipal production wells. A new production well has been installed in a near proximity to the Stageright facility. If the new well is not pumping at the same rate or from the same vertical interval as the pumping parameters used in the assumptions of the optimization model, the model may have to be reevaluated.	The authors agree. The new well was added, unknown to the authors, near the end of the analysis.  However, the groundwater velocity in this area most likely will not decrease significantly due to installation of a new extraction well.
MH Specific Comment 4	Stageright  Specific Comment		4) Page 5, pp 3; This paragraph suggests that the site characterization should be performed and suggests an additional monitoring well pair be installed. Any site wells should be installed using VAS techniques. Beyond just installing two additional wells additional characterization should be undertaken to determine the distribution and magnitude of the source.	Comment noted.

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
MH Specific Comment 5	Stageright  Specific Comment		5) Page 5, last paragraph; The document suggests that fewer contaminants could be analyzed during sampling events. If the Agencies agree that this is the best approach, then I suggest that periodically the entire list of contaminants included in an EPA Method 8260B analysis be evaluated	The rationale for this approach should be clearly identified. Once COCs are identified, analysis for other contaminants should not be necessary unless new releases occur or hydraulic conditions change. However, given that the cost of a full 8260 analysis is not likely to be substantially more expensive than an abbreviated analysis, periodic analysis for a full analyte list should not have significant cost impacts.
MH Specific Comment 6	Stageright  Specific Comment		6) Page 6, pp 2; I would agree, continuing to monitor the groundwater for chloride, TDS and alkalinity on a regular basis is not providing information that cannot be gained on a much less frequent basis.	Comment noted.
MH Specific Comment 7	Stageright  Specific Comment		7) Page 7, pp 3; The recommendation is made to exclude MW-2-99 and MW-6-97 from the monitoring program, yet in the first paragraph of the following page the statement is made that near MW-6-97 the aquifer is "not well defined". This is counterintuitive.	Groundwater flow and contaminant transport in the Stageright area appears to be heterogeneous and channelized, with high concentrations (MW-1-02) adjacent to low concentrations (MW-6-97). The nature of the hydrogeology at and between the six points identified in Figure 6 should be clarified as part of a consensus conceptual site model.  This said, MW-2-99 and MW-6-97 do not help characterize the contaminated part of the aquifer. They probably identify an area with lower flow velocity or some sort of hydrogeological discontinuity. Because they do not characterize the contaminated zone very well, they do not provide significant information to support management decisions. Routine monitoring of these wells is not particularly efficient.
MH Specific Comment 8	Stageright  Specific Comment		8) Page 8, pp 1; The document states the intermediate groundwater zone to the east of MW1-02 and MW-6-97 is not well defined. I suggest that VAS be performed and/or a monitoring well cluster be installed in this area.	The groundwater quality is not delineated to the east of wells MW-1-02, MW-6-97 and MW-8-97. Plume delineation efforts are recommended for this area.

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

<b>Commenter</b>	<b>Area</b>	<b>Page/Lin e/Para</b>	<b>Comment</b>	<b>Response</b>
MH Specific Comment 9	Stageright  Specific Comment		9) Page 8, pp 2; The document points out that the groundwater velocity near MW-5 is extremely rapid and that concentrations are largely stable or decreasing. This indicates to me that that there is a moderately large source of parent contaminant at the site that may exist as a non-aqueous phase liquid.	Decisions on source area treatment can be complicated. The reference in footnote 4 below may be of help.  This is outside the scope of LTMO. All we can say now is that under current conditions, the plume appears to be stable. The magnitudes of dissolved contaminant concentrations are not indicative of the presence of significant NAPL. It is possible that sorbed contaminants are continually 'bleeding' into the groundwater in the source area.
MH Specific Comment 10	Stageright  Specific Comment		10) Page 8, pp 5; This paragraph in the recommendations suggests additional monitoring is needed east of MW-6-97. This should include VAS.	See response to Comment 8
MH PRB Comment 1	PRB General Comment		1) The document does not discuss any data gaps surrounding the permeable reactive barrier (PRB) wall.	Data gaps for the PRB area are discussed in Section 4.1 of the report.
MH PRB Comment 2	PRB General Comment		2) Are there institutional controls in place for all parts of the site to which contamination exists or could migrate to?	We have been told that institutional controls cover the entire Clare Water Supply site. However, the exact nature and extent of the institutional controls are unknown to us.
MH PRB Comment 3	PRB General Comment		3) How much sensitivity analysis was performed for the models and statistical software packages to bracket the range of values used in their assumptions?	None. We requested values for the input parameters from Progressive, and received, what should be, the consensus values established after a thorough site investigation. The LTMO analysis was not a modeling effort.  However, as part of the qualitative evaluation, groundwater potentiometric surface maps, reports and analytical data were reviewed. The memoranda indicate cases where the data reviewed did not mesh with input parameters supplied.

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
MH PRB Comment 4	PRB General Comment		4) The hydrogeology of the entire site should be looked at as a whole. Isopotential maps should include all parts of the site and should be updated following each monitoring event.	Comment noted.
MH PRB Comment 1	PRB Specific Comment		1) Page 2, pp 1; The document describes the surficial unconfined aquifer as perched water. "Perched" suggests that the aquifer rests above some dry vadose soils. This is not the case. This unconfined portion of the aquifer becomes continuous with the main (deeper) aquifer to the east of the PRB.	<p>Perched aquifers are aquifers that have a relatively low-permeability confining layer (aquiclude) below the groundwater, and sit above the main water table. Information supplied to the authors suggests that the surficial aquifer is perched above a relatively low-permeability till unit in the area of the PRB.</p> <p>Perched water is usually more susceptible to fluctuations caused by seasonal influences. While the perched water may discharge to the main aquifer to the east or to the ditch to the south, in the area of the PRB, the surficial unit is technically perched.</p>
MH PRB Comment 2	PRB Specific Comment		2) Page 2 bullet 1; To the best of my knowledge, monitored natural attenuation (MNA) is not part of the ROD remedy. In this bulleted section, one of the goals should be to effect reliable source control measures.	<p>In order to collect data in support of monitoring objectives, it is good to have monitoring objectives.</p> <p>As there are no explicitly defined monitoring goals for the PRB area, the authors created some. The first bullet includes evaluating the effectiveness of source control measures, which is essential in implementing 'reliable source control measures' as stated in the comment.</p> <p>Under monitoring goals for the PRB, the authors do not mention monitored natural attenuation (MNA) as a remedy strategy. However, the authors do acknowledge the existence of natural attenuation processes. Vinyl chloride is biodegraded aerobically (see reference Note 5), and physical processes such as dilution and dispersion contribute to reduced concentrations downgradient from a source. Collectively, these processes are known as 'natural attenuation', and this is what was meant in</p>



**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
				<p>the statement.</p> <p>Although MNA is not a formal part of the remedy identified in the ROD, in reality it is part of the remedy that is being relied upon because there are VOC concentrations that exceed cleanup goals that are not being treated by the PRB. This should not be ignored, regardless of whether or not MNA is included in the ROD.</p> <p>The combined influence of the PRB and natural attenuation processes limit the extent of groundwater affected with constituents above regulatory limits. The goal of the monitoring program should be to evaluate the extent of groundwater above regulatory screening levels.</p> <p>Later in the report, the authors point out that MNA appears to be a tacit remedy for intermediate and deep groundwater in the PRB area, as the PRB's do not extend to deeper areas of contamination. This comment will be edited, as it is misleading.</p> <p>The authors did not include confirmation of source control as a monitoring objective, as no source of constituents was identified to us. However, the authors would support monitoring of the source area, once it is identified. The ROD (1992) states that "a source removal action was undertaken by one of the PRPs in this area under an order from the MDNR", but it is not clear if this was the source of vinyl chloride in the PRB area.</p> <p>In the future, identification of the source of vinyl chloride and a complete statement of monitoring objectives may be included as part of a Site Conceptual Model.</p>
MH PRB	PRB		3) Page 2, Section 2.1, pp 2; The statement is made that the shallow groundwater direction is south to	Comment noted. The groundwater flow direction was inferred from the measured hydraulic potentials,

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

<b>Commenter</b>	<b>Area</b>	<b>Page/Lin e/Para</b>	<b>Comment</b>	<b>Response</b>
Comment 3	Specific Comment		southeast, across the PRB. Simply demonstrating a hydraulic potential across the PRB (4 times per year) is not equivalent to demonstrating flow through the PRB.	which is a typical practice. The authors agree that the flow direction is inferred, and not specifically demonstrated. The text will be revised to better indicate this.
MH PRB Comment 4	PRB Specific Comment		4) Page 2, Section 2.1, pp 4; The document states that the wetlands area directly recharges the aquifer. Is this known or assumed?	The ROD (1992) states "The drainage ditch empties into a small wetlands area which directly recharges the aquifer in the vicinity of the two contaminated wells." Both the ROD and the maps received are not clear in distinguishing the various ditches across the site. The ROD statement was assumed to apply to the ditch south of the PRB which appears to flow to the east.  Clarifying the interaction between area surface water and groundwater may be a goal of a site conceptual model.
MH PRB Comment 5	PRB Specific Comment		5) Page 3, Section 2.2, pp 3; The authors state that at the ExCello site, that some impacts" remained in place near DMW1S, 2S, and 3S. This area should be defined and the impacts monitored.	Comment noted.
MH PRB Comment 6	PRB Specific Comment		6) Page 3, Section 2.2, pp 4; I would like to know how much water PRP-1 is pumping and at what rate in a $10^{-7}$ cm/sec formation. Does PRP-1 even pump water? If the MAROS software(s) used this hydraulic conductivity, then a sensitivity analysis should be performed or pneumatic slug testing of the existing site monitoring wells.	PRP-1 is approximately 400 ft W/SW of the Ex-Cello area. The PRP-1 area was not analyzed as part of the LTMO evaluation, and the authors do not have any details about this well. Hydraulic conductivity in this area may be different from the soil cell as the clay/till unit disappears to the east.  For the Ex-Cello/Soil Remedy area, seepage velocity was used as a qualitative metric of the propensity for the groundwater plume to expand. The combination of low groundwater velocity and decreasing to non-detect concentrations indicates the plume does not require an extensive monitoring effort. The authors do recommend further groundwater testing to delineate the groundwater quality north and east of the soil cell as described in

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
				Section 5.1 of the report.
MH PRB Comment 7	PRB Specific Comment		7) Page 5, Section 3.3; The statement is made that the "Dataset transmitted by Progressive was not complete...". This should be looked into. If the MAROS evaluation can be influenced by data that was omitted, that data should be provided and reevaluated. I would like to know why "data for vinyl chloride and tetrachloroethylene collected prior to 2005 were not included for most wells	This statement will be corrected. The data set for the PRB provides what appears to be a full set of data for PCE, TCE, cDCE and VC.  The soil remedy data set does not have results for PCE and VC prior to 2005 for many wells.  See Comment 1a on historic data.
MH PRB Comment 8	PRB Specific Comment		8) Page 6, Section 3.3, pp 3; The dynamics of the groundwater flow at the site should be evaluated and should include the entire range of groundwater directions that would result from seasonal variation.	Comment noted.
MH PRB Comment 9	PRB Specific Comment		9) Page 8, pp 3; The last sentence in this bullet indicates that surface water exposure pathway is not a concern. This should be discussed among the agencies. If this result influences the MAROS data evaluation, the site should be reevaluated.	The potential for groundwater to discharge to the ditch is of concern to the authors.  The LTMO analysis indicates that the southerly (inferred downgradient) extent of the VOC plume is not well defined.south of the PRBs.  Unless additional sample data are available for shallow groundwater and the groundwater/surface water interface, the LTMO evaluation will not change.
MH PRB Comment 10	PRB Specific Comment		10) Page 8, pp 4; The contamination in the intermediate and deeper portions of the aquifer should be defined and monitored.	Comment noted.
MH PRB Comment 11	PRB Specific Comment		11) Page 8, last paragraph; MNA is not part of the ROD remedy.	Comment noted. MNA was not considered as a remedial alternative in the ROD (1992). This will be edited.
MH PRB Comment 12	PRB Specific		12) Page 9, Section 4.2, bullet 3; I have to raise the question of how can one reliably estimate the center of mass if that mass has not been defined and is not monitored?	The center of mass is calculated only for the area covered by the wells. Mass outside of the well network is not considered.

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Commenter	Area	Page/Lin e/Para	Comment	Response
	Comment			
MH PRB Comment 13	PRB Specific Comment		13) Page 10, pp 2; This paragraph describes an order of magnitude change in concentration over the course of the past year yet earlier in this document the authors recommend that this well no longer be monitored due to its redundancy. This would seem to be a valuable well, why would we not monitor it?	<p>The authors state that well MW-305 “is recommended for <i>retention</i> in the monitoring program at a semiannual frequency”.</p> <p>The initial statistical evaluation found this well to be redundant because, over the length of the monitoring record, the concentration at MW-305 could be estimated from surrounding wells. Statistically, the well was not unique. However, the well was retained in the network after the qualitative evaluation (see Table 6) because of reasons laid out in Table 3.</p> <p>The preliminary frequency analysis indicated that MW-305 should be sampled Quarterly, because of the jump in concentration. However, after the qualitative evaluation the recommendation was made for semi-annual sampling.</p> <p>MW-305 is a good example of why all statistical evaluations should be reviewed qualitatively.</p>
MH PRB Comment 14	PRB Specific Comment		14) Page 10, Section 4.3, bullet 3; Once again, MNA is not part of the ROD remedy.	Comment noted. See response to MH PRB comment 2.
MH PRB Comment 15	Soil Remedy Specific Comment		15) Page 11, pp 3; Before the “risks to receptors” is evaluated, shouldn’t we define the limits of the groundwater and soil contamination?	Comment noted. Definition of extent of contamination is typically performed prior to completion of risk analysis.
MH PRB	Soil Remedy		16) Page 11, pp 4; As Parsons points out, the institutional controls should be evaluated in light of where contamination is and can potentially migrate	Comment noted.

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

<b>Commenter</b>	<b>Area</b>	<b>Page/Lin e/Para</b>	<b>Comment</b>	<b>Response</b>
Comment 16	Specific Comment		to.	
MH PRB Comment 17	Soil Remedy Specific Comment		17) Page 11, Last paragraph; This paragraph details a data gap in the current monitoring well network. This data gap should be filled with a VAS investigation and an appropriate monitoring well or two.	Comment noted.
MH PRB Comment 18	Soil Remedy Specific Comment		18) Page 12, pp 2; This paragraph correctly reiterates the need for additional characterization and some additional monitoring to demonstrate that the ExCello remedy is working effectively.	Comment noted.
MH PRB Comment 19	Soil Remedy Specific Comment		19) Page 12, pp 4; Hydraulic conductivity measurements in a distribution of site monitoring wells should be measured to resolve this data gap. I suggest pneumatic slug testing as it is fairly inexpensive and easy to perform.	Comment noted.
MH PRB Comment 20	Soil Remedy Specific Comment		20) Page 12, last paragraph; The statement is made that "this TCE detection does not appear to be of concern given the lack of nearby receptors." This should be looked at in light of the 10-year capture zone for the municipal well system, ARAR's, and the availability of adequate institutional controls.	A formal site conceptual model may be a good place to evaluate these issues.
MH PRB Comment 21	Soil Remedy Specific Comment		21) Page 13, pp 1; Perhaps the ExCello remedy needs to be reevaluated. Since water is being pumped from within the enclosure, even after years of operation, it may be that the cap, sidewalls or floor may be leaking. Is it time to sample the soil within the enclosure (I did not see any soil gas probes) to determine if the treatment objectives have been met? How do the soil/groundwater concentrations outside the cell compare to those media within the cell?	The authors do not have access to sampling data within the cell.

**RESPONSE TO MDEQ's COMMENTS ON  
THE DRAFT LONG-TERM GROUNDWATER MONITORING OPTIMIZATION  
CLARE WATER SUPPLY SUPERFUND SITE  
(Continued)**

Notes:

1. JS = Comment received from John Spielberg MDEQ
2. BV = Comment received from Barbara Vetorts MDEQ.
3. MH = Comment received from Mark Henry.
4. DNAPL References: Kavanaugh et al. (2003) The DNAPL Remediation Challenge: Is there a case for source depletion. USEPA EPA/600/R-03/143.
5. Bradley, P.M. and F.H. Chapelle, Effect of Contaminant Concentration on Aerobic Microbial Mineralization of DCE and VC in Stream-Bed Sediments. Environmental Science and Technology, 1998. **32**(5): p. 553-557.