
TE TETRA TECH

Implementation and Optimization of Air Sparge/Soil Vapor Extraction System with Horizontal and Vertical Wells – a case study

Tammy Rabideau, CPG Brandon Kinter, P.E. Lesa Sweet, CPG Daniel Sopoci, CHMM


Presentation Outline





Site History

- Active manufacturing facility
 1966 to present
- ▶ 180 acres
- 1.6 million square foot building and several outbuildings
- Multiple OUs and SWMUs
- Contaminants of concern
 - Chlorinated solvents
 - PNAs
 - Hydraulic oils/PCBs
 - VOCs
 - Heavy metals





Site History – Former UST Farm

Former UST Farm

- 16 USTs (730 to 15,000 gallons)
- Fuels, waste paints and solvents

➢History

- Previous activities removed a number of tanks
- Process utility lines not removed or abandoned
- Interim remedial actions
 - o Passive recovery
 - Vacuum enhanced recovery





Conceptual Site Model

Geology
Hydrogeology
Contaminant concentrations
Extent of impacts






Conceptual Site Model – Geology






Conceptual Site Model – Geology





Conceptual Site Model – *Hydrogeology*





Conceptual Site Model – Concentrations in Perched Water

Contaminant of Concern	Maximum Detected Concentration (μg/L)	Cleanup Standard (µg/L)
Acetone	11,000,000	2,100
Benzene	51	5
Cis-1,2-DCE	645	70
Ethylbenzene	7,900	74
MEK	5,200,000	38,000
MIBK	55,000	5,200
TCE	180	5
1,2,4-TMB	96	63
Toluene	410,000	790

Total Mass: ~17M ug/L



Conceptual Site Model – Concentrations in Soil


Contaminant of Concern	Maximum Detected Concentration (µg/Kg)	Cleanup Standard (µg/Kg)
Acetone	1,000,000	15,000
Benzene	130	100
Ethylbenzene	690,000	1,500
MEK	240,000	260,000
Methylene Chloride	150	100
PCE	190	100
1,2,4-TMB	2,000	2,100
Toluene	3,000,000	16,000

Total Mass: ~5M ug/Kg



Conceptual Site Model – Contaminant Extent in Perched Water and Soil

Lateral Extent soil impacts: ~0.42 acres Lateral extent of perched water impacts: ~1.1 acres





Selecting a Remedial Technology

- Completed a Corrective Action Matrix (CAM)
- Technologies evaluated against metrics
 - Threshold Criteria
 - Balancing Criteria

➢Other metrics

- Site end use
- Stakeholder's additional remedial objectives
- Identification and screening of remedial technologies
- Media specific corrective measures standards



Selecting a Remedial Technology

Remediation technologies evaluated

- Institutional Controls
- Containment
- Removal and Offsite Disposal and/or Alternate Discharge
- Ex-Situ Treatment
- In-Situ Treatment



Selecting a Remedial Technology – Corrective Action Matrix Results

Soil

- SVE
- Excavation with offsite disposal*
- Perched Water
 - Extraction with onsite treatment and POTW discharge
 - Extraction with onsite treatment and NPDES discharge
 - Air Sparge
 - Bioremediation
 - Chemical oxidation
- Interim Measures* vs. Pilot Testing





Interim Measures and Pilot Tests

Interim Measures


- Source excavation*
 - o Excavation of tanks, soil and dewatering
 - o Installed perched water recovery trench
 - o Abandoned tank in place (under building)
- Vacuum enhanced recovery

➢Pilot Tests

ISCO desktop study for perched water
 Data was not supportive of full scale
 Access to plant floor was limited



Interim Measures – Source Removal





Interim Measures – Utility Relocation





Implementation Challenges

Active manufacturing plant

- Interior multiple obstacles
- Exterior truck parking, traffic
- Multiple stakeholders
- Security issues
- Plant projects
 - Scheduling
 - plant re-configuration and construction projects
 - Utility relocation and re-installation (water, gas, fire line, electric)

Existing above and below grade infrastructure



Results of Pilot Testing and Selection of Remedial Technology

- Combined Remedial Technology Selected
 - SVE/AS using Horizontal Wells
 - SVE/AS data indicated good zone of influence

Remedial Technology Not Selected

- Groundwater extraction with onsite treatment and POTW discharge
- Groundwater extraction with onsite treatment and NPDES discharge
- Bioremediation



Full Scale Implementation Horizontal Well Installation





Full Scale Implementation Horizontal Well Installation

SVE Horizontal Well - April 2010 •150' total length o 130' of 3" 304SS screen 64 slots/foot (0.012" x 1.5") o 20' of 3" SS casing ~7' below plant floor (final elevation) AS Horizontal Well – November 2010 130' total length o 60' 4" SS screen 80 slots/foot (0.012" x 1.5") o 70' 4" SS casing

o ~18' below plant floor (final elevation)



Full Scale Implementation – *SVE/AS*


System Details

- Roots Rotary Blowers
 - SVE max extraction rate 450 cfm with typical operation rate at 350 cfm
 - AS max flow rate 150 cfm with typical operation rate at 30 cfm
- 80 gallon internal KO tank
- 300 gallon external KO tank
- 3 carbon vessels used in series





Radius of Influence SVE/AS with Horizontal Wells



Full Scale Implementation – *SVE/AS*

Installation of vertical SVE wells in January 2012


- 3 interior vertical SVE wells
- 2 exterior vertical SVE wells

Interior plant reconfiguration


- Required 4 changes to interior SVE vertical wells
- System down time




Radius of Influence SVE/AS with Horizontal and Vertical Wells



Results – SVE/AS with Horizontal Wells




Results – SVE/AS with Horizontal Wells






Groundwater Results -SVE/AS with Horizontal Wells






Groundwater Results -SVE/AS with Horizontal Wells



Contaminant Extent in Perched Water and Soil

► Lateral Extent soil impacts: ~0.44 acres

Lateral extent of perched water impacts: ~0.41 acres (63% decrease)





Conclusions

- Remedial activities were completed in conjunction with multiple Plant projects
- Above ground infrastructure installed during periods of Plant shutdown
- Installation of horizontal wells
 - Competent drilling firm
 - Accurate location of well during drilling
 - Threading the needle during installation
 - Proper well development
- Operation and Maintenance of system in winter
 - Generating a larger volume of condensate
 - Carbon vessel hoses froze
 - Heated cargo container to house the carbon vessels



Before and After



Thank You



